(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
20 September 2001 (20.09.2001)

PCT

(10) International Publication Number
WO 01/68867 A1

(51) International Patent Classification[7]: C12N 15/52, 15/76, C12P 17/18, 19/44, 19/62, C12Q 1/68, C07H 17/08, 19/01

(21) International Application Number: PCT/GB00/02072

(22) International Filing Date: 30 May 2000 (30.05.2000)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
9912563.5 28 May 1999 (28.05.1999) GB

(71) Applicant *(for all designated States except US)*: **BIOTICA TECHNOLOGY LIMITED** [GB/GB]; 181A Huntingdon Road, Cambridge CB3 0DJ (GB).

(72) Inventors; and

(75) Inventors/Applicants *(for US only)*: **LEADLAY, Peter, Francis** [GB/GB]; 17 Clarendon Road, Cambridge CB2 2BH (GB). **STAUNTON, James** [GB/GB]; 29 Porson Road, Cambridge CB2 2ET (GB). **OLIYNYK, Marko** [UA/GB]; Cambridge University, Department of Biochemistry, Tennis Court Road, Cambridge CB2 1QW (GB).

(74) Agents: **STUART, Ian** et al.; Mewburn Ellis, York House, 23 Kingsway, London WC2B 6HP (GB).


(81) Designated States *(national)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States *(regional)*: ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

Published:
— *with international search report*

[Continued on next page]

(54) Title: POLYKETIDES AND THEIR SYNTHESIS



monensin A : R = ethyl
monensin B : R = methyl

(57) Abstract: The complete sequence of the gene cluster for the monensin type I polyketide synthase, from *S. cinnamonensis*, is provided. Thus variant polyketides containing monensin-derived elements can be genetically engineered. Furthermore there are features, e.g. a regulatory protein *mon RI*, which are of wide utility.

WO 01/68867 A1

— *with (an) indication(s) in relation to deposited biological material furnished under Rule 13bis separately from the description*

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

POLYKETIDES AND THEIR SYNTHESIS

The present invention relates to processes and materials (including enzyme systems, nucleic acids, vectors and cultures) for preparing polyketides, particularly polyethers but including polyenes, macrolides and other polyketides by recombinant synthesis, and to the polyketides so produced, particularly novel polyketides. (N.B the term "polyketide" is being used in its conventional sense to include structures notionally derived by the reduction and/or other processing or modification of one or more Ketide units). Furthermore the invention provides the entire nucleic acid sequence of the biosynthetic gene cluster that governs the production of the ionophoric antibiotic polyether polyketide monensin in *Streptomyces cinnamonensis*, and the use of all or part of the cloned DNA first, in the specific detection of other polyether biosynthetic gene clusters; secondly in the engineering of mutant strains of *S. cinnamonensis* and of other actinomycetes which are suitable host strains for the high level production of novel recombinant polyketides; and thirdly in the provision of recombinant biosynthetic genes which lead to such novel polyketide products.

Polyketides are a large and structurally diverse

class of natural products that includes many compounds possessing antibiotic or other pharmacological properties, such as erythromycin, tetracyclines, rapamycin, avermectin, monensin, epothilones and FK506. In particular, polyketides are abundantly produced by *Streptomyces* and related actinomycete bacteria. They are synthesised by the repeated stepwise condensation of acylthioesters in a manner analogous to that of fatty acid biosynthesis. The greater structural diversity found among natural polyketides arises from the selection of (usually) acetate or propionate as "starter" or "extender" units; and from the differing degree of processing of the β-keto group observed after each condensation. Examples of processing steps include reduction to β-hydroxyacyl-, reduction followed by dehydration to 2-enoyl-, and complete reduction to the saturated acylthioester. The stereochemical outcome of these processing steps is also specified for each cycle of chain extension. In addition, the biosynthetic pathways to many polyketides involve additional enzyme-catalysed modifications which may include: methylation by O- and C-methyltransferases, hydroxylation by cytochrome P450 enzymes, other oxidation or reduction processes, and the biosynthesis and attachment of novel sugars and/or deoxy sugars.

The biosynthesis of polyketides is initiated by a group of chain-forming enzymes known as polyketide synthases. Two classes of polyketide synthase (PKS) have been described in actinomycetes. One class, named Type I PKSs, represented by the PKSs for the macrolides erythromycin, oleandomycin, avermectin and rapamycin, consists of a different set or "module" of enzymes for each cycle of polyketide chain extension. (For examples see Cortés, J. *et al.* Nature (1990) 348:176-178; Donadio, S. *et al.* Science (1991) 252:675-679; Swan, D.G. *et al.* Mol. Gen. Genet. (1994) 242:358-362; MacNeil, D.J. *et al.* Gene (1992) 115:119-125; Schwecke, T. *et al.* Proc. Natl. Acad. Sci. USA (1995) 92:7839-7843.)

The term "extension module" as used herein refers to the set of contiguous domains, from a β-ketoacyl-ACP synthase ("KS") domain to the next acyl carrier protein ("ACP") domain, which accomplishes one cycle of polyketide chain extension. The term "loading module" is used to refer to any group of contiguous domains which accomplishes the loading of the starter unit onto the PKS and thus renders it available to the KS domain of the first extension module. The length of polyketide formed has been altered, in the case of erythromycin biosynthesis, by specific relocation using genetic engineering of the enzymatic domain of the erythromycin-

producing PKS that contains the chain releasing thioesterase/cyclase activity (Cortés J. *et al.* Science (1995) 268:1487-1489; Kao, C.M. *et al.* J. Am. Chem. Soc. (1995) 117:9105-9106).

In-frame deletion of the DNA encoding part of the ketoreductase domain in module 5 of the erythromycin-producing PKS (also known as 6-deoxyerythronolide B synthase, DEBS) has been shown to lead to the formation of erythromycin analogues 5,6-dideoxy-3-α-mycarosyl-5-oxoerythronolide B, 5,6-dideoxy-5-oxoerythronolide B and 5,6-dideoxy,6-β-epoxy-5-oxoerythronolide B (Donadio, S. *et al.* Science (1991) 252:675-679). Likewise, alteration of active site residues in the enoylreductase domain of module 4 in DEBS, by genetic engineering of the corresponding PKS-encoding DNA and its introduction into *Saccharopolyspora erythraea*, led to the production of 6,7-anhydroerythromycin C (Donadio, S. *et al.* Proc. Natl. Acad. Sci. USA (1993) 90:7119-7123).

International Patent Application number WO 93/13663 describes additional types of genetic manipulation of the DEBS genes that are capable of producing altered polyketides. However many such attempts are reported to have been unproductive (Hutchinson, C.R. and Fujii, I. Annu. Rev. Microbiol. (1995) 49:201-238, at p. 231). The complete DNA sequence of the genes from *Streptomyces*

hygroscopicus that encode the modular Type I PKS governing the biosynthesis of the macrocyclic immunosuppressant polyketide rapamycin has been disclosed (Schwecke, T. *et al.* (1995) Proc. Natl. Acad. Sci. USA 92:7839-7843). The DNA sequence is deposited in the EMBL/Genbank Database under the accession number X86780.

WO 98/01546 discloses that a PKS gene assembly (particularly of Type I) encodes a loading module which is followed by at least one extension module. The first open reading frame encodes the first multi-enzyme or cassette (DEBS1) which consists of three modules: the loading module (ery-load) and two extension modules (modules 1 and 2). The loading module comprises an acyltransferase and an acyl carrier protein. This may be contrasted with Figure 1 of WO 93/13663 (referred to above). This shows ORF1 as only two modules, the first of which is in fact both the loading module and the first extension module.

WO 98/01546 describes in general terms the production of a hybrid PKS gene assembly comprising a loading module and at least one extension module. It also describes (see also Marsden, A.F.A. *et al.* Science (1998) 279:199-202) construction of a hybrid PKS gene assembly by grafting the wide-specificity loading module for the avermectin-producing polyketide synthase onto the first

multi-enzyme component (DEBS1) for the erythromycin PKS in place of the normal loading module. Certain novel polyketides can be prepared using the hybrid PKS gene assembly, as described for example in WO 98/01571.

WO 98/01546 further describes the construction of a hybrid PKS gene assembly by grafting the loading module for the rapamycin-producing polyketide synthase onto the first multi-enzyme component (DEBS1) for the erythromycin PKS in place of the normal loading module. The loading module of the rapamycin PKS differs from the loading modules of DEBS and the avermectin PKS in that it comprises a CoA ligase domain, an enoylreductase ("ER") domain and an ACP, so that suitable organic acids including the natural starter unit 3,4-dihydroxycyclohexane carboxylic acid may be activated *in situ* on the PKS loading domain and, with or without reduction by the ER domain, transferred to the ACP for intramolecular loading of the KS of extension module 1 (Schwecke, T. *et al.* Proc. Natl. Acad. Sci. USA (1995) 92:7839-7843). WO 98/51695 and WO 98/49315 describe additional types of genetic manipulation of the DEBS genes that are capable of producing altered polyketides.

The second class of PKS, named Type II PKSs, is represented by the synthases for aromatic compounds. Type II PKSs contain only a single set of enzymatic activities

for chain extension and these are re-used as appropriate in successive cycles (Bibb, M.J. *et al.* EMBO J. (1989) 8:2727-2736; Sherman, D.H. *et al.* EMBO J. (1989) 8:2717-2725; Fernandez-Moreno, M.A. *et al.* J. Biol. Chem. (1992) 267:19278-19290). The "extender" units for the Type II PKSs are usually acetate units, and the presence of specific cyclases dictates the preferred pathway for cyclisation of the completed chain into an aromatic product (Hutchinson, C.R. and Fujii, I. Ann. Rev. Microbiol. (1995) 49:201-238). Hybrid polyketides have been obtained by the introduction of cloned Type II PKS gene-containing DNA into another strain containing a different Type II PKS gene cluster, for example by introduction of DNA derived from the gene cluster for actinorhodin, a blue-pigmented polyketide from *Streptomyces coelicolor*, into an anthraquinone polyketide-producing strain of *Streptomyces galileus* (Bartel, P.L. *et al.* J. Bacteriol. (1990) 172:4816-4826).

The minimal number of domains required for polyketide chain extension on a Type II PKS when expressed in a *Streptomyces coelicolor* host cell (the "minimal PKS") has been defined for example in WO 95/08548 as containing the following three polypeptides which are products of the *actI* genes: firstly KS; secondly a polypeptide termed the CLF with end-to-end

amino acid sequence similarity to the KS but in which the essential active site residue of the KS, namely a cysteine residue, is substituted either by a glutamine residue or, in the case of the PKS for a spore pigment such as the *whiE* gene product (Davis, N.K. and Chater, K.F. Mol. Microbiol. (1990) 4:1679-1691) by a glutamic acid residue; and finally an ACP. The CLF has been stated (for example in WO 95/08548) to be a factor that determines the chain length of the polyketide chain that is produced by the minimal PKS. However it has been found (Shen, B. *et al.* J. Am. Chem. Soc. (1995) 117:6811-6821) that when the CLF for the octaketide actinorhodin is used to replace the CLF for the decaketide tetracenomycin in host cells of *Streptomyces glaucescens*, the polyketide product is not found to be altered from a decaketide to an octaketide, so the exact role of the CLF remains unclear. An alternative nomenclature has been proposed in which KS is designated KSα and CLF is designated KSβ, to reflect this lack of knowledge (Meurer, G. *et al.* Chemistry & Biology (1997) 4:433-443). The mechanism by which acetate starter units and acetate extender units are loaded onto the Type II PKS is not known, but it is speculated that the malonyl-CoA: ACP acyltransferase of the fatty acid synthase of the host cell can fulfil the same function for the Type II PKS (Revill, W.P. *et al.* J.

Bacteriol. (1995) 177:3946-3952).

WO 95/08548 describes the replacement of actinorhodin PKS genes by heterologous DNA from other Type II PKS gene clusters, to obtain hybrid polyketides. It also describes the construction of a strain of *Streptomyces coelicolor* which substantially lacks the native gene cluster for actinorhodin, and the use in that strain of a plasmid vector pRM5 derived from the low-copy number vector SCP2* isolated from *Streptomyces coelicolor* (Bibb, M.J. and Hopwood, D.A. J. Gen. Microbiol. (1981) 126:427-442) and in which heterologous PKS-encoding DNA may be expressed under the control of the divergent *actI/ actIII* promoter region of the actinorhodin gene cluster (Fernandez-Moreno, M.A. *et al.* J. Biol. Chem. (1992) 267:19278-19290). The plasmid pRM5 also contains DNA from the actinorhodin biosynthetic gene cluster encoding the gene for a specific activator protein, ActII-orf4. The ActII-orf4 protein is required for transcription of the genes placed under the control of the *actI/actIII* bidirectional promoter and activates gene expression during the transition from growth to stationary phase in the vegetative mycelium (Hallam, S.E. *et al.* Gene (1988) 74:305-320).

Type II clusters in *Streptomyces* are known to be activated by pathway-specific activator genes (Narva,

K.E. and Feitelson, J.S. J. Bacteriol. (1990) 172:326-333; Stutzman-Engwall, K.J. *et al.* J. Bacteriol. (1992) 174:144-154; Fernandez-Moreno, M.A. *et al.* Cell (1991) 66:769-780; Takano, E. *et al.* Mol. Microbiol. (1992) 6:2797-2804; Gramajo, H.C. *et al.* Mol. Microbiol. (1993) 7:837-845). The DnrI gene product complements a mutation in the *actII*-orf4 gene of *S. coelicolor*, implying that DnrI and ActII-orf4 proteins act on similar targets. A gene (*srmR*) has been described (EP 0 524 832 A2) that is located near the Type I PKS gene cluster for the macrolide polyketide spiramycin. This gene specifically activates the production of the macrolide antibiotic spiramycin, but no other examples have been found of such a gene. Also, no homologues of the ActII-orf4/DnrI/RedD family of activators have been described that act on Type I PKS genes. WO 98/01546 describes the use of the ActII-orf4 family of activators in conjunction with their cognate promoters (e.g actII-orf4 with the *actI* promoter) in a heterologous actinomycete to obtain high level expression of recombinant Type I polyketide synthase genes.

Although large numbers of therapeutically important polyketides have been identified, there remains a need to obtain novel polyketides that have enhanced properties or possess completely novel bioactivity. The complex

polyketides produced by Type I PKSs are particularly valuable, in that they include compounds with known utility as anthelminthics, insecticides, immunosuppressants, antifungal agents or antibacterial agents. Because of their structural complexity, such novel polyketides are not readily obtainable by total chemical synthesis, nor by chemical modifications of known polyketides.

There is also a need to develop reliable and specific ways of deploying individual genes and portions of genes in practice so that all, or a large fraction, of hybrid PKS genes that are constructed, are viable and produce the desired polyketide product. This includes the development of advantageous host strains for expression of such genes. For example many polyketides are rendered bioactive by the action of further enzymes other than the polyketide synthase, and host strains that contain and are able to express the genes for such enzymes are particularly convenient for the efficient synthesis of the bioactive material. In those cases where the construction of a known or a novel polyketide requires specialised precursors, host strains containing and able to express the genes for key enzymes that enhance the production of such specialised precursors are equally valuable and desirable. There is also a need to develop

rational methods of increasing the expression level of all the genes required for production of a specific polyketide. Clearly also a host cell which is advantageous for the above reasons, and/or because of other favourable characteristics including but not limited to its speed of growth, excellent handling characteristics in fermentation, and ease of transformation with DNA by various techniques, can be made even more favourable by the cloning into that cell of such auxiliary genes for polyketide modification, or gene activation, or post-translational modification, or precursor supply.

The DNA sequences have been disclosed for several Type I PKS gene clusters that govern the production of 16-membered macrolide polyketides, including the tylosin PKS from *Streptomyces fradiae* (application EP 0 791 655 A2), the niddamycin PKS from *Streptomyces caelestis* (Kavakas, S.J. *et al.* J. Bacteriol. (1997) 179:7515-7522) and the spiramycin PKS from *Streptomyces ambofaciens* (application EP 0791 655 A2). DNA sequences have also been disclosed for Type I PKS gene clusters that govern the production of further complex polyketides, for example rifamycin from *Amycolatopsis mediterranei* (WO 98/07868), and soraphen from *Sorangium cellulosum* (US

5716849), but so far no DNA sequence has been disclosed for one of the most widespread and important classes of complex polyketides, the polyethers.

Polyethers form an important group of complex polyketide antibiotics (Westley, J.W. in "Antibiotics IV. Biosynthesis" (Corcoran, J.W. Ed.), Springer-Verlag, New York (1981) p. 41-73). They are polyoxygenated carboxylic acids which act as selective ionophores transporting cations across the cell membrane of target cells and thereby causing depolarisation and cell death. Certain polyethers including monensin, lasalocid and tetronasin are in widespread use in animal husbandry as coccidiostats (principally targetted against *Eimeria spp.*) and as growth promoters. Polyethers have also been reported to be active *in vitro* and *in vivo* against the malarial parasite *Plasmodium falciparum* (Gumila, C. *et al.* Antimicrobial Agents and Chemotherapy (1997) 41: 523-529).

Polyethers contain multiple asymmetric centres and are characterised by the presence of tetrahydrofuran and tetrahydropyran rings, producing a characteristic shape which is non-polar on its outer surface and therefore well adapted for transport of material across bacterial membranes; and provides on its inner surface polar coordinating ligands for a centrally-bound metal ion. In

addition to tetrahydrofuran and tetrahydropyran rings, other groups which are often present include spiroketal, dispiroketal, and substituted benzoic acid moieties and occasionally other groups for example a tetronic acid or a 6-membered carbocyclic ring

Monensins A and B are produced by the actinomycete *Streptomyces cinnamonensis*. Their structures are shown in Figure 1. Monensin B differs from monensin A only in the presence of a methyl sidechain at C-16 rather than an ethyl sidechain. Monensin selectively binds and transports sodium ions. In addition to its antibacterial and antifungal properties monensin has some activity against protozoal parasites such as the malarial parasite *Plasmodium falciparum*. Although the structures of polyethers differ significantly from those of other complex polyketides such as the polyhydroxylated and polyene macrolides, their biosynthesis appears to take place by a metabolic pathway which has many common elements. Thus experiments using carbon 14-labelled precursors have shown that monensin A is synthesised from five acetate, one butyrate and seven propionate units (Day, L.E. *et al.* Antimicrob. Agents Chemother. (1973) 4:410-414). Similarly experiments using precursors doubly-labelled with carbon-13 and oxygen-18 have shown that oxygens (O)1, (O)3, (O)4, (O)5, (O)6 and (O)10 of

monensin arise from the carboxylate oxygens of either propionate or acetate, while growth in the presence of oxygen-18 oxygen gas demonstrated that the three remaining ether oxygens (O)7, (O)8 and (O)9 are derived from molecular oxygen (Cane, D.E. *et al.*, J. Am. Chem. Soc. (1981) 103:5962-5965; Cane, D.E. *et al.* J. Am. Chem. Soc. (1982) 104:7274 - 7281; Ajaz, A.A. and Robinson, J.A. J. Chem. Soc. Chem. Commun. (1983) 12:679-680). These findings have been rationalised by proposing that the biosynthesis of monensin proceeds via an acyclic triene intermediate (1) in which the geometry of all three carbon-carbon double bonds is E (entgegen) rather than Z (zusammen). The triene is then proposed to be subject to epoxidation to a tri-epoxide (2) and then ring opening is proposed to occur with concomitant sequential formation of the five ether rings as shown in Figure 2A. Such a biosynthetic pathway, first mooted by Westley in 1974 (Westley J.W. *et al.*, J. Antibiot. (1974) 27:597-604) accounts for the observed stereochemistry at the multiple asymmetric centres in monensin, (Cane, D.E. *et al.* J. Am. Chem. Soc. (1982) 104:7274-7281; Sood, G.R. *et al.* J. Chem. Soc. Chem. Commun. (1984) 21:1421-1424) and analogous schemes can be used to account for the biosynthesis of other known polyethers. such as lasalocid A (Hutchinson C.R. *et al.*, J. Am. Chem. Soc. (1981)

103:5953-5956), tetronasin (ICI 139603) (Demetriadou, A.K. *et al.* J. Chem. Soc. Chem. Commun. (1985) 7:408-410) and narasin (Spavold, Z. *et al.* Tetrahedron Letters (1986) 27:3299-3302). The hydroxylation at C-26 and the introduction of an O-methyl group on oxygen 3-are proposed to occur as late steps in the biosynthesis, after formation of the polyether structure.

Unfortunately key aspects of the biosynthetic scheme shown in Figure 2A have so far eluded experimental confirmation. No biosynthetic intermediates have been isolated from mutants of *S. cinnamonensis* that are blocked in early stages of monensin production. 26-deoxymonensin A has been isolated from a *S. cinnamonensis* mutant partially blocked in monensin production (Ashworth, D.M. *et al.* J. Antibiot. (1989) 42:1088-1099) and 3-0-demethylmonensins A and B have been recovered as minor components from the fermentation broth of a monensin-producing strain (Pospisil, S. *et al.* J. Antibiot. (1987) 40:555-557). When fed to cells of *S. cinnamonensis* in radio-labelled form, neither 26-deoxymonensin A, nor 3-0-demethylmonensin A, nor 3-0-demethyl, 26-deoxymonensin A were significantly incorporated into monensin A (Ashworth, D.M. *et al.* J. Antibiot. (1989) 42:1088-1099), either because they are actively excluded or because these modifications in fact

occur earlier in the biosynthetic pathway so that these metabolites are shunt products not readily converted into the final antibiotic by the respective hydroxylase or methyltransferase. Similarly, the putative all (E)-triene precursor (1) has been synthesised and shown not to become incorporated into monensin when fed to growing cells of *S. cinnamonensis* (Holmes, D.S. *et al.* Helv. Chim. Acta (1990) 73:239-259). An alternative pathway has been proposed, as shown in Fig 2B, based on the transition-metal-mediated oxidation of 1,5-dienes (Walba, D.M. and Edwards, P.D. Tetrahedron Lett. (1980) 21:3531-3534). The triene intermediate (4) would different from that of Figure 2A (1) only in that each carbon-carbon double bond would have the (Z)-configuration (Townsend, C.A. and Basak, A. Tetrahedron (1991) 47:2591-2602) and not the (E)- configuration.

The genetic basis of secondary metabolite biosynthesis essentially exists in the genes which code for the individual biosynthetic enzymes and in the regulatory elements which control the expression of the biosynthetic genes. The genes encoding biosynthesis of polyketides in actinomycetes have hitherto been found as clusters of adjacent genes, ranging in size from 20 kilobasepairs (kbp) to over 100 kbp. The clusters often contain specific regulatory genes and genes

conferring resistance of the producing strain to its own antibiotic.

In various of its aspects the invention provides the following:-

(1) a DNA sequence encoding at least one-peptide necessary for the biosynthesis of monensin, preferably comprising one or more of the following genes: *mon BI, mon BII, mon CI, mon CII, mon H, mon RI, mon RII, mon T, mon AIX* and *mon AX* as depicted in the appended sequence data or an allele or mutation thereof;

(2) a DNA sequence according to the first aspect comprising all of the genes listed therein or an allele or mutation thereof;

(3) a DNA sequence according to the first aspect comprising the complete monensin gene cluster;

(4) a DNA sequence coding for one or more of the peptides set out below, said peptide having the amino acid sequence as set out in the appended sequence data or being a variant thereof having the specified activity:

peptide	activity
mon CII	epoxyhydrolase/cyclase
mon E	S-adenosylmethionine-dependent methyltransferase
mon T	monensin resistance gene
mon RII	repressor protein
mon AIX	thioesterase

mon AI	polyketide synthase multienzyme
mon AII	polyketide synthase multienzyme
mon AIII	polyketide synthase multienzyme
mon AIV	polyketide synthase multienzyme
mon AVI	polyketide synthase multienzyme
mon AVII	polyketide synthase multienzyme
mon AVIII	polyketide synthase multienzyme
mon H	regulatory protein
mon CI	flavin-dependent epoxidase
mon BII	carbon-carbon double bond isomerase
mon BI	carbon-carbon double bond isomerase
mon D	cytochrome P450 hydroxylase
mon RI	activator protein
mon AX	thioesterase

(5) a recombinant cloning or expression vector comprising a DNA sequence according to any of aspects 1-4;

(6) a transformant host cell which has been transformed to contain a DNA sequence according to any of aspects 1-4 and is capable of expressing a corresponding peptide;

(7) a hybridization probe comprising a polynucleotide which binds specifically to a region of the monensin gene cluster selected from *mon BI, mon BII, mon CI, mon CII, mon H, mon RI, mon RII, mon T, mon AIX* and *mon AX;*

(8) use of a probe according to aspect (7) in a method of detecting the presence of a gene cluster which governs the synthesis of a polyether, and optionally isolating a gene cluster detected thereby;

(9) Use of a probe comprising a polynucleotide which binds specifically to a gene responsible for levels of activity of the monensin gene cluster, preferably a regulatory gene, resistance gene or thioesterase gene, more preferably the regulatory gene *mon RI*, in a method of detecting an analogous gene in a gene cluster of another polyketide, preferably a polyether, and optionally manipulating the gene detected thereby to alter the level of expression of said other polyketide;

(10) a host cell, preferably *Streptomyces cinnamonensis*, containing a heterologous gene under the control of the *mon RI* gene and a monensin promoter;

(11) use of a portion of the monensin gene cluster having chain terminating activity, preferably comprising at least one of *mon AIX* and *mon AX* or a mutant or allele thereof having chain terminating activity, to effect chain release of a peptide other than one required for monensin biosynthesis;

(12) use of a portion of the monensin gene cluster having carbon-carbon double bond isomerase activity, preferably comprising at least one of *mon BI* and *mon BII*

or a mutant or allele thereof having isomerase activity to provide a desired stereochemical outcome in the synthesis of a polyketide other than monensin;

(13) a polypeptide encoded by a portion of the monensin gene cluster, preferably comprising at least one of *mon BI* and *mon BII* or a mutant or allele thereof, having carbon-carbon double bond isomerase activity;

(14) an epoxidase enzyme encoded by *mon CI* or a derivative or variant thereof having epoxidase activity;

(15) a cyclase enzyme encoded by *mon CII* or a derivative or variant thereof having cyclase activity.

Some embodiments of the invention will now be described by way of example with reference to the accompanying drawings in which:

Fig 1 shows the structure of monensins A and B;

Fig 2 illustrates proposed biosynthetic pathways;

Fig 3 illustrates the proposed organization of the monensin polyketide synthase (PKS) enzyme complex; and

Fig 4 illustrates the proposed organization of the monensin biosynthetic gene cluster.

The overall gene organization of the monensin biosynthetic gene cluster, as shown in Fig 4, is similar to that previously found for many macrolide biosynthetic gene clusters, which have one or more open reading frames (ORFs) encoding large multifunctional PKSs flanked by

other genes which encode functions required for the biosynthesis of the antibiotic. In the case of monensin, there is an unusually high number of distinct ORFs encoding PKS multi-enzymes (eight in total, labelled *monAI* to *monAVIII*) but there is again a separate module of enzymes for each cycle of polyketide chain extension, exactly as found for modular PKSs for macrolide biosynthesis (see Fig 3). Thus there are 12 condensations predicted to be required for the production of the carbon skeleton of monensin, and in agreement with this there are found to be 12 extension modules of PKS enzymes distributed among the 8 PKS ORFs. However, as mentioned in detail below, the other genes in the monensin cluster include genes which have not previously been found in any other gene cluster for the biosynthesis of a complex polyketide, and which are not significantly similar to any genes in published sequence databases. The cloned DNA for these genes is useful to allow the diagnosis that a polyketide biosynthetic gene cluster in any actinomycete, uncovered previously by conventional hybridization against a PKS gene probe from (say) the DEBS or some other characterised PKS gene cluster, is one that governs the synthesis of a polyether; and these genes are also valuable either singly or in combination as specific hybridization probes for the specific detection and

isolation of additional polyether biosynthetic gene clusters. Examples of these previously-unknown genes are the genes *monBI*, *monBII*, *monCI* and *monCII*. In addition the regulatory genes *monH monRI*, and *monRII* and the resistance gene *monT* and the thioesterase genes *monAIX* and *monAX* are all useful for the detection of analogous genes in other polyether clusters which are required for the rational manipulation of such genes in order to increase levels of the specific product.

The cloned and sequenced cluster of genes for *monensin biosynthesis* is useful secondly in the engineering of mutant strains of *S. cinnamonensis* and of other actinomycetes which are suitable strains for the high level production of either natural or novel recombinant polyketides. The sequence of the monensin cluster disclosed here shows the surprising fact, that the gene cluster contains a gene *monRI* whose gene product has an amino acid sequence highly similar to that of *actII*-orf4, the pathway-specific activator gene which activates the *actI* and other promoters of the actinorhodin biosynthetic gene cluster of *Streptomyces coelicolor*. The recognition of this aspect of the natural regulation of a Type I PKS cluster is important and valuable because first, it is possible to increase the yield of monensin by increasing the level of the activator MonRI, either by

placing the gene *monRI* under the control of a powerful promoter or arranging for the presence within the cells of one or more additional copies of the *monRI* gene (as exemplified below); secondly, it will be possible to use the *monRI* gene as a specific hybridisation probe to locate similar genes in other complex PKS gene clusters, especially other polyether PKS gene clusters but also polyene and macrolide gene clusters and all other Type I modular PKS gene clusters; even in cases where (as for rapamycin and erythromycin) no such gene has been previously found within the currently accepted physical limits of the relevant biosynthetic gene cluster. In such cases the *monRI* gene probe might be expected to uncover the activator even if it resides on the chromosome at some distance from the main body of the gene cluster; and simple experiments would then show whether the activator(s) so uncovered are involved in regulation of the biosynthesis of those particular metabolites; thirdly, increasing the copy number of the *monRI* gene or of any of the activator genes uncovered will tend to increase the yield of a heterologous polyketide by "crosstalk" where the activator mimics the presence of the normal activator for the transcription of the genes for that heterologous polyketide synthase. It is clear from recently published work (Wietzorrek, A. and Bibb, M. Mol. Microbiol. (1997)

25:1181-1184) that the ActII-orf4 family of activators exert their effects by binding to promoter regions within the target gene cluster, so it will be possible to use the *monRI* gene together with monensin promoter regions to drive the high-level transcription and translation of heterologous genes in *Streptomyces cinnamonensis*, and perhaps in other host strains too; such genes need not be PKS genes or even involved in polyketide biosynthesis. Monensin promoter regions are found at the 5′ end of genes or groups of genes in the cluster and their location is clear from the sequence analysis disclosed here. Thus a useful vector would provide the monensin promoter and the ribosome binding site and continue up to the start of the open reading frame, after which the monensin ORF naturally found there would be replaced by the heterologous gene. The relative strength of the monensin promoters can be readily determined using any one of a number of known promoter probes, i.e. genes whose expression gives rise to readily measurable and quantifiable effects, such as Green Fluorescent Protein (GFP); or beta-galactosidase in the presence of a chromogenic substrate. It should be possible to mutate randomly the small region of the monensin promoters especially likely to interact with the MonRI activator (identified by the presence of tandem heptanucleotide repeats with a common consensus sequence

between the various monensin promoters) (Wietzorrek, A. and Bibb, M. Mol. Microbiol. (1997) 25:1181-1184), and to determine the optimal DNA sequence for the maximal activation effect using either *S. cinnamonensis* (preferably - in case there are other unknown factors that make the activation function better in this strain than in other heterologous systems), or even in another host actinomycete strain. If the natural monensin promoters were mutated to have this optimal recognition sequence, then this would further increase the production of monensin. By extension, the use of this modified monensin promoter in conjunction with the *monRI* gene in heterologous systems could form the basis of further improvements in expression of polyketide synthases or other genes, either by appropriate chromosomal alterations to introduce the altered promoter and also the *monRI* gene; or by provision of vectors containing these optimised signals linked to specific genes and housed in suitable host cells.

The sequencing of the monensin cluster has uncovered another strategy for gene regulation in such Type I clusters. The previously-sequenced genes for the rapamycin biosynthetic pathway in *Streptomyces hygroscopicus* included a gene of unknown function (*rapH*). A closely similar gene has now been found in the monensin

biosynthetic gene cluster (*monH*), and it is clear from this recurrence (and the comparison of the sequences with those of database proteins) that this gene is potentially an important DNA-binding sensor gene which acts to regulate the transcription of the cluster in concert with other regulatory signals. Simple experimentation is needed in order to define whether the gene is an activator, in which case putting in another copy or increasing its transcription will have the potential to increase polyketide biosynthesis; or alternatively the *rapH* gene product may be a negative regulator, whereupon deletion of this gene may release the biosynthetic pathway from this inhibitory effect and increase yields.

There is a continuing need to develop new methods of high-level production of bioactive metabolites and other valuable gene products in actinomycetes. *Streptomyces cinnamonensis* is a recognised and very valuable industrial strain for the production of very high levels of monensin, it is readily transformable with DNA by standard methods of conjugation or of protoplast transformation, it is a host for numerous known broad range plasmids including well-known expression plasmids of both high- and low-copy number, it also grows quickly relative to other actinomycete strains (for example about three times faster than wild type *Saccharopolyspora erythraea* the

erythromycin producer, under comparable conditions) and sporulates relatively easily. Heterologous polyketides can be expressed in *Streptomyces cinnamonensis* using for example the low-copy number plasmid pCJR24 (which has no origin of replication active in actinomycetes so is maintained by integration into the chromosome) (Rowe, C. *et al.* Gene (1998) 216:215-223) or the related plasmid pCJR29 in which the polyketide synthase gene(s) are placed under the control of the *actI* promoter which is activated by the ActII-orf4 activator; or alternatively the *monAI* promoter can be substituted together with the MonRI activator; or some other pairing of activator and cognate promoter chosen from either a Type II or a Type I polyketide synthase gene cluster. As an example, the wild type strain of *Streptomyces cinnamonensis* has been used to express the plasmid pCJR29 (Rowe, C. *et al.* Gene (1998) 216:215-223) containing as insert the three ORFs for the PKS governing the production of 6-deoxyerythronolide B, the macrolide precursor of erythromycin A in *Saccharopolyspora erythraea*, these genes being placed under the control of the pathway-specific *actI* promoter from *Streptomyces coelicolor* together with its cognate activator gene *actII*-orf4. The transformed strain when cultivated in a suitable liquid medium produced 6-deoxyerythronolide B in good yield.

It is well known to the person skilled in the art that it is possible to use standard vectors unable to replicate in actinomycetes to introduce DNA into a *Streptomyces* cell, such DNA comprising two portions of contiguous DNA which are each identical to one of two portions of the cell's chromosome that are spaced up to 100 kbp apart; and that through recombination between the incoming DNA and the chromosome occurring in both portions of DNA the net result is that the chromosomal sequence is replaced by the defective sequence originally that of the incoming DNA. Such a procedure has been applied to the monensin-producing strain of *S. cinnamonensis* as described in detail below, and a strain of *S. cinnamonensis* has been obtained that carries a specific deletion in the monensin cluster and which is unable to produce the antibiotic. The use of such a strain facilitates the production of heterologous polyketides by removal of the background of monensin production.

The multiple uses of portions of the cloned and sequenced DNA from the monensin cluster will readily occur to the person skilled in the art. A surprising feature of the PKS of the monensin cluster is an unusual mechanism of polyketide chain initiation. We have found that the monensin PKS loading module has three domains, which from the amino-terminus of the protein are: a KSq domain, an

acyltransferase domain and an ACP domain. We have uncovered this organisation in the PKS for the 14-membered macrolide oleandomycin as well as in the monensin PKS, an organisation of the loading module previously only found for the 16-membered macrolides and in which the KSq domain (which looks like a ketosynthase or condensation domain except that the active site cysteine residue is substituted by a glutamine for which the single letter notation is Q) had been previously speculated to have no function. It was realised that the acyltransferase of the loading module actually has malonyl-CoA and not acetyl-CoA as a substrate and that KSq is an active decarboxylase. It appears that a better discrimination can be achieved in the selection of the smaller acetate unit over propionate if the choice is made initially between methylmalonyl- and malonyl-CoA.

An unprecedented feature of the monensin PKS genes is that no integral chain-terminating domain is present as a C-terminal appendage of the PKS extension module that catalyzes the twelfth and final chain extension. Because the product of the monensin PKS is a carboxylic acid, it would have been firmly predicted that chain release would have been catalyzed by such a C-terminal domain containing a "thioesterase" activity. Previously sequenced PKS gene sets have been of two sorts: first, those macrolide PKSs

typified by erythromycin, spiramycin, tylosin, niddamycin which have a readily recognisable C-terminal "thioesterase" domain, which in these enzymes functions as a specific cyclase rather than releasing the polyketide product as a free carboxylic acid; secondly, those macrolide PKSs typified by rapamycin, FK506, and rifamycin, where there is an alternative and recognised mode of chain termination by transfer of the polyketide chain to an acceptor moiety, catalyzed by a specific enzyme (eg pipecolate incorporating enzyme for rapamycin (Schwecke T. *et al.* Proc. Natl. Acad. Sci. USA (1995) 92:7839-7843) and FK506 (Mothamedi H. and Shafiee A, Eur. J. Biochemistry (1998) 256:528-534); arylamine synthetase for rifamycin (August P.R. *et al.* Chemistry & Biology (1998) 5:69-79).

The monensin PKS surprisingly falls into neither category, and therefore seems to be the first example of a novel mode of chain termination. It is novel and noteworthy in this connection that the monensin PKS gene cluster contains two small genes that encode discrete, monofunctional thioesterase enzymes. Although many PKS gene clusters have been previously shown to contain one such discrete thioesterase, none have been shown to have two. The role of such thioesterases is not known, although in the case of methymycin/pikromycin PKS, which has been

reported to be responsible for the biosynthesis of both the 12-membered macrolide methymycin and the 14-membered macrolide pikromycin (Xue Y.Q. Proc. Natl. Acad. Sci. USA (1998) 95:12111-12116) the disruption of this thioesterase reportedly caused a ten-fold drop in the amount of both macrolides produced. A similar finding has been reported for the discrete thioesterase of the tylosin PKS gene cluster (Cundliffe E. *et al.* Chemistry & Biology in press). Additional copies of such thioesterases may therefore accelerate the production of specific polyketide, but this has not yet been demonstrated. However, the presence of the discrete thioesterase is not completely essential for polyketide production.

It is highly desirable to have a broadly effective method of catalysing the release of polyketide gene products from a PKS as the free acid. The well-studied integral thioesterase domain in the erythromycin PKS thioesterase has a broad specificity in cyclization to form a lactone (assuming that a hydroxy group is present in the growing polyketide chain at an appropriate position), but hydrolysis to form the free acid is very slow. The recognition of the unusual arrangement of the monensin PKS means that it is now possible to harness either the entire PKS module that catalyses the twelfth and final extension cycle in monensin biosynthesis, or the

C-terminal portion of it, and graft it onto a different polyketide synthase by genetic engineering, so as to allow the release mechanism characteristic of monensin to operate in a different context. The use of this portion only of the monensin PKS suffices to allow the novel mechanism of chain release to operate successfully. The speed of the polyketide chain hydrolysis in a given case can depend on the additional presence of one or both of the discrete thioesterase genes (*monAIX* and *monAX*) from the monensin gene cluster. The use of this novel method of chain termination represents a valuable way of generating a large number of novel engineered polyketides that are currently inaccessible, and ensuring that the products have a specified chain length.

The genes *monBI* and *monBII* appear to encode very similar enzymes with significant amino acid sequence similarity to authentic ketosteroid isomerases which are known to catalyse the migration of an activated carbon-carbon double bond. The conservation of active site residues makes it very likely that these *mon* genes govern a reaction involving activated double bonds in the biosynthetic pathway to monensin and this surprising observation can be accommodated if the initial product of the polyketide chain growth on the monensin PKS is a linear precursor in which the double bonds were initially

formed with a conventional *trans* or E (entgegen) geometry; but before the polyketide chain was extended by insertion of the next unit the *monBI* and/or the *monBII* gene product(s) catalyse the specific rearrangement of the newly-created double bond into the *cis* or Z (zusammen) geometry. This new view of the monensin biosynthetic pathway allows the deduction that the *monBI* and *monBII* genes, perhaps in combination with specific portions of the monensin modules where they normally exert their effects (namely modules 3, 5 and 7) might be used in order to achieve the extremely desirable targetted biosynthesis of novel polyketides containing double bonds with Z geometry at specified point(s) along the chain. Thus for example it should be possible to provide for the direct biosynthesis of C22-C23 *cis* or Z double bond in avermectins, thus avoiding tedious and expensive chemical conversion of an initial fermentation product into this important anthelminthic. Only limited experimentation is needed to see whether the *monBI* and/or *monBII* gene products are sufficient or whether the *mon* PKS at modules 3, 5 and 7 forms part of the specific docking site(s) for the isomerases and therefore must also be used in the creation of the hybrid PKS that will insert the *cis* or Z double bond at the desired position. The substrate specificity of the isomerases need not be limited to 2,3-

unsaturated thioesters. The purified enzymes could also be used to effect such isomerisations *in vitro*, depending on the position of the equilibrium or whether further enzymes are used to achieve the further transformation of the product as it is formed (*vide infra*).

The product of the *monCI* gene is a novel oxidative enzyme with some sequence similarity to authentic examples of such enzymes in the databases; and with a clearly definable role in the monensin biosynthetic pathway, the epoxidation of the double bonds at three separate positions in the initially-formed acyclic intermediate in monensin biosynthesis. This epoxidase could therefore be used in conjunction with *monBI/monBII* gene products to effect oxidative reactions on suitable substrates *in vitro* and *in vivo*. Similarly the *monCII* gene product is a putative cyclase that opens the epoxides and causes the formation of ether rings in monensin.

Any or all of the *monBI, monBII, monCI or monCII* genes may be introduced into a heterologous strain containing the gene cluster for another polyether, in order to divert the biosynthetic pathway and produce a polyketide of altered structure. In these experiments the analogues of these *monB* genes could either be present or (once located and characterised using the *mon* genes as probes) they may be deleted prior to the introduction of

the *monB* and *monC* genes into that strain. The converse experiment in which analogues of the *monB* and *monC* genes from other strains are introduced into *S. cinnamonensis* likewise has the potential to produce novel oxidised polyketides. Also, the *monB* and *monC* genes or their analogues may be introduced into a strain that normally produces a macrolide or a polyene or some other complex polyketide and expressed there, when they may effect the diversion of the growing polyketide chain on a heterologous modular PKS towards a new product, which may or may not have the structure of a polyether.

The availability of the monensin gene sequence allows the institution of domain swaps to alter the acyltransferase (AT) specificity of a given module, for example the ethylmalonyl-CoA specific extender found in one of the modules of the monensin PKS can be used to replace one of the other ATs to generate an ethyl side branch at that position in the chain, or the AT can be used to substitute in any other (e.g. macrolide) PKS, as described in WO 98/01571 and WO 98/01546. Similarly the alteration of the level of reduction in a module, by manipulation of the reductive enzymes, can be applied to the monensin genes and here it will produce, depending on which module is affected, either an altered monensin, or a

species which is only partly cyclised, or a polyether with an altered pattern of cyclisation, or even a linear polyketide.

In general the targetted alteration of the pattern of substitution of sidechains or reduction level along the polyketide chain produced by the monensin PKS will, like the disruption or deletion of the oxidative enzymes mentioned above, lead to non-polyether polyketide products. It should be possible, by introduction of the DEBS thioesterase at the C-terminus of one of the later modules of the monensin PKS, together with an appropriately placed hydroxy group earlier in the chain, to produce novel macrolide products from this polyether PKS system, or alternatively novel polyenes of defined chain length and chosen ring size.

Example 1

Cloning of the monensin A biosynthetic gene cluster using DNA probes derived from the erythromycin-producing polyketide synthase of *Saccharopolyspora erythraea*

A genomic library of the monensin A producing strain *Streptomyces cinnamonensis* ATCC 15413 was constructed using methods well-known in the art, namely, the production of high molecular weight genomic DNA, followed by the partial cleavage of this DNA using the frequent-cutting restriction enzyme *Sau*3A, fractionation of the fragments on a sucrose gradient and selection of fragments of average size 35-40 kbp, and the cloning of these fragments into the cosmid vector pWE15 (Evans, G.A. *et al.* Gene (1989) 79:9-20) which had been previously digested with *Bam*HI and treated with shrimp alkaline phosphatase. The library was packaged and transfected into *Escherichia coli* XL-1 Blue MR cells. The library was plated out on 2xTY agar medium (10 g tryptone, 10 g yeast extract, 5 g NaCl, 15 g bactoagar per litre containing ampicillin 50 μg/ml) for cosmid selection and the colonies were allowed to grow overnight. The library was then screened by hybridisation using as a probe DNA encoding the ketosynthase domain of module 1 of the erythromycin-producing *PKS* (6-deoxyerythronolide B synthase, DEBS) of *Saccharopolyspora erythraea*. The colonies giving a

positive hybridisation signal in the hybridisation were selected and the cosmid DNA from each colony was purified and mapped by restriction digestion. The presence of the target biosynthetic genes on a cosmid was verified by sequencing of the ends of the cosmid inserts using the commercially available T3 and T7 primers which hybridise specifically to the respective ends of each cosmid insert (Evans, G.A. *et al.* Gene (1989) 79:9-20).

Example 2

Sequencing of the biosynthetic gene cluster for monensin A from *Streptomyces cinnamonensis*

Three cosmids obtained by screening of the genomic library of *S. cinnamonensis* were used to obtain the entire DNA sequence of the monensin biosynthetic gene cluster. These cosmids, MO.CN02, MO.CN11 and MO.CN33 between them contain the entire DNA sequence of the cluster and the adjacent regions of the chromosome. They have been deposited in NCIMB, 23 St Machair Drive, Aberdeen AB24 3RY, UK, under the NCIMB accession numbers 40956 (MO-CN11); 40957 (MO-CN33) and 40958 (MO-CN02) respectively.

The DNA of each cosmid was separately subjected to partial digestion with *Sau*3A and fragments of approximately 1.5-2.0 kbp were separated by agarose gel electrophoresis. The fragments were then ligated into the

plasmid vector pUC18 (Messing, 1982), previously digested with *BamHI* and treated with shrimp alkaline phosphatase. The library was transformed into *E. coli* strain XL1-Blue MR and plated on 2xTY agar medium containing ampicillin (100 µg/ml) to select for plasmid-containing cells. Plasmid DNA was purified from individual colonies and sequenced using the Sanger dye-terminator procedure on an ABI 377 automated sequencer (Sanger, F. Science (1981) 214:1205-1210). The sequence data obtained from single random subclones of a cosmid was assembled into a single continuous sequence and edited using GAP4.1 program of the STADEN gene analysis package (Staden, R. Molecular Biotechnology (1996) 5:233-241).

The sequence is set out in the appended sequence listing.

Tables I and II contain data about individual genes and gene products.

Example 3

Inactivation of the monensin A biosynthetic gene cluster

A chromosomal gene disruption experiment was used to verify the identity of the cloned polyketide synthase gene cluster. Plasmid pMOB6314 is a pUC18 sequencing subclone of the presumed monensin A biosynthetic gene cluster prepared as described in Example 1, whose inserted DNA comprises the DNA sequence from nucleotide 9763 to

nucleotide 10108 in SEQ ID 1, and which therefore contains a region of DNA wholly internal to *orfE*, a putative 3-O-methyltransferase. A *Hin*dIII fragment containing the thiostrepton resistance gene *tsr* from plasmid pIJ702 (Katz, E. *et al.* J. Gen. Microbiol. (1983) 129:2703-2714) was cloned into the *Hin*dIII site of plasmid pMOB6314 and the ligation mixture was used to transform *E. coli* cells. Transformants bearing the required plasmid pMOΔE01 were identified by isolation of plasmid DNA and analysis by restriction digestion. pMOΔE01. Plasmid pMOΔE01 was used to transform protoplasts of *Streptomyces cinnamonensis* as described by (Hopwood D.A. *et al.* (1985)). Since plasmid pMOΔE01 lacks an origin of replication that is active in *Streptomyces*, growth in the presence of thiostrepton (25 µg/ml) in the regeneration medium led to the isolation of stable integrants. Isolated putative integrants were tested for the presence of integrated pMOΔE01 sequences by Southern hybridisation. A clone of *Streptomyces cinnamonensis* identified by its restriction pattern in Southern hybridisation as bearing pMOΔE01 integrated in the region of *monE* of the monensin A biosynthetic gene cluster was designated *S. cinnamonensis* MO-DD01.

Detection of production of the monensin A related metabolites produced by *S. cinnamonensis* MO-DD01 was performed by GC-MS analysis of methanol extracts of the

entire broth harvested in 72 hours of growth of the strain. No significant amounts of monensin A-related metabolite production were detectable.

Example 4

Overproduction of erythromycin aglycone in *Streptomyces cinnamonensis*

S. cinnamonensis is a suitable system for overproduction not just of monensin A but also of other polyketide metabolites. Established techniques of genetic transformation allow fast introduction of foreign polyketide producing genes sets into this host. Fast growth of *S. cinnamonensis* in liquid culture and optimal precursor supply favour high yield of polyketide metabolites.

Construction of pIB061

S. erythraea NRRL2338 was transformed with pCJR30 (Rowe, C. J., et al. (1998) Gene 216:215-223) using a routine protoplast transformation technique as described by Hopwood et al. (1985). A stable integrant of *S. erythraea* [pCJR30] was identified and the production of 10mg/L of the triketide lactone (delta lactone of (2S,3R,4R,5R)-2,4-dimethyl-3,5-dihydroxy-heptanoic acid) in addition to erythromycins was confirmed by MS analysis.

Total DNA of *S. erythraea* [pCJR30] was purified and

approximately 200 ng was digested with *Eco*RI endonuclease. The digestion mixture was precipitated with isopropanol and the resulting DNA was treated with T4 DNA-ligase for 16 hours at 16°C. The ligation mixture was used to transform *E.coli* DH10B cells. The transformants were screened for the presence of the plasmid. A clone containing a 44.7kb plasmid was identified and confirmed by restriction analysis to contain three complete genes: *ery*AI, *ery*AII and *ery*AIII. The plasmid was named pIB061.

Transformation of *S. cinnamonensis*

Protoplasts of *S. cinnamonensis* were prepared by a modified procedure of Hopwood *et al.* (1985). Plasmid pIB061 was transformed into the protoplasts of *S. cinnamonensis* and stable thiostrepton resistant colonies were isolated. Individual colonies were checked for their plasmid content and the presence of plasmid pIB061 was confirmed by its restriction pattern. *S. cinnamonensis* (pIB061) was inoculated into 250 ml of M-C3 minimal production medium containing 10 μg/ml of thiostrepton and allowed to grow for 72 hours at 30 °C. After this time the mycelia were removed by filtering. The broth was extracted with two volumes of ethyl acetate and the combined ethyl acetate extracts were washed with an equal volume of saturated sodium chloride, dried over anhydrous sodium sulphate, and the ethyl acetate was removed under reduced

pressure to give about 200 mg of crude product. The product was analysed by LCQ and mass was confirmed to that of erythronolide B.

This example demonstrates the importance of *S. cinnamonensis* for production of high levels of foreign polyketide antibiotics. Introduction of the complete erythromycin gene cluster or other gene clusters into this system are likely to produce high levels of the corresponding metabolites.

Example 5

Construction of plasmid pCJW58 containing the monensin activator gene under the ermE* promoter

The ermE* promoter derived from the *ermE* resistance methyltransferase gene of *S. erythraea* (Bibb *et al.* Gene (1985) 38:215-226) was amplified by PCR as a *Spe*I-*Xba*I fragment using the following oligonucleotides 5'-CCACTAGTATGCATGCGAGTGTCCGTTCGAGT-3' and 5'-TTGTATACACCTAGGATGGTTGGCCGTGC-3' with pRH3 (Dhillon *et al.* Molecular Microbiology (1989) 3:1405-1414 as a template and cloned into *Sma*I-digested, phosphatase-treated pUC18, to produce plasmid pIB135. The integrative plasmid pSET152 (Bierman, M. *et al.* (1992) Gene 116:43-49)) was digested with *Xba*I and the backbone was dephosphorylated and ligated to the *Spe*I-*Xba*I fragment of pIB135 containing the *ermE** promoter. The ligation mixture was used to

transform *E. coli* DH10B and the orientation of the insert in the plasmids from individual clones was checked by using restriction analysis. A plasmid with the *ermE** promoter oriented so that the *NdeI* and *XbaI* sites are adjacent to the apramycin resistance gene was selected and named pIB139.

The *monR* gene from the monensin biosynthetic gene cluster was amplified and *NdeI* and *XbaI* restriction sites introduced at 5′ and 3′ ends respectively, by PCR using as primers the following oligonucleotides:
5′-AGA TAC CAT ATG CTG GGC CCG CTC CGC AT -3′
and 5′-AAT GCT CTA GAC TGT CAG CGA CCG GAC AGG GCC AA-3′
and cosmid MO.CN11 as template. The PCR product was ligated into *SmaI*-treated and phosphatase-treated plasmid pUC18 and the ligation mixture was used to transform *E. coli* DH10B cells. Transformant colonies were analysed for the presence of plasmid and the identity of the plasmid inserts was verified by sequencing. A plasmid whose insert contained the *monR* gene flanked by *NdeI* and *XbaI* restriction sites was selected and designated pCJW57.

Plasmid pCJW57 was digested with *NdeI* and *XbaI* and the fragment containing the monR gene was ligated together with the backbone of plasmid pIB139 which had been digested with the same two restriction enzymes, and purified by gel elution. The ligation mixture was used to

transform *E. coli* strain DH10B cells. Transformant colonies were analysed for the presence of plasmid and the identity of the plasmid inserts was verified by restriction analysis. One such recombinant was selected and named plasmid pCJW58.

Plasmid pCJW58 was used to transform the methylation-deficient *E. coli* strain ET 12567 (MacNeil D. J. et al. (1992) Gene 111:61-68) and the recovered, unmethylated plasmid was then used to transform the same *E. coli* strain ET12567 housing the plasmid pUB307, a derivative of RP4 which is *mob*$^-$ and which contains a gene for kanamycin resistance (Piffaretti, J. C. et al. (1988) Mol. Gen. Genet. 212:215-218). Recombinants were plated on 2 x TY agar medium containing apramycin and kanamycin at final concentrations of 50 micrograms per ml and 50 micrograms per ml respectively. The plasmid content of recombinants was checked isolation of plasmid DNA and checking of the identity of these plasmids by restriction analysis. One such clone which contained both pUB307 and plasmid pCJW58 was selected and used for further experiments.

Construction of *Streptomyces cinnamonensis* (pCJW58) and production of monensins

A single colony of *E. coli* ET12567 housing both pUB307 and pCJW58 was toothpicked into 3 ml of TY liquid medium, containing apramycin and kanamycin at 25 and 25

micrograms respectively, and grown overnight at 37°C. This culture was used to inoculate 25 ml of TY medium, supplemented with the same antibiotics at the same concentrations, and growth was continued until the absorbance at 600 nm (1 cm pathlength) was between 0.3-0.6. The cells were centrifuged (room temperature, 7 minutes, 2000 x *g*), resuspended in TY liquid medium (10 ml) containing no added antibiotics, re-centrifuged as before, then resuspended in 2ml of TSB medium and placed on ice. Meanwhile, 0.5 ml of TSB medium was added to 100 microL containing approximately 10^8 spores of *S. cinnamonensis*. After a brief heat shock, at 50°C for 10 minutes, the suspension was briefly cooled, mixed with 0.5 ml of donor *E. coli* cells, and plated on solid A medium, which has composition as follows:

A medium

Sigma wheat starch	5g
Corn steep powder	1.25g
Yeast extract	1.5g
$CaCO_3$	1.5g
$FeSO_4$	6 mg
DIFCO agar	10g
H_2O	to 500 ml

pH adjusted to pH 7 with KOH.

And to which in addition was added 10 mM $MgCl_2$ to a final concentration of 10 mM.

The plates were allowed to dry overnight at room temperature, and were then allowed to incubate a further 18 hours at 30°C. After this time each 25 ml plate was overlaid with a solution of apramycin (final concentration 50 micrograms per ml) and nalidixic acid (final concentration 20 micrograms per ml), and the plates were allowed to incubate for four days at 30°C. At this time individual colonies were toothpicked onto solid A medium and allowed to grow. Four representative colonies from the A medium plate were grown up in liquid modified YEME medium, which has composition as follows:

Modified YEME medium

Sucrose	100g
DIFCO Yeast extract	3g
Bacto peptone	5g
Oxoid Malt extract	3g
Glucose	10g

H_2O to 1L

pH adjusted to pH 7.2 with NaOH.

These cultures were used to provide a 2% vol/vol inoculum for 30 ml of modified YEME which was grown for 7 days, and then transferred to SM16 medium, which has

composition as follows:

SM16 medium

3-[N-Morpholino]-propane sulfonic acid (MOPS) buffer	20.9g
L-proline	10.0g
Glucose	20g
NaCl	0.5g
K_2HPO_4	2.1g
Ethylenediaminetetraacetic acid, sodium salt	0.25g
$MgSO_4.7H_2O$	0.49g
$CaCl_2.2H_2O$	0.029g
Trace elements solution (Hopwood, D. A. et al. (1985) Genetic Manipulation of *Streptomyces* - a Laboratory Manual, at p.235)	2 ml
0.5 M $CoCl_2$ solution	2 microlitres
H_2O to 1L	
pH adjusted to pH 7 with NaOH.	

After growth for a further 7 days, mycelium was collected by centrifugation at 2000 x g for 30 minutes, and the supernatant was extracted three times with 300 ml of ethyl acetate. The combined extracts were concentrated by evaporation under reduced pressure to an oil, which was

mixed with 1 ml of methanol. Samples were applied to an LCQ liquid chromatograph fitted with a mass spectrometer detector unit. The column used was a C18 reversed phase column, equilibrated with a mixture of 80% 20mM ammonium acetate/20% acetonitrile, and the column was eluted with a gradient of increasing acetonitrile, reaching 100% acetonitrile over 24 minutes. Monensins A and B emerged from the column with retention times respectively of 8.2 minutes and 9.2 minutes. The relative amounts of monensin produced by three independent clones (A-C) containing an additional copy of the *monR* gene were compared to a control fermentation of the wild type *S. cinnamonensis* strain, with the results shown in the Table below:

Table showing increased monensin production in strains bearing additional copy of *monR* gene

Strain	monensin A concentration (arbitrary units)	monensin B concentration (arbitrary units)
Control	188	861
A	430	1 800
B	450	1 300
C	249	1 300

Example 6

Construction of *S. cinnamonensis* M12AT5

A region lying immediately 5′ of the DNA encoding the

acyltransferase (AT12) domain of module 12 of the monensin polyketide synthase in the monensin biosynthetic gene cluster was amplified with the following primers: 5′-GGTGGCCACGGAAACACCAACACCGGACCCGCGCC-3′, and 5′-CTCTCGGAGGCCCGGCGCAACGGCCACAA-3′, 3′ using cosmid MO-CN11 as a template. The PCR product was ligated into *Sma*I digested and phosphatase-treated plasmid pUC18 and the ligation mixture was used to transform *E. coli* DH10B cells. Transformant colonies were analysed for the presence of plasmid and the identity of the plasmid inserts was verified by sequencing. A plasmid whose insert contained a fragment upstream of the AT12-encoding sequence from about 82.3kb to 83.2kb of the *mon* cluster was designated pMO81. Similarly a region lying immediately 3′ of the DNA encoding the acyltransferase (AT12) domain of module 12 of the monensin polyketide synthase in the monensin biosynthetic gene cluster was amplified with the following primers: 5′-GGCCTAGGGCTGCCTCGGGTGGTGGATCTGCCGA-3′ and 5′- TGGTCGGGCGCGGTGCGTGCGATACGT-3′, using cosmid MO-CN11 as a template. The PCR product was ligated into *Sma*I-treated and dephosphorylated pUC18 and the ligation mixture was used to transform DH10B *E.coli* cells. Transformant colonies were analysed for the presence of plasmid and the identity of the plasmid inserts was verified by sequencing. A plasmid whose insert contained

a fragment downstream of the AT12-encoding sequence, from 80.5kb to 81.4kb of the *mon* cluster, was designated pMO82.

The DNA encoding AT of module 5 was amplified and *Msc*I and *Avr*II restriction enzyme recognition sites were introduced at the ends by PCR using the following primers: 5'-CCTGGCCAGGGCGGCCAGTGGGTGGGCATG-3' and 5'-GGCCTAGGGGTCGGCCGGGAACCAGCGCCGCCAGT-3' and the cosmid MO-CN33 as a template. The PCR product was ligated into *Sma*I-treated and dephosphorylated pUC18 and the ligation mixture was used to transform DH10B *E.coli* cells. Transformant colonies were analysed for the presence of plasmid and the identity of the plasmid inserts was verified by sequencing. A plasmid whose insert DNA, with sequence from about 44.2kb to 45.2kb of the *mon* cluster, encoded the AT5 domain was designated pMO83.

pMO81 was digested with *Msc*I and *Hin*dIII and ligated to the 0.9kb *Msc*I - *Hin*dIII fragment of pMO82. A clone containing both fragments was designated pMO84. Plasmid pMO84 was cleaved with *Avr*II and *Hin*dIII, treated with phosphatase, and ligated together with the 1.0 kb *Avr*II - *Hin*dIII fragment of pMO83 to produce pMO85, which contains the DNA encoding the AT5 domain flanked by DNA from either side of the DNA encoding the AT12 domain of the monensin PKS. The thiostrepton resistance gene *tsr*, derived from plasmid pIJ702 (Katz, E. et al., J. Gen. Microbiol.

1983), was cloned into the *Hin*dIII site of pMO85. The resulting plasmid pMO86 was analysed by its restriction pattern and confirmed to contain all the desired elements.

Plasmid pMO86 was used to transform *S. cinnamonensis* protoplasts as described by Hopwood, D. A. (1985). Stable thiostrepton-resistant transformants were isolated and checked for the desired integration of the pMO85 into the AT12 flanking regions by Southern blot hybridisation. One such integrant, *S. cinnamonensis* MO-08, containing pMO85 integrated upstream of the AT12, was passed through 4 cycles of sporulation on a non-selective nutrient medium. Spores obtained after the fourth cycle were replica-plated onto media with and without thiostrepton. DNA of clones that had lost thiostrepton resistance was analysed by Southern blot hybridisation. Clones in which the DNA encoding the AT12 domain had been replace by the DNA encoding the AT5 domain was designated *S. cinnamonensis* M12-AT5. At this time individual colonies were toothpicked onto solid A medium and allowed to grow. Four representative colonies from the A medium plate were grown up in liquid modified YEME medium, which has composition as follows:

Modified YEME medium

Sucrose	100g
DIFCO Yeast extract	3g
Bacto peptone	5g
Oxoid Malt extract	3g
Glucose	10g
H_2O to 1L	

pH adjusted to pH 7.2 with NaOH.

These cultures were used to provide a 2% vol/vol inoculum for 30 ml of modified YEME which was grown for 7 days, and then transferred to SM16 medium, which has composition as follows:

SM16 medium

3-[N-Morpholino]-propane sulfonic acid (MOPS) buffer	20.9g
L-proline	10.0g
Glucose	20g
NaCl	0.5g
K_2HPO_4	2.1g
Ethylenediaminetetraacetic acid, sodium salt	0.25g
$MgSO_4.7H_2O$	0.49g
$CaCl_2.2H_2O$	0.029g
Trace elements solution (Hopwood, D. A. et al. (1985) Genetic	

Manipulation of *Streptomyces* - a Laboratory Manual, at p.235) 2 ml

0.5 M $CoCl_2$ solution 2 microlitres

H_2O to 1L

pH adjusted to pH 7 with NaOH.

After growth for a further 7 days, mycelium was collected by centrifugation at 2000 x g for 30 minutes, and the supernatant was extracted three times with 300 ml of ethyl acetate. To confirm presence of the C-2-ethyl substituents of both monensin A and B the combined extracts were concentrated by evaporation under reduced pressure to an oil, which was mixed with 1 ml of methanol. Samples were applied to an LCQ liquid chromatograph fitted with a mass spectrometer detector unit. The column used was a C18 reversed phase column, equilibrated with a mixture of 80% 20mM ammonium acetate/20% acetonitrile, and the column was eluted with a gradient of increasing acetonitrile, reaching 100% acetonitrile over 24 minutes. Mass ions 14 mass units above those expected for both monensin A and B confirmed production of the respective C-2-ethyl substituents.

Example 7. Construction of pSGK005 and its use in the production of C-13 propyl-erythromycin

Plasmid pSGK005 is a pCJR24 based plasmid containing a PKS gene comprising a loading module plus the first and

second extension modules and the chain terminating thioesterase of the PKS responsible for the production of erythromycin (DEBS). The loading module comprises the KS and ethyl-malonyl CoA specific AT from module 5 of the monensin PKS linked to the DEBS loading ACP domain. In addition, the active site cysteine of this module 5 KS has been mutated to glutamine to convert an extender di-domain to a loading di-domain. Plasmid pSGK005 was constructed as follows.

A 2769bp DNA segment of the monensin cluster of *S. cinnamonensis* extending from nucleotide 42438 to 45207 was amplified by PCR using the following oligonucleotide primers. 5′-GTGACGTCATATGTCGAGTGCTGAAGAGTCG-3′ and 5′-GGGGTCGCCTAGGAACCAGCGCCGCCAGTCGA-3′

The design of these primers introduced *Nde* I and *Avr* II sites at the ends of the amplifed fragment. Monensin cosmid 05 was used as a template for the reaction. The resulting 2769bp fragment was digested with *Nde* I and *Xho* I and a 656bp fragment (Fragment A) purified by preparative gel electrophoresis.

A second PCR reaction was used with the same template to amplify DNA from nucleotide 43098 to 45207. The primers used were 5′-CGGCCTCGAGGGCCCGTCGGTCAGTGTCGACACGGCGCAGTCCTCCTCGC-3′ and 5′-GGGGTCGCCTAGGAACCAGCGCCGCCAGTCGA-3′

The design of the upstream oligonucleotide primer incorporated a change of the codon specifying the KS active site cysteine (nucleotides 43135-43137, TGC) to glutamine (CAG). The resulting 2109bp DNA fragment (Fragment B) was digested with *Xho* I and *Avr* II and purified by preparative gel electrophoresis.

Plasmid pCJW80 is derived from pCJR24 and DEBS1-TE in which *Msc* I and *Avr* II sites have been introduced to flank the AT of the DEBS loading module. This plasmid was digested with *Nde* I and *Avr* II and the larger fragment (Fragment C) purified by preparative gel electrophoresis.

The three fragments (Fragments A, B, C) were ligated together using T4 DNA ligase and the ligation mixture used to transform electrocompetent *E. coli* DH10B cells. Individual clones were checked for the presence of the desired plasmid pSGK005. The identity of pSGK005 was confirmed by restriction pattern and sequence analysis.

Plasmid pSGK005 was used to transform *S. erythraea* NRRL2338 using a routine protoplast transformation technique. Thiostrepton resistant colonies were selected on R2T20 media containing g/ml thiostrepton. Further analysis confirmed that pSGK005 had integrated into the *S. erythraea* NRRL2338 chromosome by Southern blot hybridisation of their genomic DNA with DIG-labelled DNA containing the *actII orf4* promoter. The culture *S.*

erythraea NRRL2338 (pSGK005) was inoculated into 5ml tap water medium in a 30ml flask. After three days incubation at 29°C this flask was used to inoculate 30ml of Ery-P medium in a 300ml flask. The broth was incubated at 29°C at 200rpm for 6 days. After this time the whole broth was adjusted to pH8.5 with NaOH, and then extracted twice with an equal volume of ethyl acetate. The ethyl acetate extract was evaporated to dryness at 45°C under a nitrogen stream using a Zymark Turbovap LV evaporator. The product identities were confirmed by LC/MS. A peak was observed with a m/z value of 734 $(M+H)^+$ required for erythromycin A. A second peak was observed with a m/z value of 748 $(M+H)^+$, required for 13-propyl erythromycin A.

References

1. Ajaz, A.A. and Robinson, J.A. (1983) The utilization of oxygen atoms from molecular oxygen during the biosynthesis of Monensin-A. *Journal of the Chemical Society-Chemical Communications*, **12**, 679-680.

2. Ashworth, D.M., Holmes, D.S., Robinson, J.A., Oikawa, H. and Cane, D.E. (1989) Selection of a specifically blocked mutant of *Streptomyces cinnamonensis* - isolation and synthesis of 26-deoxymonensin-A. *Journal of Antibiotics*, **42**, 1088-1099.

3. August, P.R., Tang, L., Yoon, Y.J., Ning, S., Muller, R., Yu, T.W., Taylor, M., Hoffmann, D., Kim, C.G., Zhang, X.H., Hutchinson, C.R. and Floss, H.G. (1998) Biosynthesis of the ansamycin antibiotic rifamycin: deductions from the molecular analysis of the *rif* biosynthetic gene cluster of *Amycolatopsis mediterranei* S699. *Chemistry & Biology*, **5**, 69-79.

4. Bartel, P.L., Zhu, C.B., Lampel, J.S., Dosch, D.C., Connors, N.C., Strohl, W.R., Beale, J.M. and Floss, H.G. (1990) Biosynthesis of anthraquinones by interspecies cloning of actinorhodin biosynthesis genes in *Streptomycetes* - clarification of actinorhodin gene functions. *Journal of Bacteriology*, **172**, 4816-4826.

5. Bibb, M.J., Biro, S., Motamedi, H., Collins, J.F. and Hutchinson, C.R. (1989) Analysis of the nucleotide sequence of the *Streptomyces glaucescens Tcml* genes provides key information about the enzymology of polyketide antibiotic

biosynthesis. *EMBO Journal*, **8**, 2727-2736.

6. Bibb, M.J. and Hopwood, D.A. (1981) Genetic studies of the fertility plasmid SCP2 and its SCP2* variants in *Streptomyces coelicolor* A3(2). *Journal of General Microbiology*, **126**, 427-442.

6a. Bibb M.J., Janssen G.R. and Ward J.M. (1985) Cloning and analysis of the promoter region of the erythromycin resistance gene (ErmE) of *Streptomyces erythraeus*. *Gene*, **38**, 215-226.

6b. Bierman, M., Logan, R., O'Brien, K., Seno, E.T., Rao R.N. and Schoner B.E. (1992) Plasmid cloning vectors for the conjugal transfer of DNA from Escherichia coli to Streptomyces spp. *Gene*, **116**, 43-49.

7. Cane, D.E., Liang, T.C. and Hasler, H. (1981) Polyether biosynthesis - origin of the oxygen atoms of Monensin-A. *Journal of the American Chemical Society*, **103**, 5962-5965.

8. Cane, D.E., Liang, T.C. and Hasler, H. (1982) Polyether biosynthesis 2. Origin of the oxygen atoms of monensin A. *Journal of the American Chemical Society*, **104**, 7274-7281.

9. Cortés, J., Haydock, S.F., Roberts, G.A., Bevitt, D.J. and Leadlay, P.F. (1990) An unusually large multifunctional polypeptide in the erythromycin producing polyketide synthase of *Saccharopolyspora erythraea*. *Nature*, **348**, 176-178.

10. Cortés, J., Wiesmann, K.E.H., Roberts, G.A., Brown, M.J.B., Staunton, J. and Leadlay, P.F. (1995) Repositioning

of a domain in a modular polyketide synthase to promote specific chain cleavage. *Science*, **268**, 1487-1489.

11. Davis, N.K. and Chater, K.F. (1990) Spore color in *Streptomyces coelicolor* A3(2) involves the developmentally regulated synthesis of a compound biosynthetically related to polyketide antibiotics. *Molecular Microbiology*, **4**, 1679-1691.

12. Day, L.E. (1973) *Antimicrobial Agents and Chemotherapy*, **4**, 410-414.

13. Demetriadou, A.K., Laue, E.D., Staunton, J., Ritchie, G.A.F., Davies, A. and Davies, A.B. (1985) Biosynthesis of the polyketide polyether antibiotic ICI-139603 in *Streptomyces longisporoflavus* from O-18-labeled acetate and propionate. *Journal of the Chemical Society Chemical Communications*, **7**,408-410.

13a. Dhillon, N., Hale, R.S., Cortes, J. and Leadlay P.F. (1989) Molecular characterization of a gene from *Saccharopolyspora erythraea* (*Streptomyces erythraeus*) which is involved in erythromycin biosynthesis. *Molecular Microbiology* **3**, 1405-1414.

14. Donadio, S., McAlpine, J.B., Sheldon, P.J., Jackson, M. and Katz, L. (1993) An erythromycin analog produced by reprogramming of polyketide synthesis. *Proceedings of the National Academy of Sciences of the United States of America*, **90**, 7119-7123.

15. Donadio, S., Staver, M.J., McAlpine, J.B., Swanson, S.J. and Katz, L. (1991) Modular organization of genes required

for complex polyketide biosynthesis. *Science*, **252**, 675-679.

16. Evans, G.A., Lewis, K. and Rothenberg, B.E. (1989) High efficiency vectors for cosmid microcloning and genomic analysis. *Gene*, **79**, 9-20.

17. Fernandez-Moreno, M.A., Caballero, J.L., Hopwood, D.A. and Malpartida, F. (1991) The Act cluster contains regulatory and antibiotic export genes, direct targets for translational control by the *bldA* transfer-RNA gene of *Streptomyces*. *Cell*, **66**, 769-780.

18. Fernandez-Moreno, M.A., Martinez, E., Boto, L., Hopwood, D.A. and Malpartida, F. (1992) Nucleotide sequence and deduced functions of a set of cotranscribed genes of *Streptomyces coelicolor* A3(2) including the polyketide synthase for the antibiotic actinorhodin. *Journal of Biological Chemistry*, **267**, 19278-19290.

19. Gramajo, H.C., Takano, E. and Bibb, M.J. (1993) Stationary phase production of the antibiotic actinorhodin in *Streptomyces coelicolor* A3(2) is transcriptionally regulated. *Molecular Microbiology*, **7**, 837-845.

20. Gumila, C., Ancelin, M.L., Delort, A.M., Jeminet, G. and Vial, H.J. (1997) Characterization of the potent *in vitro* and *in vivo* antimalarial activities of ionophore compounds. *Antimicrobial Agents and Chemotherapy*, **41**, 523-529.

21. Hallam, S.E., Malpartida, F. and Hopwood, D.A. (1988) Nucleotide sequence, transcription and deduced function of a gene involved in polyketide antibiotic synthesis in *Streptomyces coelicolor*. *Gene*, **74**, 305-320.

22. Holmes, D.S., Sherringham, J.A., Dyer, U.C., Russell, S.T. and Robinson, J.A. (1990) Synthesis of putative intermediates on the monensin biosynthetic pathway and incorporation experiments with the monensin-producing organism. *Helvetica Chimica Acta*, **73**, 239-259.

23. Hopwood, D.A., Bibb, M.J., Chater, K.F., Kieser, T., Bruton, C.J., Kieser, H.M., Lydiate, D.J., Smith, C.P., Ward, J.M. and Schrempf, H. (1985) *Genetic manipulation of Streptomyces, a laboratory manual*. John Innes Institution, Norwich, UK.

24. Hutchinson, C.R. and Fujii, I. (1995) Polyketide synthase gene manipulation - a structure function approach in engineering novel antibiotics. *Annual Review of Microbiology*, **49**, 201-238.

25. Hutchinson, C.R., Sherman, M.M., Vederas, J.C. and Nakashima, T.T. (1981) Biosynthesis of macrolides .5. Regiochemistry of the labeling of lasalocid a by C-13,O-18-labeled precursors. *Journal of the American Chemical Society*, **103**, 5953-5956.

26. Kakavas, S.J., Katz, L. and Stassi, D. (1997) Identification and characterization of the niddamycin polyketide synthase genes from *Streptomyces caelestis*. *Journal of Bacteriology*, **179**, 7515-7522.

27. Kao, C.M., Luo, G.L., Katz, L., Cane, D.E. and Khosla, C. (1995) Manipulation of macrolide ring size by directed mutagenesis of a modular polyketide synthase. *Journal of the American Chemical Society*, **117**, 9105-9106.

28. Katz, E., Thompson, C.J. and Hopwood, D.A. (1983) Cloning and expression of the tyrosinase gene from *Streptomyces antibioticus* in *Streptomyces lividans*. *Journal of General Microbiology*, **129**, 2703-2714.

29. MacNeil, D.J., Occi, J.L., Gewain, K.M., Macneil, T., Gibbons, P.H., Ruby, C.L. and Danis, S.J. (1992) Complex organization of the *Streptomyces avermitilis* genes encoding the avermectin polyketide synthase. *Gene*, **115**, 119-125.

29a. MacNeil, D.J., Gewain, K.M., Ruby, C.L., Dezeny, G., Gibbons,P.H. and MacNeil, T. (1992) Analysis of Streptomyces avermitilis genes required for avermectin biosynthesis utilizing a novel integration vector. *Gene* **111**, 61-68.

30. Marsden, A.F.A., Wilkinson, B., Cortés, J., Dunster, N.J., Staunton, J. and Leadlay, P.F. (1998) Engineering broader specificity into an antibiotic-producing polyketide synthase. *Science*, **279**, 199-202.

31. Meurer, G., Gerlitz, M., Wendt Pienkowski, E., Vining, L.C., Rohr, J. and Hutchinson, C.R. (1997) Iterative type II polyketide synthases, cyclases and ketoreductases exhibit context-dependent behavior in the biosynthesis of linear and angular decapolyketides. *Chemistry & Biology*, **4**, 433-443.

32. Motamedi, H. and Shafiee, A. (1998) The biosynthetic gene cluster for the macrolactone ring of the immunosuppressant FK506. *European Journal of Biochemistry*, **256**, 528-534.

33. Narva, K.E. and Feitelson, J.S. (1990) Nucleotide sequence and transcriptional analysis of the RedD locus of

Streptomyces coelicolor A3(2). *Journal of Bacteriology*, **172**, 326-333.

33a. Piffaretti J.C., Arini A. and Frey J. (1988) pUB307 mobilizes resistance plasmids from Escherichia coli into Neisseria gonorrhoeae. *Mol Gen Genet*.**212**, :215-218.

34. Pospisil, S., Sedmera, P., Vokoun, J., Vanek, Z. and Budesinsky, M. (1987) 3-O-Demethylmonensin-A and 3-O-demethylmonensin-B produced by *Streptomyces cinnamonensis*. *Journal of Antibiotics*, **40**, 555-557.

35. Revill, W.P., Bibb, M.J. and Hopwood, D.A. (1995) Purification of a malonyltransferase from *Streptomyces coelicolor* A3(2) and analysis of its genetic determinant. *Journal of Bacteriology*, **177**, 3946-3952.

36. Rowe, C.J., Cortés, J., Gaisser, S., Staunton, J. and Leadley, P.F. (1998) Construction of new vectors for high-level expression in actinomycetes. *Gene*, **216**, 215-223.

37. Sanger, F. (1981) Determination of nucleotide sequences in DNA. *Science*, **214**, 1205-1210.

38. Schwecke, T., Aparicio, J.F., Molnár, I., König, A., Khaw, L.E., Haydock, S.F., Oliynyk, M., Caffrey, P., Cortés, J., Lester, J.B., Böhm, G.A., Staunton, J. and Leadlay, P.F. (1995) The biosynthetic gene cluster for the polyketide immunosuppressant rapamycin. *Proceedings of the National Academy of Sciences of the United States of America*, **92**, 7839-7843.

39. Shen, B., Summers, R.G., Wendtpienkowski, E. and Hutchinson, C.R. (1995) The *Streptomyces glaucescens* TcmKl polyketide synthase and TcmN polyketide cyclase genes govern the size and shape of aromatic polyketides. *Journal of the American Chemical Society*, **117**, 6811-6821.

40. Sherman, D.H., Malpartida, F., Bibb, M.J., Kieser, H.M. and Hopwood, D.A. (1989) Structure and deduced function of the granaticin-producing polyketide synthase gene cluster of *Streptomyces violaceoruber* Tu22. *EMBO Journal*, **8**, 2717-2725.

41. Sood, G.R., Robinson, J.A. and Ajaz, A.A. (1984) Biosynthesis of the polyether antibiotic Monensin-A - incorporation of [2-2-2H-2]-propionate, (R)-[2-2H-1]-propionate and (S)-[2-2H-1]- propionate. *Journal of the Chemical Society-Chemical Communications*, **21**, 1421-1423.

42. Spavold, Z., Robinson, J.A. and Turner, D.L. (1986) Biosynthesis of the polyether antibiotic narasin origins of the oxygen atoms and the mechanisms of ring formation. *Tetrahedron Letters*, **27**, 3299-3302.

43. Staden, R. (1996) The Staden sequence analysis package. *Molecular Biotechnology*, **5**, 233-241.

44. Stutzman-Engwall, K.J., Otten, S.L. and Hutchinson, C.R. (1992) Regulation of secondary metabolism in *Streptomyces* Spp and overproduction of daunorubicin in *Streptomyces peucetius*. *Journal of Bacteriology*, **174**, 144-154.

45. Swan, D.G., Rodriguez, A.M., Vilches, C., Mendez, C. and Salas, J.A. (1994) Characterization of a *Streptomyces antibioticus* gene encoding a type I polyketide synthase which

has an unusual coding sequence. *Molecular & General Genetics*, **242**, 358-362.

46. Takano, E., Gramajo, H.C., Strauch, E., Andres, N., White, J. and Bibb, M.J. (1992) Transcriptional regulation of the *redD* transcriptional activator gene accounts for growth phase-dependent production of the antibiotic undecylprodigiosin in *Streptomyces coelicolor* A3(2). *Molecular Microbiology*, **6**, 2797-2804.

47. Townsend, C.A. and Basak, A. (1991) Experiments and speculations on the role of oxidative cyclization chemistry in natural product biosynthesis. *Tetrahedron*, **47**, 2591-2602.

48. Walba, D.M. and Edwards, P.D. (1980) *Tetrahedron Letters*, **21**, 3531-3534.

49. Westley, J.W. (1974) *Journal of Antibiotics*, **27**, 597-604.

50. Westley, J.W. (1981) *Antibiotics IV. Biosynthesis*. Springer-Verlag, New York.

51. Wietzorrek, A. and Bibb, M. (1997) A novel family of proteins that regulates antibiotic production in *Streptomycetes* appears to contain an OmpR-like DNA-binding fold. *Molecular Microbiology*, **25**, 1181-1184.

52. Xue, Y.Q., Zhao, L.S., Liu, H.W. and Sherman, D.H. (1998) A gene cluster for macrolide antibiotic biosynthesis in *Streptomyces venezuelae*: Architecture of metabolic diversity. *Proceedings of the National Academy of Sciences of the United States of America*, **95**, 12111-12116.

TABLE I

gene	function	start	end
gdhA	glutamate dehydrogenase (partial)	1038	0
dapA	dihydrodipicolinate synthase	2140	1220
orf3	putative transcriptional activator	2211	3152
orf4	hypothetical protein	3264	3680
orf5	hypothetical protein	4307	3684
orf6	hypothetical protein	4570	4758
orf7	hypothetical protein	5058	5612
acpX	acyl carrier protein	6010	5693
ksX	ketoacyl synthase	8531	6045
monCI	probable epoxihydrolase/cyclase	9542	8643
monE	methyltransferase	10426	9596
monT	monensin resistance gene (ABC-	10656	12191
monRI	probable repressor	12205	12780
monAI	thioesterase	13829	13023
monAI	polyketide synthase loading &	14121	23198
	KS-L	14172	15486
	AT-L malonate specific	15777	16880
	ACP-L	17019	17276
	KS1	17358	18626
	AT1 methylmalonate specific	18960	19976
	DH1 (potential)	20019	20519
	KR1 (inactive)	21636	22241
	ACP1	22536	22793
monAI	polyketide synthase module 2	23205	29921
	KS2	23307	24569
	AT2 methylmalonate specific	24891	25913
	DH2	25953	26369
	ER2	27600	28463
	KR2	28485	29042
	ACP2	29313	29570
monAI	polyketide synthase modules 3 & 4	29974	42372
	KS3	30076	31347
	AT3 malonate specific	31798	32838
	DH3	32884	33465
	KR3	34692	35181
	ACP3	35553	35811
	KS4	35899	37170
	AT4 methylmalonate specific	37489	38511
	DH4	38557	38982
	ER4	40123	40986
	KR4	41005	41562
	ACP4	41848	42105
monAI	polyketide synthase modules 5 & 6	42448	54564
	KS5	42628	43890
	AT5 ethylmalonate specific	44221	45243
	DH5	45289	45744
	KR5	46785	47337
	ACP5	47593	47850

	KS6	47947	49218
	AT6 malonate specific	49579	50601
	DH6	50644	51075
	ER6	52222	53102
	KR6	53101	53661
	ACP6	54052	54306
monA	polyketide synthase modules 7 & 8	54614	66934
	KS7	54716	55978
	AT7 methylmalonate specific	56300	57319
	DH7	57358	57802
	KR7	59048	59608
	ACP7	59867	60124
	KS8	60185	61453
	AT8 malonate specific	61808	62839
	DH8	62882	63316
	ER8	64577	65437
	KR8	65456	66016
	ACP8	66404	66661
monA	polyketide synthase module 9	66952	72054
	KS9	67075	68340
	AT9 malonate specific	68698	69729
	KR9 (potential)	70735	71262
	ACP9	71536	71783
monH	probable regulator	72051	74993
monCI	FAD containing epoxidase	76541	75051
monBI	double bond isomerase	76960	76538
monBI	double bond isomerase	77450	77016
monA	polyketide synthase modules 11 &	88708	77447
	KS11	88612	87344
	AT11 methylmalonate specific	87022	85993
	KR11	85111	84562
	ACP11	84292	84035
	KS12	83962	82694
	AT12 methylmalonate specific	82354	81335
	DH12 (potential) delta	81286	80855
	ER12 (potential)	79618	78914
	KR12	78895	78337
	ACP12	78070	77812
monA	polyketide synthase module 10	93741	88816
	KS10	93636	92368
	AT10 methylmalonate specific	92040	91021
	KR10	90132	89584
	ACP10	89322	89068
monD	P450 oxygenase	94081	95273
monRI	probable activator	96141	95338
monA	thioesterase	96941	96138
orf29	cell wall biosynthesis capK	97580	98953
lipB	lipase B	99983	98991
orf31	ion pump	101433	100507
orf32	membrane structural protein	102581	101490
amtA	glycine amidinotransferase	102924	103450

TABLE II

GdhA, glutamate dehydrogenase (partial coding sequence) Length: 346 amino acids

```
  1  LTTRPDTKTA LSQKTALSQL LTEIEHRNPA QPEFHQAARE VLETLAPVIA
 51  ARPEYAEAGL IERLCEPERQ IVFRVPWQDD HGRVRVNRGF RVEFNSALGP
101  YKGGLRFHPS VNLGVIKFLG FEQIFKNALT GLGIGGGKGG SDFDPRGRSD
151  AEVMRFCQSF MTELYRHIGE HTDVPAGDIG VGGREIGYLF GQYRRITNRW
201  EAGVLTGKGR NWGGSLIRPE ATGYGNVLFA AAMLRERGET LEGRTAVVSG
251  SGNVAIYTIQ KLAALGANAV TCSDSSGYVV DEKGIDLDLL KQVKEVERAR
301  VDTYAQRRGA SARFVPGRRV WEVPADIALP SATQNELDAD DATALI
```

DapA, dihydrodopicolinate synthase Length: 307 amino acids

```
  1  MTLASSLEPT TEPLFNGLYV PLVTPFTDDL RLAPEALARL ADEALSAGAS
 51  GLVALGTTAE AATLTAEERE TVIRVCSAAC RAHGAPLIVG VGTNDTATAI
101  TALRELAARG DVAAALVPAP PYIRPGEAGT LAHFAALAEH GGLPLVVYDI
151  PYRTGQTLGA GTITALGRLP EVVGIKHATG SIDPTTMELL DSPLPGFAVL
201  GGDDIVLSPL VAAGAHGGIV ASANLRTADY AEMIALWRRG SAAPARALGA
251  DLARLSAALF TEPNPTVIKG VLHAQNRIPS PAVRMPLLAA SADSVRRAAP
301  LAASRK*
```

ORF3, putative transcriptional activator protein Length: 314 amino acids

```
  1  MLDVRRLHLL RELDRRGTIA AVAEALTFTA SAVSQQLGVL EREAGVPLLE
 51  RSGRRVVLTP AGRSLVAHAD AVLNRLEQAV AELAGARDGI GGPLRIGTFP
101  SGGHTIVPGA LAELASRHPA LEPMVREIDS ARVSDGLRAG ELDVALVHDY
151  DFVPATPDTT VDEVPLLEEP MYLVTHAADT ATDSGSGSTL AALLGPCAEV
201  PWITARDGTT GHAMAVRACQ AAGFQPRIRH QVNDFRTVLA LVAAGQGAGF
251  VPRMAAEPSP AGVVLTKLPL FRRSKVAFRA GGGAHPAIAA FVAAATTAVE
```

301 RMAGSRGPAG GSE*

ORF4, hypothetical protein Length: 139 amino acids

1 MADDAYLFLL PDRHPRLGAA LAAVGALECT ETPAVHAWLQ AHEASVSSEQ

51 VRILPADAET LIPKDAERLP VPLSEEEALK VEQECAPQTV TDMESELLAF

101 RETTQDWQAL VHRALTAGIP AQRIARLTGL DPEEIGRL*

ORF5, hypothetical protein Length: 208 amino acids

1 LAVAACAAVV LPIDAVVRIS AADVGVLVFF AYLLPYLAIT MTVFVSVAPE

51 QVRSWARREA RGTFLQRYVL GTAPGPGGSL FIAAAALVVA VLWLPGHLST

101 TFSALPRTLV ALALVVAAWI CVVVAFAVTF QADNLVENER ALEFPGERSP

151 AWADYVYFAL AAMTTFGTTD VDVTSRDMRR TVAANTVIAF VFNTVTVAIL

201 VSALGGR*

ORF6, hypothetical protein Length: 63 amino acids

1 MTVMDKLKQM LKGHEDKAGQ GIDKAGDFVD GKTQGKYSGQ VDTAQDKLRD

51 QFGSDQQEPP QR*

ORF7, hypothetical protein Length: 185 amino acids

1 MGTAQSQEQA AAPGACAAFV RFVLCGGGVG LASSFAVVAL ASWVPWALAN

51 ALVAVVSTVV ATELHARFTF GAGGRATWRQ HAQSAGSAAA AYAVTCVAMF

101 VLQQLVAAPG AVLEQVVYLS ASALAGVARF VVLRLVVFAR NRSLPAAAAV

151 RTARPVRRVP APVPATVAHA ASRPAGPAAL CPAA*

AcpX, acyl carrier protein (ACP) Length: 106 amino acids

1 MTSTDHTSGQ DATELEKQLA AATPEEREKL LTDTIRTQAG TLLNTTLSDD

51 SNFLENGLNS LTALELTKTL MTLTGMEIAM VAIVENPTPA QLAHHLGQEL

101 AHTTA*

KsX, ketoacyl-ACP synthase Length: 829 amino acids

```
  1  VANEEKLVEY LKWTTAELHQ AQQQLRELKA AQHEPIAVVS MACRLPGKTR
 51  TPDDLWDLVS EGRDAVTGFP DDRAWELPEE RPYAELGGFL DDAAGFDAGF
101  FDISDTEAVA TEPLQRLMLH LAWETVERGH IAPHTLRSTL TGVYVGATGH
151  DYATRLETAP DELLPYLGGG TSGSLVSGRI AYALGLEGPA ISVDTACSSS
201  LVALHLACQA LRRGECGLAL AGGGTVMSTP HTFHAFAHQK SLAQDGRCKP
251  FAAAADGMGL GEGVGLVLLE RLGDARKNGH PVLAVIRGSA VNQDGAGYGL
301  AAPNGPSQQH VIRAALADAG LTPDQIDAVE AHGTGTPIGD AIEVQALLAT
351  YGADRSPDRP LWLGSVKSNT GHTQGAAGAA ALIKMVQAFR HGTLPPTLHV
401  DRPTPLAAWK KGAVRLLTEA VDWPRREEPR RVGISAFATS GTNAHLILEE
451  PPVDEAPVPD AARDQTSPVA PELPVAWSLS ARTPEALRAQ AKALVTHLAA
501  TDPAPSPAEV AYSLAATRSP LEHRAVLTGT DHTELLAAAR ALAAGEDHPD
551  LVRSTPGAGP KKIAWHFDGR PADGVTTGAA PGAKPGATFG ATFGAAFGGA
601  EFHSAFPLFA SAFDEARALL DTHLPTPLPT PHSELARFAV HTALARLLLE
651  TGVRPHTLTG DGVGHIAAAY AAGILTLDDA CRLAAAHAAA AQAAEGEQPA
701  PPDAYEPVLK QLTFQRATLT LTSTAPADTP IASADYWHHH LTSPAPTAPP
751  TPETHTLLHL GALSPEGTQT SAVSALLTAL ARLHTTGGTV DWTPLVRRTP
801  HPRTIDLPTY SFQATRYWLH DHTAHAAV*
```

MonCII, probable epoxyhydrolase/cyclase Length: 300 amino acids

```
  1  VKNLRIPVSQ TVSLNVRYRP ADGPGAPGRP FLLLHGMLSN ARMWDEVAAR
 51  LAAAGHPAYA VDHRGHGESD TPPDGYDNAT VVTDLVAAVT ALDLSGALVA
101  GHSWGAHLAL RLAAEHPDLV AGLALIDGGW YEFDGPVMRA FWERTADVVR
151  RAQQGTTSAA DMRAYLRATH PDWSPTSIEA RLADYRVGPD GLLIPRLTST
201  QVMSIVAGLQ REAPADWYPK VTVPVRLLPL IPAIPQLSDQ VRAWVAAAEA
```

251 ALEQVSVRWY PGSDHDLHAG APDEIAADLL LLARSCEAMP GGKAGVRPA*

MonE, S-adeonosylmethionine-dependent methyltransferase Length: 277 amino acids

1 VNKTVAPEPS DIGHYYDHKV FDLMTQLGDG NLHYGYWFDG GEQQATFDEA

51 MVQMTDEMIR RLDPAPGDRV LDIGCGNGTP AMQLARARDV EVVGISVSAR

101 QVERGNRRAR EAGLADRVRF EQVDAMNLPF DDGSFDHCWA LESMLHMPDK

151 QQVLTEAHRV VKPGARMPIA DMVYLNPDPS RPRTATVSDT TIYAALTDIG

201 DYPDIFRAAG WTVLELTDIT RETAKTYDGY VEWIRAHRDE YVDIIGVEGY

251 ELFLHNQAAL GKMPELGYIF ATAQRP*

MonT, putative monensin resistance gene (ABC-transporter) Length: 512 amino acids

1 MSADLGARRW WAVGALVLAS MVVGFDVTIL SLALPAMADD LGANNVELQW

51 FVTSYTLVFA AGMIPAGMLG DRFGRKKVLL TALVIFGIAS LACAYATSSG

101 TFIGARAVLG LGAALIMPTT LSLLPVMFSD EERPKAIGAV AGAAMLAYPL

151 GPILGGYLLN HFWWGSVFLI NVPVVILAFL AVSAWLPESK AKEAKPFDIG

201 GLVFSSVGLA ALTYGVIQGG EKGWTDVTTL VPCIGGLLAL VLFVMWEKRV

251 ADPLVDLSLF RSARFTSGTM LGTVINFTMF GVLFTMPQYY QAVLGTDAMG

301 SGFRLLPMVG GLLVGVTVAN KVAKALGPKT AVGIGFALLA AALFYGATTD

351 VSSGTGLAAA WTAAYGLGLG IALPTAMDAA LGALSEDSAG VGSGVNQSIR

401 TLGGSFGAAI LGSILNSGYR GKLDLDGVPE QAHGAVKDSV FGGLAVARAI

451 KSNGLADSVR SAYVHALDVV LVVSGGLGLL GVVLAVVWLP RHVGQSTAKT

501 AESEHEAADA V*

MonRII, probable repressor protein Length: 192 amino acids

1 VPGLRERKKA RTKAAIQREA VRLFREQGYT ATTIEQIAEA AEVAPSTVFR

51 YFATKQDLVF SHDYDLPFAM MVQAQSPDLT PIQAERQAIR SMLQDISEQE

```
101  LALQRERFVL ILSEPELWGA SLGNIGQTMQ IMSEQVAKRA GRDPRDPAVR
151  AYTGAVFGVM LQVSMDWAND PDMDFATTLD EALHYLEDLR P*
```

MonAIX, thioesterase Length: 269 amino acids

```
  1  MDRGTAARAP QIGDEFGAAT GNGVWLRRYH AAAEAPVRLV CFPFAGGSAS
 51  YYFGLSGLLA PGVEVLAVQY PGRQDRHAEP CLASVAELAD GVVPHLPCDG
101  KPFALFGHSL GAIVAFEVAR RLRGPAGPGL PVHLFVSGGL ARPYRPAGRS
151  GAFGDADILA HLRAMGGTDE RFFRSPELQE LVLPALRADY RAVATYEAPG
201  PGRLDCPITA LIGDADERTS PEQAATWRER TGAAFDLRVL PGGHFYLDGC
251  QEQVAAVVTE ALTAGPGV*
```

MonAI, polyketide synthase multi-enzyme MONS1, housing loading module and extension module 1 Length: 3026 amino acids

```
  1  MAASASASPS GPSAGPDPIA VVGMACRLPG APDPDAFWRL LSEGRSAVST
 51  APPERRRADS GLHGPGGYLD RIDGFDADFF HISPREAVAM DPQQRLLLEL
101  SWEALEDAGI RPPTLARSRT GVFVGAFWDD YTDVLNLRAP GAVTRHTMTG
151  VHRSILANRI SYAYHLAGPS LTVDTAQSSS LVAVHLACES IRSGDSDIAF
201  AGGVNLICSP RTTELAAARF GGLSAAGRCH TFDARADGFV RGEGGGLVVL
251  KPLAAARRDG DTVYCVIRGS AVNSDGTTDG ITLPSGQAQQ DVVRLACRRA
301  RITPDQVQYV ELHGTGTPVG DPIEAAALGA ALGQDAARAV PLAVGSAKTN
351  VGHLEAAAGI VGLLKTALSI HHRRLAPSLN FTTPNPAIPL ADLGLTVQQD
401  LADWPRPEQP LIAGVSSFGM GGTNGHVVVA AAPDSVAVPE PVGVPERVEV
451  PEPVVVSEPV VVPTPWPVSA HSASALRAQA GRLRTHLAAH RPTPDAARVG
501  HALATTRAPL AHRAVLLGGD TAELLGSLDA LAEGAETASI VRGEAYTEGR
551  TAFLFSGQGA QRLGMGRELY AVFPVFADAL DEAFAALDVH LDRPLREIVL
601  GETDSGGNVS GENVIGEGAD HQALLDQTAY TQPALFAIET SLYRLAASFG
```

651 LKPDYVLGHS VGEIAAAHVA GVLSLPDASA LVATRGRLMQ AVRAPGAMAA

701 WQATADEAAE QLAGHERHVT VAAVNGPDSV VVSGDRATVD ELTAAWRGRG

751 RKAHHLKVSH AFHSPHMDPI LDELRAVAAG LTFHEPVIPV VSNVTGELVT

801 ATATGSGAGQ ADPEYWARHA REPVRFLSGV RGLCERGVTT FVELGPDAPL

851 SAMARDCFPA PADRSRPRPA AIATCRRGRD EVATFLRSLA QAYVRGADVD

901 FTRAYGATAT RRFPLPTYPF QRERHWPAAA GVGQQPETPE LPESSESSEQ

951 AGHEREEGAR AWGGPEGRLA GLSVNDQERV LLGLVTKHVA VVLGDASGTV

1001 QAARTFKQLG FDSMAAAELS ERLGTETGLP LPATLTFDYP TPLAVAAHLR

1051 AELTGTPAPA GSAPATGALG AGDLGTDEDP VAIVAMSCRY PGGAGTPEDL

1101 WRLVADGADA IGDFPTDRGW DLARLFHPDP DRSGTSCTRQ GGFLYDAADF

1151 DAEFFDISPR EALAVDPQQR LLLECAWEAF ERAGLDPRAL KGSPTGVFVG

1201 MTGQDYGPRL HEPSQATDGY LLTGSTPSVA SGRLSFSFGL EGPALTVDTA

1251 CSSSLVTLHL AAQALRRGEC DLALAGGATV LATPGMFTEF SRQRGLAPDG

1301 RCKPFAAGAD GTGWAEGVGL VLLERLSEAR RKGHAVLAVI RGSAINQDGA

1351 SNGLTAPNGP SQQRVIRAAL AAARLTADEV DVVEAHGTGT TLGDPIEAQA

1401 LLATYGQGRS AERPLWLGSV KSNIGHTQAA AGVAGVIKMV MAMRHDLLPA

1451 TLHVDEPSGH VDWSTGAVRL LTEPVVWPRG ERPRRAAVSS FGISGTNAHL

1501 VLEEAGQDEY VAGAADDAGP VDGAVLPWVV SGRTGAALRE QARRLRELVT

1551 GGSADVSVSG VGRSLVTTRA VFEHRAVVVG RDRDTLIGGL EALAAGDASP

1601 DVVCGVAGDV GPGPVLVFPG QGSQWVGMGA QLLGESAVFA ARIDACEQAL

1651 SPYVDWSLTE VLRGDGRELS RVDVVQPVLW AVMVSLAAVW ADHGVTPAAV

1701 VGHSQGEIAA VVVAGALTLE DGAKIVALRS RALRQLSGGG AMASLGVGQE

1751 QAAELVEGHP GVGIAAVNGP SSTVISGPPE QVAAVVADAE ARELRGRVID

1801 VDYASHSPQV DAITDELTHT LSGVRPTTAP VAFYSAVTGT RIDTAGLDTD

1851 YWVTNLRRPV RFADAVTALL ADGHRVFIEA SSHPVLTLGL QETFEEAGVD

1901 AVTVPTLRRE DGGRARLARS LAQAFGAGCA VRWENWFPAT GTSTVELPTY

1951 AFQRRRYWLE APTGTQDAAG LGLAAAGHPL LGAATEIADG DIRLLTGRIS

2001 RHSHPWLAQH TLFGAAVVPA SVLAEWALRA ADEAGCPRVD DLTLRTPLVL

2051 PETAGVQVQI VVGPADARDG HRDFHVYARP DGKDASEGEG IAEGEGASEG

2101 EGASGGTDAP WTCHADGRLV AEPTGTASED SPDTVWPPPG AEPVDLGDFY

2151 ERAAATGVGY GPVFTGLRAL WRRDGELFAE AVLPQEAPET AGFGMHPALL

2201 DAALHPALLG ERPAEEDKVW LPFTLTGVTL WATGATSVRV RLTPLDDDPD

2251 ASADGRAWRV GVSDPTGAEV LTCEALVAVA AGRRELRAAG ERVSDLYAVE

2301 WVPVPGPGPV GEGADFSGWA GLGECGERWE CVGRVERWYE DLDALGAAVE

2351 GGASVPSVVL ATAAAAPGGA GDGAADALSA VRWTGALLDQ WLADARFADA

2401 RLVVITSGAV ATGDDFLPDP AAAAVRGLVE QAQVRHPGRI LLVDTEAGAG

2451 LGVGAGVDDA LLEQAVAMAL GADEPQLALR AGRVLAPRLT APQDAAVTEA

2501 ARPLDPDGTV LITGPAGAPV ADLAEHLVRT GQCRHLLLLP GDGELEEMAE

2551 ELRGLGATVD LSTADPADPT ALAEVVAAVE GDHPLTGVIH ATGVVDAFDP

2601 GDSASDLMID SASDSFAEAW SSRAGVTAAL HTATAHLPLD LFAVLSPAGA

2651 DLGIARSAAA AGADAFSAAL ALRRHTTVTT DTTAPPRTTA PPRTTASPRT

2701 TALSSSRTTG VALAYGPPTA PRPGIKGTAP GRIPVLLDAA RAHGGGSPLL

2751 GARLAARALA AESAAEGVAG LPAPLRALAV AAAAAGAPTR RTAADRKPPA

2801 DWPARLAPLS APEQLRLLID AVRTHAAAVL GRTDPEALRG DATFKQLGLD

2851 SLTAVELRNR LVEDTGLRLP TALVFRYPTP AAIAAHLRER LTSPSETTAT

2901 QRSGGQTPAA GQASSALAPG GSAAGPPAAD TVLSDLTRME NTLSVLAAQL

2951 PHTETGEITT RLEALLTRWK TTNATANDSG DGNGGDDDAA ERLKAASADQ

3001 IFDFIDNELG VGHGTSRVTP TPKAG*

MonAII, polyketide synthase multi-enzyme MONS2, housing extension module 2 Length: 2239 amino acids

```
   1  MASEEQLVEY LRRVTTELHD TRRRLVQEED RRQEPVALVG MACRFPGGVA
  51  SPEDLWDLVA AGKDAIEDFP TDRGWDLEAL YDPDPAAYGT SYVRHGGFVD
 101  DAGSFDADFF GISPREALAM DPQQRLMLET SWELFERAGI EPVSLKGSRT
 151  GVYAGVSSED YMSQLPRIPE GFEGHATTGS LTSVISGRVA YNYGLEGPAV
 201  TVDTACSASL VAIHLASQAL RQRECDLALA GGVLVLSSPL MFTEFCRQRG
 251  LAPDGRCKPF AAAADGTGFS EGIGLLLLER LSDARRNGHK VLAVIRGSAV
 301  NQDGASNGLT APNDAAQEQV IRAALDNARL TPSEVDAVEA HGTGTKLGDP
 351  IEAGALLATY GQHRARPLLL GSLKSNIGHT HATAGVAGVI KTVMAIRNGL
 401  LPATLHVEEL SPHVDWDAGA VEVVTEPTPW PETGHPRRAG VSAFGISGTN
 451  AHLILEEAPP EEDVPAPVVV ESGGVVPWVV SGRTPEALRE QARRLGEFVA
 501  GDTDALPNEV GWSLATTRSV FEHRAVVVGR DRDALTAGLG ALAAGEASAG
 551  VVAGVAGDVG PGPVLVFPGQ GAQWVGMGAQ LLDESAVFAA RIAECERALS
 601  AHVDWSLSAV LRGDGSELSR VEVVQPVLWA VMVSLAAVWA DYGVTPAAVI
 651  GHSQGEMAAA CVAGALSLED AARIVAVRSD ALRQLQGHGD MASLSTGAEQ
 701  AAELIGDRPG VVVAAVNGPS STVISGPPEH VAAVVADAEA RGLRARVIDV
 751  GYASHGPQID QLHDLLTERL ADIRPTNTDV AFYSTVTAER LTDTTALDTD
 801  YWVTNLRQPV RFADTIEALL ADGYRLFIEA SAHPVLGLGM EETIEQADMP
 851  ATVVPTLRRD HGDTTQLTRA AAHAFTAGAD VDWRRWFPAD PAPRTIDLPT
 901  YAFQRRRYWL ADTVKRDSGW DPAGSGHAQL PTAVALADGG VVLNGRVSAE
 951  RGGWLGGHVV AGTVLVPGAA LVEWVLRAGD EAGCPSLEEL TLQAPLVLPE
1001   SGGLQVQVVV GAADEQGGRR DVHVYSRSEQ DASAVWQCHA VGELGRASVA
1051   RPVRQAGQWP PAGAEPVEVG GFYEGVAAAG YEYGPAFRGL RAMWRHGDDL
```

1101 LAEVELPEEA GSPAGFGIHP ALLDAALHPL LAQRSRDGAG AGAHGGQVLL
1151 PFSWSGVSLW ASEATTVRVR LTGLGGGDDE TVSLTVTDPA GGPVVDVAEL
1201 RLRSTSARQV RGSAGPGADG LYELRWTPLP EPLPVPAPAN GRDVAADLSG
1251 CAVLGELVAE PGPGIDLEGC PCYPGVGALA DNASPPSMIL APVHSDTTGG
1301 DGLALTERVL RVIQDFLAAP SLEQKQTRLA FVTRGAADTG STTGGSAAPA
1351 EAVDPAVAAV WGLVRSAQSE NPGRFVLLDT DAPLDQASVA PLVDAVRSAV
1401 EADEPQVALR GGRLLVPRWA RAGEPVELAG PAGARAWRLV GGDSGTLEAV
1451 VAEACDDIVL RPLAPGQVRV AVHTAGVNFR DVLIALGMYP DPDALPGTEA
1501 AGVVTEVGPG VTRLSVGDRV MGMMDGAFGP WAVADARMLA PVPPGWGTRQ
1551 AAAAPAAFLT AWYGLVELAG LKAGERVLIH AATGGVGMAA VQIARHVGAE
1601 VFATASPGKH AVLEEMGIDA AHRASSRDLA FEDAFRQATD GRGVDVVLNS
1651 LTGELLDASL RLLGDGGRFV EMGKSDPRDP ELVALEHPGV SYEAFDLVAD
1701 AGPERLGLML DRLGELFAGG SLVPLPVTAW PLGRAREALR HMSQARHTGK
1751 LVLDVPAPLD PDGTVLVTGG TGTIGAAVAE HLARTGESKH LLIVSRSGPA
1801 AHGAEELVSR IAEFGAEATF VAADVSEPDA VAALIEGIDP AHPLTGVVHA
1851 AGVLDNALIG SQTTESLTRV WAAKAAAAQQ LHEATRESRL GLFVMFSSFA
1901 STMGTPGQAN YSAANAYCDA LAALRRAEGL AGLSVAWGLW EATSGLTGTL
1951 SAADRARIDR YGIRPTSAAR GCALLAAARA HGRPDLLAMD LDARVPAASD
2001 APVPAVLRTL AAAGAPATAR PTAAAAADGA TDWSGRLAGL TEEARLELLT
2051 ELVCTHAAGV LGHADAGAVQ VDAPFKELGF DSLTAVELRN RIAAATGLKL
2101 PAALVFDYPQ ARVLAAHLAE RLVPEGAGAM GGVSGAEGVR DAYGAGGPGG
2151 DMTAQVLLEV ARVEHTLSAA VPHGLDRAAV AARLEALLAR CTATTAATGA
2201 AGAAVEGDGD SDGDGAVDQL ETATAEQVLD FIDNELGV*

MonAIII, polyketide synthase multi-enzyme MONS3, housing extension modules 3 and 4 Length: 4133 amino acids

```
   1  MVSEEKLVDY LKRVSADLHA TRQRLREAEE RGQEPVAVVE AACRYPGGIR
  51  TPEDLWDLVA AGGNALGAFP DNRGWDLRRL FHPDPDHPGT TYAREGGFLH
 101  DADLFDPEFF GISPREAAVL DPQQRLLLEC AWEALERAGI DPRSLQGSRT
 151  GVYAGAALPG FGTPHIDPAA EGHLVTGSAP SVLSGRLAYT FGLEGPAVTI
 201  DTACSSSLVA VHLAAHALRQ RECDLALAGG VTVMTTPYVF TEFSRQRGLA
 251  ADGRCKPFAA AADGTAFSEG AGLLVLERLS DARRAGHRVL AVIRGSAVNQ
 301  DGASNGLTAP NGPAQQRVIR AALAGARLSP AEVDAVEAHG TGTRLGDPIE
 351  ADALLATYGQ ERHGGRPLWL GSVKSNIGHT QGAAGAAGLI KMVQALRHET
 401  LPATLYADEP TPHADWESGA VRLLSAPVAW PRGEHGEHTR RAGISSFGIS
 451  GTNAHLILEE APAADAEGAG GDGDGDGGGV RPVVRVGATG PREEQGQGQG
 501  QEQHQQQRQQ RQRSSMMPTP HLPWLLSARS PAALRAQADA LANHVAHADH
 551  SIADIGGTLL RRTLFEHRAV VLGTDRDERA AALAALAAGR AHPALTRAAG
 601  PARNGGTAFL FTGQGSQRPG MGRQLYDTFD VFAESLDETC ARLDPLLEQP
 651  LKPVLFAPAD TAQAAVLHGT GMTQAALFAL EVALYRQVTS FGIAPSHLTG
 701  HSVGEIAAAH VAGVFSLADA CTLVAARGRL MQALPAGGAM LAVQAAEDDV
 751  LPLLAGQEER LSLAAVNGPT AVVVSGEAAA VGEVEKALRG RGLKTKRLNV
 801  SHAFHSPLIE PMLDDFREVA RGLTFHAPTL PVVSNLTGRL ADAELMADAE
 851  YWVRHVRRPV RFHDGLRALS EQGVVRYLEL GPDPVLATMV QDGLPAPAEG
 901  EEPEPVVAAA LRSKHDEGRT LLGAVAALHT DGQPADLTAL FPADAGQVPL
 951  PTYRFQRRRY WRVAPDAAAP ARAAGLQETG HPLLPAVIRQ ADGGILLAGR
1001  LSLRTHPWLA DHTIAGGVPL PATAFVELAL LAGRHAACDT IDDLTLETPL
1051  LLDDTGTGVG AAVGAGADAL VDAIEVQLAL GAPDGSGRRA LTVHSRPADD
1101  AADDGDAADA ADAAGRGGPG GSGDLGDPGD PGDLGDGGGS RGWRRHATGI
```

1151 LSAGPAAEPA APDAAPWPPA DATALDVDAL YARLDAQGYS YGPAFRAVHA

1201 AWRHGDDLYA DVRLADEQRA EADAFALHPA LLDAALHAVD ELYRGSEGRG

1251 QEQGQGGQEP EQGRGDADAP VRLPFSFSDI RHHATGATRL WVRLSPQGDD

1301 RLRLSLTDGE GGQVATVDAL QLRLIPADRW RAARPTTAAP LYHLDWHELP

1351 LPEPAETDPA AHSWAVLGAH DAGLAPAAHY PDLAALKAAV EAGEPVPDIV

1401 FAPFPAQGTE TDVPAQVRAH ARHALELLRD WLTTEAFAAA RLVVLTTGAV

1451 TARPEDGPAD LATAPVWGLV RAAQAEQPDH VVLVDIDKDI DKDTDEETDQ

1501 ATDAGTASRH ALPAALAAAA AQAETQLALR AGTVLVPRLA VVPPRTDTPA

1551 LHATAPESTT DTVDSTGIAG AAESGGTVLI TGGTGGLGQA VARHLAAAHG

1601 ARHLLLVSRR GDAAEGVAEL RADLADDGVD VRVAACDITD RDALAGLLAD

1651 IPAAHPLTAV VHTAGVIDDS LITAMTPERL DAVLAPKADA AWHLHELTRD

1701 KDLSAFVLFS SGASVLGNGG QANYAAANTF LNTLAEHRRA AGLAATSVAW

1751 GLWESASGGM AARLGDADRA RIHRTGVTGL TDEQALALFD AALTAEHPTV

1801 LATRFDRAVL RGQAAARTLQ PALRGLVRTP RPTASAGAIG STAATGSATD

1851 ENAPSSWAAR LARLSAADRD RALNELIREQ IATVLAHPSP DTIELGRAFQ

1901 ELGFDSLTAL ELRNRLSTAT GIRLPATLVF DHPSPTALVR HLHSHLPDEA

1951 QHTSPTAPGA SAEGTAATAT GIDDDPIAIV GMACRYPGGV TSPEQLWQLV

2001 ATGTDAIGPF PEDRGWDTAG LFDPDPDQVG HSYTREGGFL YDAARFDAGF

2051 FGISPREAAA TDPQQRLLLE TAWQAFEHAG IDPAALRGTP CGVITGIMYD

2101 DYGSRFLARK PDGFEGRIMT GSTPSVASGR VAYTFGLEGP AITVDTACSS

2151 SLVAMHLAAQ ALRQGECELA LAGGVTVMAT PNTFVEFSRQ RGLAPDGRCK

2201 PFAAAADGTG WGEGAGLVVL ERLSDARRKG HRVLALLRGS AVNQDGASNG

2251 MTAPNGPSQE RVIRTALAGA GRGPEDIDVV EAHGTGTTLG DPIEAQALLA

2301 TYGQGRPEDR PLWLGSVKSN IGHTQAAAGV AGVIKMVMAL RHEQLPTTLH

2351 ADEPTPHVQW DGGGVRLLTE PVPWSRGERT RRAGVSSFGI SGTNAHLILE

2401 EPPEEDLPEP VAAEPGGVVP WVVSGRTPDA LREQARRLGE FVVGAGDVSA

2451 AEVGWSLATT RSVFEHRAVV AGRDRDDLVA GMQALAAGET PTDVVSGAAA

2501 SSGAGPVLVF PGQGSQWVGM GAQLLDESPV FAARIAECEQ ALSAYVDWSL

2551 SDVLRGDGSE LSRVEVVQPV LWAVMVSLAA VWADYGVTPA AVVGHSQGEM

2601 AAACVAGALS LEDAARIVAV RSDALRQLQG HGDMASLGTG AEQAAELIGD

2651 RPGVVVAAVN GPSSTVISGP PEHVAAVVAE AEARGLRARV IDVGYASHGP

2701 QIDQLHDLLT EGLADIRPAN TDVAFYSTVT AERLTDTTAL DTDYWVTNLR

2751 QPVRFADTIE ALLADGYRLF IEASAHPVLG LGMEETIEQA DIPATVVPTL

2801 RRDHGDTTQL TRAAAHAFTA GADVDWRRWF PADPTPRTVD LPTYAFQHQH

2851 YWLEEPSGLT GDAADLGMVA AGHPLLGACV ELAESDSYLF TGRLSRRAPS

2901 WLAEHVVAGT VLVPGAALVE WVLRAGDEAG CPTIEELTLQ APLVLPESGG

2951 LQVQVVVGAT DEQSGRRDVH VYSRSEQDAS AVWVCHAVGV VSSEMPEAAA

3001 ELSGQWPPAG AEAVDVEDFY ARAAEAGYAY GPAFQGLRAL WRHGTELFAE

3051 VVLPEQAGGH DGFGIHPALL DAALHPLMLL DRPADGQMWL PFAWSGVSLN

3101 ADRATHVRVR LSPRGEAAER DLRVVIADAT GAPVLTVDAL TLRAADPGRL

3151 GAAARGGVDG LYTVDWTPLP LPQPLPLPRT DAGGSADWVI LSDNSSAALA

3201 DAVSSATAAG GGAPWALLAP VGGGSADDGL PVVRRTLSLV QEFLAAPELT

3251 ESRLVIVTRG AVATDADGDV AASAAAVWGL IRSAQSENPG RFVLLDVEEE

3301 HLHPDGGELP YAALRHAVEE LDEPQLALRS GKFLVPRMTP AAAPEELVPP

3351 VGTSGWRLGT SGTATLENLS VIDAPEAFAP LEPGQVRISV RAAGMNFRDV

3401 LIALGMYPDK GTFAGSEGAG HVTEVGPGVT HLSVGDRVMG LFEGAFAPLA

3451 VADARMVVPI PEGWSFQEAA AVPVVFLTAW YGLVDLGRLR AGESLLIHAG

3501 TGGVGMAATQ IARHLGAEVF ATASPAKHGV LDGMGIDAAH RASSRDLDFE

3551 ETLRAATGGR GMDVVLNSLA GEFTDASLRL LAEGGRMVDM GKTDKRDPDR

3601 VAAEHAGAWY RAFDLVPHAG PDRIGEMLAE LGELFASGAL APLPVQTWPL

3651 GRAREAFRFM SQAKHTGKLV LEIPPALDPD GTVLITGGTG VLAAAVAEHL

3701 VREWGVRHLL LAGRRGSEAP GSSELAEELT ELGAEVTFAA ADVSDPDAVA

3751 ELVGKTDPAH PLTGVIHAAG VLDDAVVTAQ TPESLARVWA AKATAAHLLH

3801 EATREARLGL FLVFSSAAAT LGSPGQANYA AANAYCDALV RQRRAEGLAG

3851 LSIGWGLWQT ASGMTGHLGE TDLARMKRTG FTPLTTEGGL ALLDAARAHG

3901 RPHVVAVDLD ARAVAAQPAP SRPALLRALA AGATPGARTA RRTAAAGSVA

3951 PAGGLADRLA GLPHPERRRL LLDLVRGNVA GVLGHSDHDA VRPDTSFKEL

4001 GFDSLTAVEL RNRLAAATGL KLPAALVFDY PESATLVDHL LERLSPDGAP

4051 PPVKDAADPV LNDLGRIESS LDALALDADA RSRVTRRLNT LLSKLNGAAT

4101 AGSPADVTDL DALDALDDVS DDEMFEFIDR EL*

MonAIV, polyketide synthase multi-enzyme MONS4, housing extension modules 5 and 6 Length: 4039 amino acids

1 MSSAEESSPD VSGTGVSGTG ESATGTSSTE AKLRQYLKRV TVDLGQARRR

51 LREVEERAQE PIAIVSMACR FPGDTRTPEA LWDLVAEGGD AIDDFPTNRG

101 WDLESLYHPD PDHPGTSYVR RGGFLYDAPA FDASFFGISP REALAMDPQQ

151 RVLMETAWQL LERAGIDPAS LKLSATGVYI GAGVLGFGGA QPDKTVEGHL

201 LTGSALSVLS GRISFTLGLE GPSVSVDTAC SSSLVSMHLA AQALRQGECD

251 LALAGGVTVM STPGAFTEFS RQGALSPDGR SKAFAASADG TGFSEGAGLL

301 LLERLSDARR NGHKVLAVIR GSAVNQDGAS NGLTAPNGPS QERVIRAALA

351 NAGLGAAEVD AVEAHGTGTK LGDPIEAGAL LATYGRDRDE DRPLWLGSVK

401 SNIGHPQGAA GVAGVIKMVM ALQRELLPAT LYVDEPTPHV DWSSGSVRLL

451 TEPVPWTRGE RPRRAGVSAF GMSGTNAHVI LEEAPPEEAA AAETPAEGTG

501 AVVPWVVSGR GEEALRAQAA QLAEHVRDDD QRPASPLEVG WSLATTRSVF

551 ENRAVVVGDD RDALLDGLRS LAAGEASPDV VSGAVGPTGP GPVMVFPGQG

601 GQWVGMGARL LDESPVFAAR IAECEQALSA YVDWSLTDVL RGDGSELARI

651 DVVQPVLWAV MVALAAVWAD QGIEPAAVVG HSQGEIAAAC VVGAISLDEA

701 ARIVAVRSVL LRQLSGRGGM ASLGMGQEQA ADLIDGHPGV VVAAVNGPSS

751 TVISGPPEGI AAVVADAQER GLRARAVASD VAGHGPQLDA ILDQLTEGLA

801 GIRPAATDVA FYSTVTAGHL TDTTELDTAY WVRNVRRTVR FADTIDALLA

851 DGYRLFIEVS PHPVLNLALE GLIERAAVPA TVVPTLRRDH GDTTQLARAA

901 AHAFAAGADV DWRRWFPADP APRTVDLPTY AFQRQDFWPA PAGGRSGDPA

951 GLGLAASGHP LLGASVGLAS GDVHLLSGRV SRQSAAWLDD HVVAGQALVP

1001 GAAQVEWVLR AGDDAGCSAL EELTLQTPLV LPDTGGLRIQ VVVEAADAHG

1051 RRDVRLFSRP DDDDAFASTH PWTCHATGVL APAPTDGTNG TRDAADTLDG

1101 AWPPADAEPV PADDLYAQAD RTGYGYGPAF RGVRALWRHG KDVLAEVTLP

1151 KEAGDPDGFG IHPALLDAVL QPAALLLPPT DAEQVWLPFA WNDVALHAVR

1201 ATTVRVRLTP LGERIDQGLR ITVADAVGAP VLTVRDLRSR PTDTGRLAAA

1251 ATRDRHGLFD LEWIAPENAA ENAAGPARDA SEGWVTLGED AASLADLLAS

1301 VEAGAPAPQL VAAPVEPDRT DDGLALATHV LDLVQTWLAS PLHDSRLVLV

1351 TRGAVTDADV DVAAAAVWGL VRSAQSEHPG RFTLIDLGPD DTLAAAMQAA

1401 HLEEPQLAVH GGEIRVPRLV RATTDPTAPN GTPEADRTAD PSEGLHRNGT

1451 VLITGGTGVL GRLVAEHLVT EWGVRHLLLA SRRGDQAPGS AELRARLSEL

1501 GASVEIAPAD VGDAEAVAAL IASVDPAHPL TGVIHAAGVL DDAVITAQTP

1551 ESLARVWATK ATAARHLHEA TRETPLDFFV VFSSAAASLG SPGQANYAAA

1601 NAYCDALVQH RRAQGLAGLS IAWGLWQATS GMTGQLSETD LARMKRTGFA

1651 ALTDEGGLAL LDAARAHDRA YVVAADLDPR AVTDGLSPLL RALTAPATRR

1701 RVASEGLADG ALATRLAGLD ADGRLRLLTD VVREYVAAVL GHGSAARVGV

1751 DIAFKDLGFD SLTAVELRNR LSAACDVRLP ATLIFDHPTP QALATHLVDR

1801 LAGSTSATTT VNATAPAAAH VAAGADVDAD TDDPVAIVAM TCRFPGGVAS

1851 PDDLWDLLDA RKDAMGAFPT DRGWDLERLF HPDPDHPGTS YTDQGGFLPD

1901 AGDFDAAFFG INPREALAMD PQQRLLLEAS WEVLERAGID PTTLKGTPTG

1951 TYVGLMYHDY AKSFPTADAQ LEGYSYLAST GSMVSGRVAY TLGLEGPAVT

2001 VDTACSSSLV SIHLATQALR HGECDLALAG GVTVMADPDM FAGFSRQRGL

2051 SPDGRCKAYA AAADGVGFSE GVGVLLLERL SDARRHGRRV LGVVRGSAVN

2101 QDGASNGLTA PNGPSQERVI RQALASGGLS SVDVDVVEGH GTGTTLGDPI

2151 EAQALLATYG QGRPEDRPLW LGSVKSNIGH TQAAAGVAGV IKMVMAMRHG

2201 VVPASLHVDV PSPHVEWDSG AVRLAVESVP WPQVEGRPRR AGVSSFGASG

2251 TNAHVIVESV PDGLEEDSVS VGGEALETET DGRLVPWVVS ARSPQALRDQ

2301 ALRLRDFASD ASFRAPLADV GWSLLKTRAL HEHRAVVVGA ERAELIAALE

2351 ALATGEPHAA LVGPACSQAR VGGDDVVWLF SGQGSQLVGM GAGLYERFPV

2401 FAAAFDEVCG LLEGPLGVEA GGLREVVFRG PRERLDHTVW AQAGLFALQV

2451 GLARLWESVG VRPDVVLGHS IGEIAAAHVA GVFDLADACR VVGARARLMG

2501 GLPEGGAMCA VQATPAELAA DVDGSAVSVA AVNTPDSTVI SGPSDEVDRI

2551 AGVWRERGRK TKALSVSHAF HSALMEPMLA EFTEAIRGVK FRQPSIPLMS

2601 NVSGERAGEE ITDPEYWARH VRNAVLFQPA IAQVADSAGV FVELGPAPVL

2651 TTAAQHTLDE SDSQESVLVA SLAGERPEES AFVEAMARLH TAGVAVDWSV

2701 LFAGDRVPGL VELPTYAFQR ERFWLSGRSG GGDAATLGLV AAGHPLLGAA

2751 VEFADRGGCL LTGRLSRSGV SWLADHVVAG AVLVPGAALV EWALRAGDEV

2801 GCVTVEELML QAPLVVPEAS GLRVQVVVEE AGEDGRRGVQ IYSRPDADAV

2851 GGDDSWICHA TGVLSPESAR LDTELGGVWP PAGAEPLDVD GFYAQAGEAG

2901 YGYGPAFRGL RAVWRHGQDL LAEVVLPEAA GAHDGYGIHP ALLDATLHPL

2951 LAARFMDGSE DDQLYVPFGW AGVSLRAVGA TTVRVRLRPV GESVDQGLSV

3001 TVTDATGGPV LSVDSLQTRP VKPSQLAAAQ QPDVRGLFTV EWTPLPQTDA

3051 DGEADWVVLS DGVGRLADVV SAAGGEAPWA VVAPVDASVG DGREGLDGRL

3101 VVERVLSLVQ EFLALPELAE SRLLVVTRGA VATGVDGDGD VDASAAAVWG

3151 LVRSAQSENP GRFILLDVDG DGDDQGPDLN GRHLPHATLR HAAEELDEPQ

3201 LALREGTLYV PRLTQARQSA ELVVPPGEPA WRLRMVHDGS LDALAAVACP

3251 EALEPLAPGQ VRIAVHAAGI NFRDVLVALG MVPAYGAMGG EGAGVVTEVG

3301 PEVTHVSVGD RVMGVFEGAF GPVVIAEARM VTPVPQGWDM REAAGIPAAF

3351 LTAWYGLVEL AGLKAGERVL VHAATGGVGM AAVQIARHVG AEVFATASPG

3401 KHAVLEEMGI DAAHRASSRD LAFEGTFREA TGGRGMDVVL NSLAGEFIDA

3451 SLRLLGDGGR FLEMGKTDVR AAEEVAAEHA DVSYTAYDLV GDAGPDRISN

3501 MLDKLVELFA SERLKPLPVR SWPLDKAQEA FRFMSQAKHT GKLVLEIPPA

3551 LDPEGTVLVT GGTGALGQVV AEHLVREWGV RHLLLASRRG PEAPGSDELA

3601 SKLTGLGAEV TIVAADVSDP ASVVELVGKT DPSHPLTGVV HAAGVLEDGV

3651 VTAQTPEGLA RVWAAKAAAA ANLHEATREM RLGLFVVFSS AAATLGSPGQ

3701 ANYAAANAYC DALMQHRRAV GQVGLSVGWG LWEAPDAKPG VAADAKASAA

3751 TVGKASALSD GTNGSAPQDT TGTAPQGMTG GLTDTDVARM ARIGVKGMSN

3801 AHGLALFDAA HRHGRPHLVG FNLDLRTLAT HPLHTRPALL RGLATPTAGG

3851 ASRPTATAGG QPADLAGRLA ALSPSDRHHT LVRLIREQAA TVLGHHPDSL

3901 TTGSTFKELG FDSLTAVELR NRLSAATGLR LPAGLVFDHP DADILAEHLG

3951 AQLAPDGDTP AGAEATDPVL RDLAKLENAL SSTLVEHLDA DAVTARLEAL

4001 LSNWKAASAA PGSGSTKEQL QVATTDQVLD FIDKELGV*

MonAV, polyketide synthase multi-enzyme MONS5, housing extension modules 7 and 8 Length: 4107 amino acids

```
   1  MASEEELVDY LKRVAAELHD TRQRLREVED RRQEPVAVVG MACRFPGGIE
  51  TPEGLWELVA AGDDAIEPFP TDRGWDLEGI YHPDPDHPGT CYVREGGFLA
 101  APDRFDSDFF GFSPREALAS SPQLRLLLET SWEALERAGI NPASLKGSPT
 151  GVYVGAATTG NQTQGDPGGK ATEGYAGTAP SVLSGRLSFT LGLEGPAVTV
 201  ETACSSSLVA MHLAANALRQ GECDLALAGG VTVMSTPEVF TGFSRQRGLA
 251  PDGRCKPFAA AADGTGWGEG AGLILLERLS DARRKGHKVL AVIRGSAINQ
 301  DGASNGFTAP NGPSQRRVIR QALSSAHLST SEIDVVEAHG TGTRLGDPIE
 351  AEALIATYGK EREDDRPLWL GSVKSNIGHT QAAAGVAGVI KMVMALQREL
 401  LPATLNVDEP TPHVQWEGGG VRLLTEPVPW SRGERPRRAG ISSFGISGTN
 451  AHVVLEEAPP EEDVPGPVAA EPEGVVPWVV SARTEEALSE QARRLGEFVA
 501  DTDPSTADVG WSLTTSRAIL EHRAVVVGRD RDALTAGLAA LAAGEESADV
 551  VAGVAGDVGP GPVLVFPGQG SQWVGMGAQL LDESPVFAAR IAECEQALSA
 601  YVDWSLSAVL RGDGSELSRV EVVQPVLWAV MVSLAAVWAD YGVTPAAVIG
 651  HSQGEMAAAC VAGALSLEDA ARVVAVRSDA LRQLMGQGDM ASLGASSEQA
 701  AELIGDRPGV CIAAVNGPSS TVISGPPEHV AAVVADAEER GLRARVIDVG
 751  YASHGPQIDQ LHDLLTDRLA DIRPATTDVA FYSTVTAERL TDTTALDTDY
 801  WVTNLRQPVR FADTIDALLA DGYRLFIEAS AHPVLGLGME ETIEQADIPA
 851  TVVPTLRRDH GDTTQLTRAA AHAFTAGATV DWRRWFPADP TPRTIDLPTY
 901  AFQRRSYWLP VDGVGDVRSA GLRRVEHSLL PAALGLADGA LVLTGRLAAS
 951  GGGGGWLADH AVAGTTLVPG AALVEWALRA ADEAGCPSLE ELTLQAPLVL
1001  PGSGGLQVQV VVGPADGQGG RREVRVFSRV DSDDEAAGQD EGWSCHATGV
1051  LSPEPGAVPD GLSGQWPPTG AEPLEISDLY EQAASAGYEY GPSFRGLRSV
1101  WRHGHNLLAE VELPEQAGAH DDFGIHPVLL DAALHPALLL DQNAPGEEQE
1151  PAQPALRLPF VWNGVSLWAT GAATVRVRLA PHGGGETDDS AGLRVTVADA
```

1201 TGAPVLSVDS LALRPADPEL LRTAGRAGSG TNGLFTVEWT ALPPADVADH

1251 AAGDGWAVLG QDVPDWAGAD MPRHPDMASL SAALDEGTQA PAAVFVETTA

1301 TSHATPNTAA DVTLDASGRA VAERTLHLLR DWLAEPRLAE TRLVLITHHA

1351 VTTPADDDVN AAPLDVPAAA LWGLIRSAQA EHPDRFVLLD TDAKANTDPG

1401 PDTSTDHSTA SGTYRTVIAR ALATGEPQLA VRAGELLAPR LARAATPTPE

1451 TPTPETQPDT GSGSEAGAGS GSGPGATLDP DGTVLIAGGT GMMGGLVAEH

1501 LVRAWSVRHL LLVSRQGPDA PDARDLADRL VGLGATVRIV AADLTDGRAT

1551 ADLVASVDPA HPLTGVIHAA GVLDDAVVTA QTSDQLARVW AAKASVAANL

1601 DAATSELPLG LFLMFSSAAG VLGNAGQAGY AAANAFVDAL VGRRRATGLP

1651 GLSIAWGLWA RGSAMTRHLD DADLARLRAG GVKPLLDEQG LALLDAARAT

1701 AAHTSLVVAA GIDVRGLNRD DVPAILRDLA GRTRRRAAAD STVDQAALER

1751 RLTGLDEAER RAVVTDVVRE CVAAVLGHRS AADVRTEANF KDLGFDSLTA

1801 VQLRNRLSAA SGLRLPATLA FDHPTPQALA AYLGTRLSGR TATPVAPVAP

1851 SAAATDEPVA IVAMACKYPG GATSPEGLWD LVAEGVDAVG AFPTGRGWDL

1901 ERLFHPDPDH PGTSYADEGA FLPDAGDFDA AFFGINPREA LAMDPQQRLL

1951 LEASWEVLER AGIDPTTLKG TPTGTYVGVM YHDYAAGLAQ DAQLEGYSML

2001 AGSGSVVSGR VAYTLGLEGP AVTVDTACSS SLVSIHLAAQ ALRQGECTLA

2051 LAGGVTVMAT PEVFTGFSRQ RGLAPDGRCK PFAAAADGTG WGEGVGVLLL

2101 ERLSDARRHG RRVLGVVRGS AVNQDGASNG LTAPNGPSQE RVIRQALASG

2151 GLSSVDVDVV EGHGTGTTLG DPIEAQALLA TYGQGRPVDR PLWLGSVKSN

2201 IGHTQAAAGV AGVIKMVMAM RHGVVPASLH VDVPSPHVEW DSGAVRLAVE

2251 SVPWPEVEGR PRRAGVSSFG ASGTNAHVIV ESVPDGLGED SVSVSGEAPE

2301 TETDGRLVPW VVSARSPQAL RDQALRLRDA VAADSTVSVQ DVGWSLLKTR

2351 ALFEQRAVVV GRERAELLSG LAVLAAGEEH PAVTRSREDG VAASGAVVWL

2401 FSGQGSQLVG MGAGLYERFP VFAAAFDEVC GLLEGPLGVE AGGLREVVFR
2451 GPRERLDHTM WAQAGLFALQ VGLARLWESV GVRPDVVLGH SIGEIAAAHV
2501 AGVFDLADAC RVVGARARLM GGLPEGGAMC AVQATPAELA ADVDDSGVSV
2551 AAVNTPDSTV ISGPSGEVDR IAGVWRERGR KTKALSVSHA FHSALMEPML
2601 AEFTEAIREV KFTRPKVSLI SNVSGLEAGE EIASPEYWAR HVRQTVLFQP
2651 GIAQVASTAG VFVELGPGPV LTTAAQHTLD DVTDRHGPEP VLVSSLAGER
2701 PEESAFVEAM ARLHTAGVAV DWSVLFAGDR VPGLVELPTY AFQRERFWLS
2751 GRSGGGDAAT LGLVAAGHPL LGAAVEFADR GGCLLTGRLS RSGVSWLADH
2801 VVAGAVLVPG AALVEWALRA GDEVGCVTVE ELMLQAPLVV PEASGLRVQV
2851 VVEEAGEDGR RGVQIYSRPD ADAVSGDDSW ICHATGTLTP QHTDAPNDGL
2901 AGAWPAAGAV PVDLAGFYER VADAGYAYGP GFQGLRAVWR HGQDLLAEVV
2951 LPEAAGAHDG YGIHPALLDA TLHPALLLDW PGEVQDDDGK VWLPFTWNQV
3001 SLRAAGAATV RVRLSPGEHD EAEREVQVLV ADATGTDVLS VGSVTLRPAD
3051 IRQLQAVPGH DDGLFSVDWT PLPLSRTDVS QTDADGDADW VVLSDGVGSL
3101 ADVVSAAGGE APWAVVAPVG ASAGGGLAGF DRREGLDGRL VVERVLSLVQ
3151 EFLAAPELAE SRLLVLTRGA VATGGDGDGD VDASAAAVWG LVRSAQSENP
3201 GRFILLDVDM DVDVDVDMDV DVDVDVDVDV DGDGNGSDLD PDLNGRRLPH
3251 ATLRHAAEEL DEPQLALRDG QLLVPRLVRA TGGGLVVAPT DRAWRLDKGS
3301 AETLESVAPV AYPGVMEPLG PGQVRLGIHA AGINFRDVLV SLGMVPGQVG
3351 LGGEGAGVVT ETGPDVTHLS VGDRVMGVLH GSFGPTAVAD TRMVAPVPQG
3401 WDMRQAAAMP VAYLTAWYGL VELAGLKAGE RVLIHAATGG VGMAAVQIAR
3451 HLGAEVFATA SAAKHVVLEE MGIDAAHRAS SRDLAFEDTF RQATDGRGMD
3501 VVLNSLTGEF IDASLRLLGD GGRFLEMGKT DVRTPEEVAA EYPGVTYTVY
3551 DLVTDAGPDR IAVMMSELGE RFASGALDPL PVRSWPLDKA REAFRFMSQA

3601 KHTGKLVLDV PAPLDPDGTV LITGGTGALG QVVAEHLVRE WGVRHLLLAS

3651 RRGLDAPGSG ELADRLSDLG AEVTVAAADV SDPASVVELV GKTDPSHPLT

3701 GVVHAAGVLE DGIVTAQTPE GLARVWAAKA AAAANLHEAT REMRLGLFVV

3751 FSSAAATLGS PGQANYAAAN AYCDALMQRR RAAGQVGLSV GWGLWEAPDA

3801 KPGVAADAKP DVAADAKTGV AADGTPQGMT GTLSGTDVAR MARIGVKAMT

3851 SAHGLALLDA AHRHGRPHLV AVDLDTRVLA HKPAPALPAL LRAFAGDQGG

3901 QGGGRGGGRG GGPARPAAAT TRQNVDWAAK LSVLTAEEQH RTLLDLVRTH

3951 AAAVLGHAGT DAVRADAAFQ DLGFDSLTAV ELRNRLSAST GLRLPATFIF

4001 RHPTPSAIAD ELRAQLAPAG ADPAAPLFGE LDKLETVITG HAHDESTRTR

4051 LAARLQNLLW RLDDTSARSD HAAGASDADG DAVENRDLES ASDDELFELI

4101 DRELPS*

MonAVI, polyketide synthase multi-enzyme MONS6, housing extension module 9 Length: 1701 amino acids

1 MPGTNDMPGT EDKLRHYLKR VTADLGQTRQ RLRDVEERQR EPIAIVAMAC

51 RYPGGVASPE QLWDLVASRG DAIEEFPADR GWDVAGLYHP DPDHPGTTYV

101 REAGFLRDAA RFDADFFGIN PREALAADPQ QRVLLEVSWE LFERAGIDPA

151 TLKDTLTGVY AGVSSQDHMS GSRVPPEVEG YATTGTLSSV ISGRIAYTFG

201 LEGPAVTLDT ACSASLVAIH LACQALRQGD CGLAVAGGVT VLSTPTAFVE

251 FSRQRGLAPD GRCKPFAEAA DGTGFSEGVG LILLERLSDA RRNGHQVLGV

301 VRGSAVNQDG ASNGLTAPND VAQERVIRQA LTNARVTPDA VDAVEAHGTG

351 TTLGDPIEGN ALLATYGKDR PADRPLWLGS VKSNIGHTQA AAGVAGVIKM

401 VMAMRHGELP ASLHIDRPTP HVDWEGGGVR LLTDPVPWPR ADRPRRAGVS

451 SFGISGTNAH LIVEQAPAPP DTADDAPEGA ATPGASDGLV VPWVVSARSP

501 QALRDQALRL RDFAGDASRA PLTDVGWSLL RSRALFEQRA VVAGRERAEL

551 LAGLAALAAG EEHPAVTRSR EEAAVAASGD VVWLFSGQGS QLVGMGAGLY

601 ERFPVFAAAF DEVCGLLEGE LGVGSGGLRE VVFWGPRERL DHTVWAQAGL

651 FALQVGLARL WESVGVRPDV VLGHSIGEIA AAHVAGVFDL ADACRVVGAR

701 ARLMGGLPEG GAMCAVQATP AELAADVDGS SVSVAAVNTP DSTVISGPSG

751 EVDRIAGVWR ERGRKTKALS VSHAFHSALM EPMLGEFTEA IRGVKFRQPS

801 IPLMSNVSGE RAGEEITSPE YWARHVRQTV LFQPGVAQVA AEARAFVELG

851 PGPVLTAAAQ HTLDHITEPE GPEPVVTASL HPDRPDDVAF AHAMADLHVA

901 GISVDWSAYF PDDPAPRTVD LPTYAFQGRR FWLADIAAPE AVSSTDGEEA

951 GFWAAVEGAD FQALCDTLHL KDDEHRAALE TVFPALSAWR RERRERSIVD

1001 AWRYRVDWRR VELPTPVPGA GTGPDADTGL GAWLIVAPTH GSGTWPQACA

1051 RALEEAGAPV RIVEAGPHAD RADMADLVQA WRASCADDTT QLGGVLSLLA

1101 LAEAPATSSD TTSHTSTSCG TGSLASHGLT GTLTLLHGLL DAGVEAPLWC

1151 ATRGAVSCGD ADPLVSPSQA PVWGLGRVAA LEHPELWGGL VDLPADPESL

1201 DASALYAVLR GDGGEDQVAL RRGAVLGRRL VPDATPDVAP GSSPDVSGGA

1251 AHADATSGEW QPHGAVLVTG GVGHLADQVV RWLAASGAEH VVLLDTGPAN

1301 SRGPGRNDDL AAEAAEHGTE LTVLRSLSEL TDVSVRPIRT VIHTSLPGEL

1351 APLAEVTPDA LGAAVSAAAR LSELPGIGSV ETVLFFSSVT ASLGSREHGA

1401 YAAANAYLDA LAQRAGADAA SPRTVSVGWG IWDLPDDGDV ARGAAGLSRR

1451 QGLPPLEPQL ALGALRAALD GGKGHTLVAD IEWERFAPLF TLARPTRLLD

1501 GIPAAQRVLD ASSESAEASE NASALRRELT ALPVRERTGA LLDLVRKQVA

1551 AVLRYEPGQD VAPEKAFKDL GFDSLVVVEL RNRLRAATGL RLPATLVYDY

1601 PTPRTLAAHL LDRVLPDGGA AELPVAAHLD DLEAALTDLP ADDPRRKGLV

1651 RRLQTLLWKQ PDAMGAAGPA DEEEQAAPED LSTASADDMF ALIDREWGTR

1701 *

MonH, probable regulatory protein Length: 981 amino acids

```
  1  VSGVERGVGS AGPVEQGDGL AGLVERAEAL AALRGAFDGS PGTGGSLVVL
 51  SGAVGTGKTA LLRAWADRIG ADADALVLTA TACRAERDLP LGVLEQLVRS
101  PGLPPASAER ALAWWDEEAS ATPGKTDANG TSANGTDANG TGAGQTGAGQ
151  AGVGQTGVGG EPVLAASALR GLCEVLRDLL AERPVVVAVD DAHHADAASL
201  QCLLSVVRRL RSARLHVLFT EYAHQKAQNA LLSSEFLHEP ALRRIRLEPL
251  SKAGVEALLA RHLDERTAQD LTPVVHGMSA GHPLLVRALA EDHRAAGGAG
301  EAYGRAVLSF LYRHETPVTQ VARAIAALGA HAGPGQVGRL LDVDAASVER
351  AVRQLTVAEV LHEGRLCHPA FAAAVLDGMP PEERRALHGR VADLLHEEGA
401  PATEVAAHLV AADRSDAPWA VPVFQEAAQL ALDEDQVETG VDYLRAAHQR
451  CRGAAQRAAV VGALADAEWR LDPAKVLRHL PDPAAMAPQT DPAALAPHTD
501  PAPTAAPTAA PTPTPIPTTP PLPTHLLWHG RVEEGLDAIG TLTGPGPNPA
551  GAPPMNPADL DTPWLWGAYL YPGHVKERLG SGALSPQRST PPAVTPELQG
601  AGTLMNDLLH GGERDATEAA ERALNRYRLG PRTIAVQTAA LAALTYRDRP
651  HRAAAWCDGL VAQADERNSP TWRALFTAWR ALLHLRQGDP AAAEQRAETA
701  LALLGSKGWG AAIGLPLAAA VQAKAALGDV DGAAALLERP VPQAVFQTRT
751  GLHYLAARGR YHLATGCHYA ALCDFYACGT RMSSWGVDLP ALEPWRLGAA
801  EAYLALGEGL LARQLVDGQL PLPTPDDGRT WGMTLRLRAA TSPAPARAEL
851  LDEAVAVLRE SGDTFELARA VADQAVAVRE GGEAERARLL ARKAELLARR
901  WGSAPAPATV PEPPERPGPA TPDAELTSAE RRVAELAAEG FTNREISRKL
951  CVTVSTVEQH LTRIYRKLDV RRLDLQAALG *
```

MonCI, flavin-dependent epoxidase Length: 496 amino acids

```
  1  VTTTRPAHAV VLGASMAGTL AAHVLARHVD AVTVVERDAL PEEPQHRKGV
 51  PQARHAHLLW SNGARLIEEM LPGTTDRLLA AGARRLGFPE DLVTLTGQGW
101  QHRFPATQFA LVASRPLLDL TVRQQALGAD NITVRQRTEA VELTGSGGGS
```

151 GGRVTGVVVR DLDSGRQEQL EADLVIDATG RGSRLKQWLA ALGVPALEED

201 VVDAGVAYAT RLFKAPPGAT THFPAVNIAA DDRVREPGRF GVVYPIEGGR

251 WLATLSCTRG AQLPTHEDEF IPFAENLNHP ILADLLRDAE PLTPVFGSRS

301 GANRRLYPER LEQWPDGLLV IGDSLTAFNP IYGHGMSSAA RCATTIDREF

351 ERSVQEGTGS ARAGTRALQK AIGAAVDDPW ILAATKDIDY VNCRVSATDP

401 RLIGVDTEQR LRFAEAITAA SIRSPKASEI VTDVMSLNAP QAELGSNRFL

451 MAMRADERLP ELTAPPFLPE ELAVVGLDAA TISPTPTPTP TAAVRS

MonBII, carbon-carbon double bond isomerase Length: 141 amino acids

1 MPDEAARKQM AVDYAERINA GDIEGVLDLF TDDIVFEDPV GRPPMVGKDD

51 LRRHLELAVS CGTHEVPDPP MTSMDDRFVV TPTTVTVQRP RPMTFRIVGI

101 VELDEHGLGR RVQAFWGVTD VTMDDPAGPA DTTHPEGIRA *

MonBI, carbon-carbon double bond isomerase Length: 144 amino acids

1 MNEFARKKRA LEHSRRINAG DLDAIIDLYA PDAVLEDPVG LPPVTGHDAL

51 RAHYEPLLAA HLREEAAEPV AGQDATHALI QISSVMDYLP VGPLYAERGW

101 LKAPDAPGTA RIHRTAMLVI RMDASGLIRH LKSYWGTSDL TVLG

MonAVIII, polyketide synthase multi-enzyme MONS8, housing extension modules 11 and 12 Length: 3754 amino acids

1 MSNEEKLLDH LKWVTAELRQ ARQRLHDKES TEPVAIVGMA CRYPGGARSA

51 EDLWELVRDG GDAVAGFPDD RGWDLESLYH PDPEHPATSY VRDGAFLYDA

101 GHFDAEFFGI SPREATAMDP QQRLLLETAW EAIEHAGMNP HALKGSDTGV

151 FTGVSAHDYL TLISQTASDV EGYIGTGNLG SVVSGRISYT VGLEGPAVTV

201 DTACSSSLVA IHLASQALRQ GECSLALAGG STVMATPGSF TEFSRQRGLA

251 PDGRCKPFAA AADGTGWGEG AGVVALELLS EARRRGHKVL AVIRGSATNQ

301 DGTSNGLAAP NGPSQERVIR AALANARLSA EDIDAVEAHG TGTTLGDPIE

351 AQALIATYGQ GRPEDRPLWL GSVKSNIGHT QAAAGVAGVI KMVMAMRNGL

401 LPTSLHIDAP SPHVQWEQGS VRLLSEPVDW PAERTRRAGI SAFGISGTNA

451 HLILEEAPPE EDAPGPVAAE PGGVVPWVVS GRTPDALREQ ARRLGEFAAG

501 LADASVSEVG WSLATTRALF DQRAVVVGRD LAQAGASLEA LAAGEASADV

551 VAGVAGDVGP GPVLVFPGQG SQWVGMGAQL LDESPVFAAR IAECEQALSA

601 HVDWSLSDVL RGDGSELSRV EVVQPVLWAV MVSLAAVWAD YGITPAAVIG

651 HSQGEMAAAC VAGALSLEDA ARIVAVRSDA LRQLQGHGDM ASLSTGAEQA

701 AELIGDRPGV VVAAVNGPSS TVISGPPEHV AAVVADAEAQ GLRARVIDVR

751 YASHGPQIDQ LHDLLTDRLA DIQPTTTDVA FYSTVTAERL DDTTALDTAY

801 WVTNLRQPVR FADTIEALLA DGYRLFIEAS PHPVLNLGIQ ETIEQQAGAA

851 GTAVTIPTLR RDHGDTTQLT RAAAHAFTAG APVDWRRWFP ADPTPRTVDL

901 PTYAFQHKHY WVEPPAAVAA VGGGHDPVEA RVWQAIEDLD IDALAGSLEI

951 EGQAESVGAL ESALPVLSAW RRRHREQSTV DSWRYQVTWK HLPDVPAPEL

1001 SGAWLLLVPA AHADHPAVLA TAQTLTAHGG EVRRHVVDAR AMERTELAQE

1051 LRVLMDGAAF AGVVNLLALD EEPHPEHSAV PAGLAATTAL VQALADNGAD

1101 IAVRTLTQGA VSTSAGDALT HPVQAQVWGL GRVAALEYPR LWGGLVDLPA

1151 RIDHQTLARL AAALVPQDED QISIRPSGVH ARRLAHAPAN TVGSGLGWRP

1201 DGTTLITGGT GGIGAVLARW LARAGAPHLL LTSRRGPDAP GAQELAAELT

1251 ELGAAVTVTA CDVGDREQVR RLIDDVPAEH PLTAVIHAAG VPNYIGLGDV

1301 SGAELDEVLR PKALAAHHLH ELTRELPLSA FVMFSSGAGV WGSGQQGAYG

1351 AANHFLDALA EHRRAEGLPA TSIAWGPWAE AGMAADQAAL TFFSRFGLHP

1401 LSPELCVKAL QQALDAGETT LTVANFDWAQ FTSTFTAQRP SPLLADLPEN

1451 RRASAPAAQQ EDATEASSLQ QELTEAKPAQ QRQLLLQHVR SQAAATLGHS

1501 DVDAVPATKP FQELGFDSLT AVELRNRLNK STGLTLPTTV VFDHPTPDAL

1551 TDVLRAELSG DAAASADPVR AAGASRGAAD DEPIAIVGMA CRYPGDVRSA
1601 EELWDLVAAG KDAMGAFPDD RGWDLETLYD PDPESRGTSY VREGGFLYDA
1651 GDFDAGFFGI SPREAVAMDP QQRLLLETAW EAIERAGLDR ETLKGSDAGV
1701 FTGLTIFDYL ALVGEQPTEV EGYIGTGNLG CVASGRVSYV LGLEGPAMTI
1751 DTGCSSSLVA IHQAAHALRQ GECSLALAGG ATVMATPGSF VEFSLQRGLA
1801 KDGRCKPFAA AADGTGWAEG VGLVVLERLS EARRNGHNVL AVIRGSAINQ
1851 DGTSNGLTAP NGQAQQRVIR QALANARLSA EDVDAVEAHG TGTMLGDPIE
1901 ASALVATYGK ERPADRPLWL GSIKSNIGHA QASAGVAGVI KMVMALRNEQ
1951 LPASLHIDAP TPHVDWDGSG VRLLSEPVSW PRGERPRRAG VSAFGISGTN
2001 AHLILEQAPD APEPVTAPAE DAAAPAGVVP WVVSARGEEA LRAQARLLAD
2051 RATADPRLAS PLDVGWSLVK TRSVFENRAV VVGKDRQTLL AGLRSLAAGE
2101 PSPDVVEGAV QGASGAGPVL VFPGQGSQWV GMGAQLLDES PVFAARIAEC
2151 ERALSAHVDW SLSAVLRGDG SELSRVEVVQ PVLWAVMVSL ASVWADYGIT
2201 PAAVIGHSQG EMAAACVAGA LSLEDAARIV AVRSDALRQL MGQGDMASLG
2251 AGSEQVAELI GDRPGVCVAA VNGPSSTVIS GPPEHVAAVV ADAEARGLRA
2301 RVIDVGYASH GPQIDQLHDL LTERLADIRP TTTDVAFYST VTAERLDDTT
2351 TLDTDYWVTN LRQPVRFADT IEALLADGYR LFIEASPHPV LNLGMEETIE
2401 RADMPATVVP TLRRDHGDAA QLTRAAAQAF GAGAEVDWTG WFPAVPLPRV
2451 VDLPTYAFQR ERFWLEGRRG LAGDPAGLGL ASAGHPLLGA AVELADGGSH
2501 LLTGRISPRD QAWLAEHRVM DTVLLPGSAF VELALQAAVR AGCAELAELT
2551 LHTPLAFGDE GAGAVDVQVV VGSVAEDGRR PVTVHSRPTG EGEEAVWTRH
2601 AAGVVAPPGP DAGDASFGGT WPPPGATPVG EQDPYGELAS YGYDFGPGSQ
2651 GLVSAWRLGD DLFAEVALPE AESGRADRYQ VHPVLLDATL HALILDAVTS
2701 SADTDQVLLP FSWSGLRVHA PGAEKLRVRI ARTAPDQLAL TAVDGGGGGE

2751 PVLTLESLTV RPVAAHQIAG ARAADRDALF RLVWMEVAAR AEETGGGAPR

2801 AAVLAPVESG PMGGTSAGAL ADALSDALAA GPVWDTFGAL RDGVAAGGEA

2851 PDVVLAVCAA PGAGAGAVAD ADGRGGDPAG YARLATVSLL SLLKEWVDDP

2901 AFAATRLVVV TRGAVAARPG ETAGDLAGAS LWGLVRSAQA ENPGRLTLLD

2951 VDGLESSPAT LTGVLASGEP ELALRDGRAY VPRLVRDDAS VRLVPPVGSL

3001 TWRLARCQEA GGGQQLSLVD APEAGRALEP HEVRVAVRAA APGPLTAGQV

3051 EGAGVVTEVG GEVGSVAVGD RVMGLFDAVG PVAVTDAALL MPVPAGWSWA

3101 QAAGSLGAYV SAYHVLADVV APRGGETLLV GEETGSVGRA VLRLALAGRW

3151 RVEAVDGAST ADDSGAERAA DVTLRHEGAL VVHRAGGRPD EGQAVVPPEP

3201 GRVREILAEL TELTELAEIT ESAEPGLPAE RGDSRALTPL DITVWDIRQA

3251 PAAMAAPPSA GTTVFSLPPA FDPEGTVLVT GGTGALGSLT ARHLVERYGA

3301 RHLLLSSRRG ADAPGALELA ADLSALGARV TFAACDPGDR DEAAALLAAV

3351 PSDHPLTAVF HCAGTVNDAV VQNLTAEQVE EVMRVKADAA WHLHELTRDA

3401 DLSAFVLYSS VAGLLGGPGQ GSYTAANAFL DALARHRHDG GAAATSLAWG

3451 YWELASGMSG RLTDADRARH ARAGVVGLGA DEGLALLDAA WAGGLPLYAP

3501 VRLDLARMRR QAQSHPAPAL LRDLVRGGSK SGGGAVSAGA AALLKSLGAM

3551 SDPEREEALL DLVCTHIAAV LGYDAATPVN ATQGLRELGF DSLTAVELRN

3601 RLSAATGLKL PATFVFDHPN PAELAAQLRQ ELAPRAADPL ADVLAEFERI

3651 EDSLLSVSSK DGSARAELAG RLRATLARLD APQDTAGEVA VATRTRIQDA

3701 SADEIFAFID RDLGRDGASG QGNGQPTGQG NGHGNGNGNG NGNGHGQAVE

3751 GQR*

MonAVII, polyketide synthase multi-enzyme MONS7, housing extension module 10 Length: 1642 amino acids

1 MAHTEEKLLE YLKRVTADLR QTERRLQDVE SAGHEPVAVI GMACRLPGGV

51 RSPEEFWELV STGGDAVAPL PGNRNWDLDS LYDPDPESTG TSYVREGGFV

101 YDAGDFDPTF FGIGPTEAAA MAPQQRLALE TAWEAIERAG IDPLSLRSSD

151 TSTFIGCDGL DYALGASEVP EGTAGYFTIG NSGSVTSGRV AYTLGLEGPA

201 VTVDTACSSS LVSLHLATQA LRTQECSLAL AGGTYVMSSP APLIGFSELR

251 GLAPDGRCKP FSASSDGMGM AEGTGVVLLE RLSDARRKGH KVLAVIRGSA

301 INQDGASNGL TAPNGPAQER VIRAALANAR LAPEDIDAVE AHGTGTTLGD

351 PIEAGALISA YGRERPEDRP LWVGAVKSNI GHTQIAAGVA GVIKMVLALR

401 HDLLPAILHV DAPSPHVEWD GSGLRLLTDP VKWPRGERPR RAGVSSFGFS

451 GTNAHLILEE APPEEEDVPG SVAEEPGGVV PWVVSGRTPD ALRAQARRLG

501 EFAAGPADAS AADVGWSLTT TRSVFEHRAV VVGRDRDALT AGLGALAAGE

551 ASAGVVAGVA GDVGPGPVLV FPGQGSQWVG MGAQLLDESP VFAARIAECE

601 RALSAYVDWS LSAVLRGDGS ELSRVEVVQP VLWAVMVSLA AVWADYGVTP

651 AAVIGHSQGE MAAACVAGAL SLEDAARIVA VRSDALRRLQ GHGDMASLST

701 GAEQAAELIG DRPGVVVAAV NGPSSTVISG PPEHVAAVVA DAEARGLRAR

751 VIDVGYASHG PQIDQLHDLL TERLADIRPA NTDVAFYSTV TAERLTDTTA

801 LDTDYWVTNL RQPVRFADTI EALLADGYRL FIEASAHPVL GLGMEETIEQ

851 ADIPATVVPT LRRDHGDTTQ LTRAAAHAFT AGAPVDWRRW FPADPTPRTV

901 DLPTYAFQHQ HYWLERSASA SGAVSGEQSA AEAQLWHAVE ELDLGLLAET

951 LGSEEGSEEA VRALEPALPV LKGWRRRHQD QATIDSWRYR VTWKQRSDGP

1001 APELGGDWLL FVPADKAEHP AVRATAEALS EHGAAAVRLH PVETGRAGRQ

1051 ELAAVDTAGL AGIVNLLALD EEPHPEHPAV PAGLAATTAL LQALGDNGTT

1101 APLHTVTQGA VSTGATDPLT HPLQAHVWGL GRVAALEHPR LWAGLVDLPA

1151 RIDRHTLPRL AAALLPQDDE DQTAVRPTGI HHRRLTHAVG SIQNPVHSEA

1201 TWRPRGTTLI TGGTGGIGAV LARWLARQGA PRLHLTSRRG PDAPGARELA

1251 AELDGLGTAV TITACDVSDP RQLSGLIDDM PAEHPLTAVI HAAGMTDLTA

1301 IGDLTTARLG EVLGSKSDAA WNLHELTRDL DLSAFVMFSS GAGVWGSGQQ

1351 GAYGAANHFL DALAEHRRAQ GLPATSIAWG PWAEAGMSAD PESLTYFKRF

1401 GLLPIAPDLC VKALHQAVDA GDATLTVANF DWAKFTPTFT AQRPSPFLDD

1451 LPENQREAEQ TGTAAETSAF REELAKTPAS QRLGFLVQQV RTYAAATLGR

1501 TVEDIPAAKP FQELGFDSLT AVQLRNQLNT TTGLSLPATV IFDHPTPEAL

1551 ATHLRGQLGD GAEVAGEGDV LAALDKWDTA FGAAEVDEAA RRRIVGRLQV

1601 LVSKWSPAQD GPEGTDSAHA DLEAASADDI FDLISSEFGK S*

MonD, cytochrome P450 hydroxylase Length: 431 amino acids

1 VGLTVGPDNA KRGIVPITDS KPAATFPDLV DPSFWARPHA ERVALFEEMR

51 GLPRPAFIRQ NMPGVPWTFG YHALVKYADI VEVSRRPQDF SSNGATTIIG

101 LPPELDEYYG SMINMDNPEH SRLRRIVSRS FGRNMIPEFE AVATRTARRI

151 IDELIARGPG DFIRPVAAEM PIAVLSDMMG IPAEDHDFLF DRSNTIVGPL

201 DPDYVPDRAD SERAVIEASR ELGDYIAGLR AERLAAPGND LITKLVQVQA

251 DGEQLTRQEL VSFFILLVIA GMETTRNAIS HALVLLTEHP EQKQLLLSDF

301 DTHAPNAVEE ILRVSTPINW MRRVATRDCD MNGHRFRRGD RIFLFYWSGN

351 RDESVFPDPY RFDITRGTNA HVTFGAVGPH VCLGAHLARM EITVLYRELL

401 AALPQIHAVG QPRRLDSSFI EGIKHLHCAF *

MonRI, probable activator protein Length: 268 amino acids

1 VRYEMLGPLR IKDGNDYATI NAQKVEIVLT VLLIRADRVV SLEQLMREIW

51 GEDLPRRATA GLHVYISQLR KFLKVPGSAG NPVETRAPGY VLHKRDDDQI

101 DAQIFPELVD VGRSLLREKR FDEAASCFGQ ALALWRGPIL GQGGNGPGTN

151 GPIIDGFSTW LTEIRLECQE MLVECQLQLG RHREAVGMLY ALTAENPMCE

201 AFYRQLMLAL YRSERQADAL KVYQSVRKTL NDELGLEPGR PLQELQRAIL

251 AGDMHLMSPP PLALSGR*

MonAX, thioesterase Length: 278 amino acids

```
  1  LSAFLAKGKI LSAFPPPDMS DPWIRRFRPR PEAVVRLVCF PHAGGSASYY
 51  HPLAQSPTLP TDSEVLAVQY PGRQDRRRER LLDDIGELAD LITDALGPFD
101  DRPLAFFGHS MGAVLAYEVA QRLRERTGKQ PCRLFVSGRR APSRFRRGTV
151  HLLDDTELAA ELRRAGGTDP RFLDDEELLA EIIPVVRNDY RAVELYRWNP
201  SPPLSCPITA LVGDRDPQAP LDEVEAWQQH TEGPFDLKVF AGGHFYLNTH
251  QQGVTEVISK ALADSAQQRA TARGNAR*
```

ORF29, a homologue of CapK involved in cell wall biosynthesis Length: 428 amino acids

```
  1  LADLVAHARS ASPYYRELYH GLPERIEDPT LLPVTDKKQL MDHFDDWPTD
 51  RDITFEKVRA FTDDPELIGR RFLGRYLVAT TSGTSGRRGL FVLDDRYMNV
101  SSAVSSRVLA SWLGPLGIAR AVVHGGRFAQ LVATEGHYVG FAGYSRLRQD
151  GEARSKLVRA FSVHEPMSRL VAELNEYRPA FVIGYASTIM LFTAEQEAGR
201  LHIDPVLVEP AGETMTESDT DRIAAAFGAK VRTMYSATEC TYLSHGCAEG
251  WYHVNDDWAV LEPVDADHRP TPPGEFSHTT LISNLANRVQ PFLRYDLGDS
301  VMLRPDPCPC GTPSPAIRVQ GRSGDILTFP SGRGDDVSLA PLAFSSLFDR
351  MPGVELFQIE QTAPSTLRVR VVQAPGADAD HVWQRAHDGL THLLADNKLD
401  NVTVERGEEP PRQASGGKYR TIIPLAA*
```

LipB, lipase B Length: 338 amino acids

```
  1  VKVPVEVTVR LSSWLGGLVA AVLAATVLPA SAASAADVSS PPLEIPAAEL
 51  AKALHCGTEL GDLRDAGDKP TVLFVPGTGL KGEENYAWNY MAELKKKGYQ
101  SCWVDSPGRG LRDMQESVEY VVYATRAIQE ATGRKVDLVG HSQGGLLTAW
151  ALRFWPDLPG KVDDMVTLGS PFQGTRLASP CRPIAEVAGC PASVLQFARD
201  SNWSKALGAD GTPMPAGPSY TTIYSYADES VVADGEAPSL PGAHRIGVQD
```

```
251  ICPGRPWPTH IAMVVDQVSY DLVADAIEHP GPADTSRIDR AHCAKPVMPL
301  NSQEAVDALP GLLNFPIELL IHSQPWVDEE PPLRPYAR
```

ORF31, putative ion pump Length: 309 amino acids

```
  1  MGHDHGPSAG AAGGTLSGTY RKRLLWTIGI SGSITVIQVV GALLSGSLAL
 51  LADAAHSLTD AVGVSLALGA ITLAQRAPTP RRTFGFCRVE IFSAVLNALL
101  LVVIFAWVLW SAIGRFSEPV EVKGGLMFVV ALGGLAANLV GLWLLRDAKE
151  KSLNLRGAYL EVLGDALGSV AVIVGGLVIL LTGWQAADPI ASIVIGLLIV
201  PRAYGLLRDS LHVLLEATPQ DVDLGEVRRH LLEERGVVAV HDLHGWTVTS
251  GMPVLTAHVV VTEEALASGY GELLGRLQRC VGGHFDVAHS TIQLEPEGHV
301  EEDGALHT*
```

ORF32, hypothetical membrane protein Length: 364 amino acids

```
  1  MTRALTLHDW IVAGIAVVAG VVAGLLLRAL LRWLGERASK TRWSGDDVIV
 51  DALRTLVPCA AITAGLAAAA GALPLTPRTG RNVTMTLTAL LILAATLTAA
101  RIVTGLVKAV AQSRSGVAGS ATIFVNITRV VVLAMGFLIV LQTLGISIAP
151  LLTALGVGGL AVALALQDTL ANLFAGVHIL AAKTVQPGDY IQLSSGEEGY
201  VVDINWRNTT VRQLSNNLVI IPNAKLAGTN MTNYSRPEQE LSIMVQVGVS
251  YDSDLEQVEK VTTEVVDEVM AEITGAVPDH EAAIRFHTFG DSRISFTVIL
301  GVGEFSDQYR IKHEFIKRLH QRYRAEGIRV PAPVRTVRVQ QGELPPPLGI
351  PHQRDTSTQA RLH*
```

AmtA, glycine amidinotransferase (partial coding sequence) Length: 131 amino acids

```
  1  MSPVNSHNEW DPLEEIIVGR LEGATIPSSH PVVACNIPTW AARLQGLAAG
 51  FEYPQRLIEP AQQELDQFIA LLQSLDVTVR RPAAVDHKHR FGTPDWQSRG
101  FCNSCPRDSM LVVGDEIIET PMAWPCRCFE T
```

CLAIMS:

1. A DNA sequence which is (a) at least part of the sequence set out in the appended sequence listing; or (b) a variant of a sequence (a) which encodes a polypeptide which is at least 80%, preferably at least 90%, identical with the corresponding peptide as set out in table II; provided that it is not a sequence encoding all or part of the polypeptide consisting of amino acids 1-920 encoded by *mon AI* as set out in table II.

2. A DNA sequence according to claim 1 comprising the complete monensin gene cluster or a variant thereof.

3. A DNA sequence encoding at least part of at least one polypeptide which is necessary for the biosynthesis of monensin, and which is encoded by DNA included in the appended sequence listing or an allele, mutation or other variant thereof; provided that said polypeptide is not all or part of amino acids 1-920 encoded by *mon AI* as set out in table II.

4. A DNA sequence according to claim 3 which comprises at least part of one or more of the following genes: *mon BI, mon BII, mon CI, mon CII, mon H, mon RI, mon RII, mon T, mon AIX* and *mon AX*.

5. A DNA sequence according to claim 4 comprising all of the genes listed therein or an allele, mutation or other variant thereof.

6. A DNA sequence according to claim 3 encoding at least part of one or more of the polypeptides set out below, said polypeptide having the amino acid sequence as set out in the appended sequence data or being a variant thereof having the specified activity:

peptide	activity
mon CII	epoxyhydrolase/cyclase
mon E	S-adenosylmethionine-dependent methyltransferase
mon T	monensin resistance gene
mon RII	repressor protein
mon AIX	thioesterase
mon AI	polyketide synthase multienzyme
mon AII	polyketide synthase multienzyme
mon AIII	polyketide synthase multienzyme
mon AIV	polyketide synthase multienzyme
mon AV	polyketide synthase multienzyme
mon AVI	polyketide synthase multienzyme
mon AVII	polyketide synthase multienzyme
mon AVIII	polyketide synthase multienzyme
mon H	regulatory protein
mon CI	flavin-dependent epoxidase
mon BII	carbon-carbon double bond isomerase

mon BI carbon-carbon double bond isomerase

mon D cytochrome P450 hydroxylase

mon RI activator protein

mon AX thioesterase

7. A DNA sequence according to claim 6 encoding a single enzyme activity of a multienzyme encoded by any of *mon AI-mon AVIII* or a variant or part thereof.

8. A DNA sequence according to any preceding claim encoding any one or more of the domains as set out in Table I or a variant or part thereof.

9. A DNA sequence according to any preceding claim which has a length of at least 30, preferably at least 60, bases.

10. A recombinant cloning or expression vector comprising a DNA sequence according to any preceding claim.

11. A transformant host cell which has been transformed to contain a DNA sequence according to any of claims 1-9 and which is capable of expressing a corresponding polypeptide.

12. A hybridisation probe which is a DNA sequence according to any of claims 1-9.

13. Use of a probe according to claim 12 to detect a PKS cluster, optionally followed by isolation of the detected cluster.

14. Use of a probe according to claim 12 which encodes at least part of a polypeptide having a known function to detect genes encoding polypeptides having analogous function.

15. Use according to claim 14 wherein the polypeptide of known function is AT of module 5 or the regulatory protein encoded by *mon RI*.

16. A hybridization probe comprising a polynucleotide which binds specifically to a region of the monensin gene cluster selected from *mon BI, mon BII, mon CI, mon CII, mon H, mon RI, mon RII, mon T, mon AIX* and *mon AX*.

17. Use of a probe according to claim 16 in a method of detecting the presence of a gene cluster which governs the synthesis of a polyether, and optionally isolating a gene cluster detected thereby.

18. Use of a probe according to claim 12 which comprise a polynucleotide which binds specifically to a gene responsible for levels of activity of the monensin gene cluster, in a method of detecting an analogous gene in a gene cluster for biosynthesis of another polyketide, optionally followed by a step of manipulating the gene detected thereby to alter the level of expression of said other polyketide.

19. Use according to claim 18 wherein the gene is a regulatory gene, resistance gene or thioesterase gene.

20. Use of the *mon RI* gene or variant and a monensin promoter to control expression of a heterologous gene in *S. cinnamonensis*.

21. Use of a portion of the monensin gene cluster encoding a polypeptide having chain terminating activity, preferably comprising at least one of *mon AIX* and *mon AX* or a mutant, allele or other variant thereof encoding a polypeptide having chain terminating activity, to effect chain release of a peptide other than monensin.

22. Use of a portion of the monensin gene cluster encoding a polypeptide having carbon-carbon double bond isomerase activity, preferably comprising at least one of

mon BI and *mon BII* or a mutant, allele or other variant thereof having isomerase activity to provide a desired stereochemical outcome in the synthesis of a polyketide other than monensin.

23. A polypeptide encoded by a portion of the monensin gene cluster, preferably comprising at least one of *mon BI* and *mon BII* or a mutant, allele or other variant thereof, having carbon-carbon double bond isomerase activity, or at least one of *mon AIX* and *mon AX* or a mutant, allele or other variant thereof having chain terminating activity.

24. An epoxidase enzyme encoded by *mon CI* or a derivative or variant thereof having epoxidase activity.

25. A cyclase enzyme encoded by *mon CII* or a derivative or variant thereof having cyclase activity.

26. Use of a portion of the monensin gene cluster encoding a peptide having epoxidase or cyclase activity, preferably comprising *mon CI* or *mon CII* or a mutant, allele or other variant thereof encoding a polypeptide having epoxidase or cyclase activity to provide a said activity in the biosynthesis of a polypeptide other than monensin.

27. A process for producing a polyketide containing a desired starter unit comprising providing a PKS gene having a loading module and a plurality of extension modules, wherein the loading module includes a KS_q domain derived from a KS domain of a monensin extension module.

28. A process according to claim 27 wherein the KS_q domain is derived from KS of module 5 of monensin.

29. A process according to claim 27 or claim 28 wherein the starter unit also includes an AT_q domain derived from an AT domain which is naturally associated with the KS domain.

30. A DNA sequence comprising DNA encoding at least one PKS loading module and a plurality of PKS extension modules, and which can be expressed to produce a polyketide; wherein at least one of said modules or at least one domain thereof is a monensin module or domain or a variant thereof and is contiguous to a further one of said modules or a domain to which it is not naturally contiguous; provided that the sequence is not an ery loading module, the first and second extension modules of the ery PKS and the ery chain-terminating thioesterase in which the DNA encoding AT of the first extension module has been substituted by DNA encoding an ethyl malonyl-CoA

AT from the monensin gene cluster.

31. A DNA sequence according to claim 30 wherein said further module or domain is also a monensin module or domain or variant thereof.

32. A DNA sequence according to claim 30 wherein said further module or domain is a module or domain of a PKS of a polyketide other than monensin or a variant thereof.

33. A DNA sequence according to claim 30, 31 or 32 wherein said loading module is adapted to load a starter unit other than a starter unit normally received by the adjacent extension module.

34. A DNA sequence according to claim 33 wherein said loading module is derived from a monensin extension module or variant thereof.

35. A polyketide synthase encoded by the DNA sequence of any of claims 30-34.

36. A polyketide compound as produced by a synthase according to claim 35.

37. A vector containing a DNA sequence of any of claims 30-34.

38. A transformant cell transformed to contain a DNA sequence of any of claims 30-34.

39. A method of producing *S. cinnamonensis* capable of enhanced levels of production of monensin comprising engineering it to overexpress the *mon RI* gene.

40. A method according to claim 39 wherein said engineering comprises introducing at least one additional copy of the *mon RI* gene as shown in the appended sequence data or a variant thereof.

41. *S. cinnamonensis* containing multiple copies of the *mon RI* gene as shown in the appended sequence data and/or variant(s) thereof.


42. A method of producing monensin comprising culturing the organism of claim 41 and/or an organism produced by the method of claim 39 or claim 40.

43. A process for expressing a gene heterologous to *S. cinnamonensis* comprising transforming *S. cinnamonensis* with DNA encoding a heterologous gene and expressing said

gene under control of the activator gene *mon RI* or actII/orf4.

44. A process according to claim 43 wherein said heterologous gene is a *PKS* gene.

45. 13-Propyl erythromycin A.



monensin A : R = ethyl
monensin B : R = methyl

Fig 1




Fig 2A

Fig 2B

Figure 2. Proposed mechanisms for monensin biosynthesis.




Fig3

Proposed organisation of the monensin PKS



Organisation of the Monensin Biosynthetic Gene Cluster
0
10
20
30
40
50
60
70
80
90
100
105 kbp
MonAI LD & M1
MonAII M2
MonAIII M3 & M4
MonAIV M5 & M6
MonAV M7 & M8
MonAVI M9
MonAVII M10
MonAVIII M11 & M12
MonAIX TE
MonRII Respressor
MonT Resistance
MonE Methyltransferase
MonCII Epoxidhydrolase/ cyclase
KSX
ACPX
orf7
orf6
orf5
orf4
orf3 Activator
dapA Dihydrodipicolinate synthase
gdhA Glutamate dehydrogenase
MonBI Isomerase
MonBII Isomerase
MonCI Epoxidase
MonH Regulation
MonAX TE
MonRI Activator
MonD P450 Oxygenase
Orf29 (capK) Cell wall biosynthesis
lipB Lipase B
orf31 Ion pump
orf32 Membrane structural protein
amA Glycine amidinotransferase

Fig 4

SEQUENCE LISTING

```
   1  GATCAGCGCG GTGGCGTCGT CGGCGTCCAG CTCGTTCTGC GTGGCGGACG
  51  GCAGCGCGAT GTCGGCAGGC ACCTCCCAGA CCCGGCGGCC CGGCACGAAG
 101  CGGGCCGAGG CGCCGCGGCG CTGGGCGTAG GTGTCCACGC GGGCGCGTTC
 151  GACCTCCTTG ACCTGCTTGA GGAGGTCCAG GTCGATGCCC TTCTCGTCGA
 201  CGACGTAACC GGAGGAGTCC GAACACGTCA CGGCGTTGGC GCCCAGGCCG
 251  GCGAGCTTCT GGATGGTGTA GATGGCGACG TTCCCGGAGC CGGACACGAC
 301  CGCCGTCCGG CCTTCGAGGG TCTCGCCGCG CTCACGCAGC ATCGCCGCCG
 351  CGAAGAGGAC GTTGCCGTAG CCGGTCGCCT CCGGACGGAT CAGGGAGCCG
 401  CCCCAGTTGC GGCCCTTGCC GGTGAGGACG CCCGCCTCCC AGCGGTTGGT
 451  GATGCGCCGG TACTGACCGA ACAGATAGCC GATCTCCCGG CCGCCGACGC
 501  CGATGTCGCC CGCGGGCACG TCCGTGTGTT CGCCGATGTG CCGGTACAGC
 551  TCCGTCATGA ACGACTGGCA GAAACGCATG ACTTCCGCGT CGCTGCGGCC
 601  GCGCGGGTCG AAGTCGCTGC CGCCCTTGCC GCCGCCGATG CCGAGGCCCG
 651  TCAGCGCGTT CTTGAAGATC TGCTCGAAGC CCAGGAACTT GATGACGCCG
 701  AGGTTCACCG ACGGGTGGAA GCGCAGGCCG CCCTTGTACG GGCCGAGGGC
 751  GCTGTTGAAC TCCACCCGGA AGCCGCGGTT GACCCGCACG CGACCGTGGT
 801  CGTCCTGCCA CGGCACCCGG AAGACGATCT GGCGCTCCGG TTCGCACAGG
 851  CGCTCGATCA GGCCGGCTTC GGCGTACTCG GGGCGAGCCG CGATGACCGG
 901  CGCCAGGGTC TCGAGGACCT CGCGGGCGGC CTGGTGGAAC TCCGGCTGGG
 951  CCGGGTTGCG GTGTTCGATC TCGGTGAGCA GCTGGGAGAG TGCTGTCTTC
1001  TGCGAGAGAG CTGTCTTCGT GTCGGGTCGC GTGGTCAAAG GAGCCCTTTC
1051  TGGCACGGCC GGCGTAGGCG CTCGGCGCCG TTGCCGTGCG CAGGGAGACG
1101  CTCGAGCCGC AAGTATGACG CGCATGTAAA CACAGCGACC AGCCCCCCGG
1151  TCCAGGGAGT GACCACCATG CGAGACCGGG CCACCGGTAG GGCCACCGGT
1201  CCGGCCTGCG GACCCCGTGT CACTTCCGGC TCGCGGCCAG GGGTGCCGCC
```

```
1251  CGGCGGACCG AATCGGCGGA GGCGGCCAGC AGTGGCATGC GGACGGCCGG
1301  GCTGGGAATG CGGTTCTGGG CGTGCAGCAC TCCCTTGATC ACCGTCGGGT
1351  TCGGTTCGGT GAAGAGGGCG GCGGAAAGGC GGGCGAGGTC GGCTCCGAGA
1401  GCGCGGGCGG GTGCGGCGGA GCCGCGTCGC CACAGCGCGA TCATCTCGGC
1451  GTAGTCGGCG GTACGCAGAT TGGCCGACGC CACGATTCCG CCGTGGGCGC
1501  CCGCAGCGAC CAGCGGCGAG AGGACGATGT CGTCACCGCC GAGCACGGCG
1551  AAGCCGGGCA GGGGCGAGTC GAGCAACTCC ATGGTGGTCG GGTCGATCGA
1601  GCCGGTCGCG TGCTTGATGC CGACGACCTC CGGCAGGCGG CCGAGTGCGG
1651  TGATCGTGCC CGCGCCGAGC GTCTGCCCGG TGCGGTAAGG GATGTCGTAC
1701  ACGACCAGGG GGAGGCCGCC GTGCTCGGCC AGCGCGGCGA AATGAGCCAG
1751  GGTCCCCGCT TCCCCGGGGC GGATGTAGGG CGGCGCGGGG ACCAGCGCGG
1801  CGGCGACGTC ACCCCGGGCC GCCAGCTCTC GCAGGGCCGT GATGGCGGTG
1851  GCGGTGTCGT TGGTGCCCAC CCCGACGATG AGCGGTGCCC CGTGTGCCCG
1901  GCACGCGGCC GAGCAGACGC GGATCACCGT CTCTCTCTCC TCGGCGGTCA
1951  GTGTGGCGGC CTCGGCGGTC GTACCGAGGG CGACGAGCCC GGAGGCGCCG
2001  GCCGACAGCG CCTCGTCGGC GAGTCGGGCC AGCGCCTCGG GGGCCAGGCG
2051  CAGATCGTCG GTGAACGGAG TTACCAGGGG GACGTACAGG CCGTTGAAGA
2101  GCGGTTCGGT GGTCGGTTCG AGGCTCGATG CGAGGGTCAT GCTCTTACCC
2151  TGGCCCACGC CACTCGGTAG ATCCATTTCA GATTCCTGCC GTCACACCTA
2201  AGCTGAACTT ATGCTCGATG TCCGTCGCCT CCATCTGCTC CGCGAACTCG
2251  ACCGGCGGGG CACCATCGCC GCCGTGGCCG AAGCGCTGAC CTTCACCGCG
2301  TCCGCCGTCT CCCAGCAGCT CGGCGTGCTG GAGAGGGAGG CGGGCGTGCC
2351  GCTGTTGGAA CGCAGCGGCA GGCGCGTGGT CCTCACGCCC GCAGGACGCT
2401  CCCTCGTCGC ACACGCCGAC GCGGTGCTGA ACCGTCTCGA ACAGGCGGTC
2451  GCCGAGCTGG CGGGCGCACG GGACGGCATC GGCGGGCCGC TGCGCATCGG
2501  GACGTTCCCT TCCGGCGGCC ACACCATCGT CCCCGGCGCG CTGGCCGAAC
```

2551 TGGCCTCTCG TCACCCCGCG TTGGAGCCGA TGGTGCGGGA GATCGACTCC

2601 GCGCGCGTCT CCGACGGTCT GCGGGCCGGT GAGCTGGACG TGGCCCTCGT

2651 ACACGACTAC GACTTCGTAC CCGCGACGCC GGACACGACC GTGGACGAGG

2701 TGCCTCTGCT CGAAGAGCCG ATGTACCTCG TCACCCATGC CGCGGACACT

2751 GCCACGGACT CCGGCTCCGG GAGCACACTG GCAGCGCTGC TCGGGCCCTG

2801 TGCCGAGGTT CCGTGGATCA CGGCGCGGGA CGGCACGACC GGTCACGCGA

2851 TGGCTGTACG CGCCTGTCAG GCCGCCGGGT TCCAGCCCAG GATCCGCCAC

2901 CAGGTCAACG ACTTCCGCAC GGTGCTGGCT CTGGTCGCCG CCGGGCAGGG

2951 GGCCGGGTTC GTGCCGCGGA TGGCCGCCGA GCCGAGCCCC GCGGGCGTGG

3001 TGCTCACGAA GCTGCCGCTG TTCCGTCGCT CGAAGGTCGC GTTCCGTGCG

3051 GGCGGCGGTG CCCATCCGGC GATCGCCGCT TTCGTGGCCG CGGCGACGAC

3101 GGCGGTCGAA CGCATGGCGG GTTCACGAGG CCCGGCCGGC GGCTCTGAGT

3151 GAACCGGCCG ACCGTGGGAA TGTGTGTGCC CTGGGCCGCA CCATTCGTGG

3201 CCTGGTGACG TCCTGGCGAC GTCCTGACGT CCTGATGTCC GAACGAGAAG

3251 GCGATTTTCC GCGATGGCCG ATGACGCGTA CCTGTTCCTC CTCCCCGACC

3301 GGCACCCCCG ACTGGGAGCG GCCCTCGCCG CCGTCGGTGC CTTGGAATGC

3351 ACGGAAACCC CTGCGGTGCA CGCCTGGTTG CAGGCTCATG AGGCCTCCGT

3401 GTCCTCGGAA CAGGTCAGGA TTCTGCCCGC CGATGCCGAG ACACTCATCC

3451 CGAAGGACGC CGAGCGGCTG CCGGTGCCGT TGAGCGAGGA GGAGGCGCTC

3501 AAGGTCGAGC AGGAGTGCGC GCCCCAGACC GTCACGGACA TGGAGAGCGA

3551 ACTGCTCGCG TTCCGGGAGA CGACCCAGGA CTGGCAGGCC CTCGTGCACC

3601 GGGCCCTGAC CGCGGGCATC CCCGCGCAGC GCATCGCCCG GCTGACCGGA

3651 CTCGACCCGG AGGAGATCGG CCGCCTGTAG GCGCTAGCGG CCGCCCAGTG

3701 CGGACACCAG GATGGCGACC GTGACGGTGT TGAAGACGAA GGCGATGACC

3751 GTGTTCGCCG CCACGGTCCG TCGCATGTCG CGTGAGGTGA CGTCGACATC

3801 GGTGGTGCCG AACGTCGTCA TCGCGGCCAG GGCGAAATAG ACGTAGTCGG

```
3851  CCCAGGCGGG ACTCCGCTCC CCGGGGAATT CCAGTGCCCG CTCGTTCTCC
3901  ACGAGGTTGT CGGCCTGGAA GGTGACGGCG AAGGCCACGA CCACGCAGAT
3951  CCAGGCGGCG ACGACCAGGG CGAGCGCCAC CAGGGTGCGG GGGAGCGCGG
4001  AGAAGGTGGT GCTGAGGTGG CCGGGAAGCC ACAGCACCGC CACCACCAGC
4051  GCGGCAGCCG CGATGAAGAG CGAACCCCCG GGGCCGGGCG CGGTTCCGAG
4101  GACGTAACGC TGCAGGAATG TGCCGCGGGC TTCGCGCCGC GCCCAGGAGC
4151  GGACCTGCTC CGGAGCGACG CTCACGAAGA CGGTCATGGT GATGGCGAGG
4201  TAGGGCAGCA GGTAGGCGAA GAAGACGAGC ACGCCGACAT CCGCTGCCGA
4251  AATCCGCACC ACGGCGTCGA TGGGGAGGAC CACTGCCGCG CACGCCGCGA
4301  CGGCCAGGCT CACCGCCGAC CGGCGCCGTT CGGAAAGCCA GCGATGCACG
4351  GACGAGCCTC TCTGGTCGGG CGTCGGGCCT CGTGTGATCG TGACCGGCTC
4401  CGCGCCCGCC GAAAGCGCGG TGCGATCTCC TGCCCTCGAA CGAGCGAAAC
4451  GCTTGCGCCG GAAAGCCTCC CTGCTGATGC CGACGGCGGC GGCAGTGGCT
4501  GCGGATGCGG ATCGTGCGCT GTGCCCTGAC CCTGGATGGG GGGAGGAACG
4551  CAGAGAGGCA GGTGCGCCCA TGACGGTCAT GGACAAGCTC AAGCAGATGC
4601  TCAAGGGGCA CGAGGACAAG GCCGGCCAGG GAATCGACAA GGCGGGCGAC
4651  TTCGTCGACG GGAAGACGCA GGGCAAGTAC AGCGGTCAAG TCGACACGGC
4701  CCAGGACAAG CTCCGGGACC AGTTCGGCTC GGATCAGCAG GAGCCTCCGC
4751  AGAGGTAGGC AGCGTCAGGG CGGAATCGGT CCGGGCGACC GCTGACCGCT
4801  GATGCAGATG CCGCAGACGT CGGCCCCGCA CTCCTCCGGG TAAATCGGAG
4851  CGTAGGCGGG GCCGACGTGT GCGCGTGCGG CCTCGTCTCT GCCGCCCCTC
4901  TCCGCCCCGT CTCTGGCCCC TTGGTGCCAG TCTGACGGGA AAATGGCACC
4951  ACTTGGTGCC ACGCATGTGC CATGATGGCG TCATCGAGAG CGCGCTGCCC
5001  CGACTCGCGG GCAGGAAGGG CGCGTTCCGC GGAGTCGGCC GTCGGAGGGG
5051  TTGCATCATG GGGACAGCAC AGAGCCAGGA GCAGGCCGCC GCGCCCGGTG
5101  CCTGCGCCGC CTTCGTCCGC TTCGTGCTCT GCGGTGGCGG AGTGGGCCTC
```

5151 GCCTCCAGCT TCGCCGTGGT CGCCCTCGCC TCCTGGGTTC CCTGGGCGCT

5201 GGCCAACGCC CTGGTCGCCG TGGTCTCCAC CGTCGTCGCC ACCGAGCTCC

5251 ACGCCCGCTT CACCTTCGGT GCGGGCGGGC GCGCGACCTG GCGGCAGCAC

5301 GCGCAGTCGG CCGGGTCCGC GGCGGCCGCG TACGCGGTGA CCTGCGTGGC

5351 GATGTTCGTC CTGCAGCAGC TGGTGGCGGC GCCCGGCGCG GTGCTCGAGC

5401 AGGTCGTGTA CCTGTCGGCC TCCGCGCTCG CCGGTGTCGC GCGGTTCGTG

5451 GTGCTGCGCC TCGTCGTCTT CGCCCGGAAC CGCTCGCTGC CCGCCGCGGC

5501 CGCCGTGCGC ACCGCGCGTC CCGTGCGTCG CGTGCCGGCG CCCGTGCCCG

5551 CGACCGTGGC CCACGCCGCA TCGCGCCCGG CCGGCCCCGC GGCGCTCTGC

5601 CCCGCCGCAT GACTCCGTGC CCGCATGTTT GTGCCCCCGG TGCTCCGTGC

5651 GTCCGGGGGC GGGGTGGGCG TCGTGCCCGG GTGGTCCAGG GGTCACGCGG

5701 TGGTGTGTGC CAGTTCCTGG CCGAGGTGGT GGGCGAGCTG TGCGGGCGTG

5751 GGGTTCTCGA CGATGGCGAC CATCGCGATC TCCATCCCGG TCAGCGTCAT

5801 CAGTGTCTTG GTGAGCTCAA GGGCGGTGAG GGAGTTGAGA CCGTTCTCGA

5851 GGAAGTTGCT GTCGTCGCTG AGGGTGGTGT TCAGAAGGGT GCCGGCCTGG

5901 GTGCGGATGG TGTCGGTGAG GAGCTTCTCG CGCTCCTCGG GGGTGGCCGC

5951 GGCGAGCTGC TTCTCCAGCT CGGTGGCGTC CTGGCCGGAG GTGTGGTCGG

6001 TGCTGGTCAT GACTGCTCCT GTGTGAGTGA GGTGTTGGCG GGGGTCACAC

6051 CGCGGCGTGC GCGGTGTGGT CGTGCAGCCA GTAACGCGTG GCCTGGAAGG

6101 AGTACGTCGG GAGGTCGATG GTCCGGGGGT GGGGGGTGCG CCGGACGAGA

6151 GGGGTCCAGT CGACGGTGCC GCCCGTGGTG TGAAGCCGCG CGAGGGCGGT

6201 CAACAGGGCG CTTACGGCGG AGGTTTGCGT GCCTTCCGGT GAGAGCGCGC

6251 CCAGGTGGAG AAGCGTGTGG GTCTCGGGGG TGGGGGGTGC GGTGGGGGCC

6301 GGCGAGGTGA GGTGGTGGTG CCAGTAGTCG GCGGAGGCGA TGGGGGTGTC

6351 GGCCGGGGCA GTGCTGGTGA GCGTGAGCGT GGCGCGTTGG AACGTCAGCT

6401 GCTTCAGCAC GGGCTCGTAG GCGTCGGGCG GAGCCGGTTG TTCACCCTCG

6451 GCGGCCTGGG CGGCAGCGGC GTGGGCGGCG GCCAGGCGGC ACGCGTCGTC

6501 GAGGGTCAGG ATTCCCGCGG CGTACGCGGC GGCGATGTGG CCGACACCGT

6551 CGCCGGTGAG GGTGTGGGGG CGTACCCCCG TTTCCAGGAG CAGCCGCGCG

6601 AGCGCGGTGT GGACCGCGAA GCGCGCCAGT TCGGAGTGGG GAGTGGGGAG

6651 GGGAGTCGGC AGATGGGTGT CGAGGAGCGC GCGCGCTTCG TCGAAGGCGG

6701 ACGCGAAGAG CGGGAACGCC GAGTGGAACT CGGCACCTCC GAAAGCCGCG

6751 CCGAATGTAG CGCCGAATGT CGCGCCGGGT TTGGCTCCGG GTGCCGCCCC

6801 CGTCGTCACC CCGTCGGCCG GGCGGCCGTC GAAGTGCCAG GCGATCTTCT

6851 TCGGGCCGGC CCCGGGCGTG GACCTGACCA GGTCCGGGTG GTCCTCTCCG

6901 GCGGCCAGGG CGCGGGCGGC GGCGAGGAGT TCGGTGTGGT CGGTGCCGGT

6951 GAGGACGGCG CGGTGTTCCA GGGGGCTGCG GGTGGCGGCG AGCGAGTAGG

7001 CGACCTCGGC GGGGGAGGGC GCGGGGTCGG TGGCCGCCAG GTGGGTGACG

7051 AGGGCCTTCG CCTGTGCCCG CAGGGCCTCG GGTGTACGAG CGGACAGGCT

7101 CCAGGCCACC GGGAGTTCCG GGGCAACGGG CGACGTCTGG TCGCGGGCGG

7151 CATCCGGCAC CGGAGCCTCG TCCACCGGCG GCTCTTCGAG GATGAGGTGC

7201 GCGTTCGTGC CGGACGTGGC GAAGGCGGAG ATGCCGACCC GGCGGGGCTC

7251 CTCGCGGCGG GGCCAGTCGA CCGCCTCGGT GAGCAGCCGT ACCGCGCCCT

7301 TCTTCCAGGC GGCGAGGGGC GTCGGGCGGT CGACGTGGAG GGTCGGCGGC

7351 AGGGTGCCGT GCCGGAACGC CTGGACCATC TTGATGAGCG CGGCCGCACC

7401 CGCGGCCCCC TGCGTGTGCC CCGTGTTGGA CTTGACGGAG CCGAGCCACA

7451 GGGGCCGGTC GGGGGAGCGG TCGGCGCCGT AGGTGGCGAG GAGGGCCTGG

7501 ACCTCGATGG CGTCGCCGAT GGGGGTGCCC GTCCCGTGCG CCTCGACGGC

7551 GTCGATCTGG TCCGGGGTGA GCCCGGCGTC GGCGAGGGCG GCGCGGATCA

7601 CATGCTGCTG GGAGGGGCCG TTGGGGGCGG CGAGGCCGTA TCCGGCGCCG

7651 TCCTGGTTGA CCGCGGAGCC GCGGATGACG GCGAGCACCG GGTGGCCGTT

7701 CTTCCTGGCG TCGCCGAGCC GCTCAAGCAG GACGAGGCCG ACGCCTTCAC

7751 CGAGGCCCAT GCCGTCGGCC GCGGCGGCGA ACGGTTTGCA ACGGCCGTCC

7801 TGCGCGAGCG ACTTCTGGTG GGCGAAGGCG TGGAAGGTGT GCGGCGTCGA

7851 CATGACGGTG CCGCCGCCGG CGAGGGCGAG GCCGCACTCC CCGCGGCGCA

7901 GCGCCTGGCA GGCCAGGTGG AGGGCGACCA GGGAGGACGA GCAGGCCGTG

7951 TCCACGCTGA TGGCGGGGCC CTCGAGGCCG AGGGCGTAGG CGATGCGGCC

8001 GGAGACGAGG CTGCCGGACG TGCCGCCGCC CAGATAGGGC AGCAGCTCGT

8051 CGGGCGCGGT CTCGAGCCGT GTCGCGTAGT CGTGCCCGGT GGCGCCGACG

8101 TAGACGCCGG TGAGGGTGGA GCGCAGGGTG TGCGGGGCGA TGTGGCCGCG

8151 TTCGACGGTC TCCCACGCGA GGTGGAGCAT GAGGCGCTGG AGGGGTTCGG

8201 TGGCCACGGC CTCGGTGTCG CTGATGTCGA AGAAGCCCGC GTCGAAGCCG

8251 GCCGCGTCGT CCAGGAACCC GCCGAGCTCC GCGTACGGGC GTTCCTCGGG

8301 GAGTTCCCAG GCGCGGTCGT CGGGGAAGCC GGTGACGGCG TCGCGGCCCT

8351 CGGACACCAG ATCCCACAGG TCGTCCGGGG TGCGGGTCTT GCCGGGCAGC

8401 CGGCAGGCCA TGGAGACGAC GGCGATCGGC TCGTGCTGTG CGGCCTTCAG

8451 TTCGCGCAGC TGCTGCTGGG CCTGGTGGAG CTCGGCCGTC GTCCACTTGA

8501 GGTATTCGAC GAGCTTCTCT TCGTTCGCCA CGGGAATGGT CAGCCTTCCT

8551 GTTCTCGCGC GTGAAGCCTC AGGTGGGACG AGGTCGGGCA AGGTGGGCAG

8601 GCAGGAGCCG CGCGCTGTGG GTGCCAGGGT CGCCGCGGCT GCTTAAGCGG

8651 GTCTAACTCC CGCCTTGCCG CCGGGCATCG CCTCGCACGA GCGGGCCAGC

8701 AGCAGGAGGT CGGCGGCGAT CTCGTCGGGT GCGCCGGCGT GCAGATCGTG

8751 GTCGGAGCCC GGGTACCAGC GCACGCTCAC CTGCTCCAGG GCCGCCTCGG

8801 CGGCGGCCAC CCAGGCCCGT ACCTGGTCGG ACAGTTGGGG GATGGCGGGG

8851 ATGAGGGGCA GCAGCCGCAC CGGCACGGTG ACCTTGGGAT ACCAGTCGGC

8901 CGGTGCCTCC CGTTGCAGGC CGGCGACGAT CGACATGACC TGTGTCGAGG

8951 TCAGGCGGGG GATGAGCAGG CCGTCCGGCC CGACGCGGTA GTCCGCCAGG

9001 CGTGCCTCGA TGGACGTGGG CGACCAGTCG GGATGGGTGG CCCGCAGGTA

9051 GGCGCGCATG TCGGCGGCGC TGGTGGTGCC CTGCTGGGCG CGCCGGACCA

9101 CGTCGGCGGT GCGCTCCCAG AAGGCGCGCA TCACCGGTCC GTCGAACTCG

9151 TACCAGCCGC CGTCGATCAG GGCGAGACCG GCCACCAGGT CCGGGTGCTC

9201 GGCCGCCAGG CGCAGCGCGA GGTGCGCGCC CCAGGAGTGC CCGGCCACCA

9251 GTGCGCCGGA CAGGTCGAGG GCGGTGACGG CCGCCACCAG GTCGGTGACG

9301 ACCGTCGCGT TGTCGTACCC GTCGGGCGGG GTGTCCGACT CGCCGTGGCC

9351 GCGGTGGTCG ACGGCGTAGG CCGGGTGTCC GGCGGCGGCG AGACGGGCGG

9401 CGACCTCGTC CCACATCCGG GCGTTCGACA GCATGCCGTG CAGCAGCAGG

9451 AACGGACGGC CCGGGGCTCC CGGCCCGTCC GCGGGCCGGT ACCTGACATT

9501 GAGGGAGACG GTCTGCGACA CGGGGATGCG GAGGTTCTTC ACAGGCGGGC

9551 CCTTGTGATC CCTTGTGCTG GGGGAGGAAA GCGGGGGCGG CACGCTCAGG

9601 GGCGCTGCGC GGTCGCGAAG ATGTATCCGA GCTCGGGCAT CTTGCCGAGG

9651 GCCGCCTGGT TGTGCAGGAA CAGCTCGTAT CCCTCTACGC CGATGATGTC

9701 GACGTACTCG TCCCGGTGGG CGCGGATCCA CTCGACGTAA CCGTCGTAGG

9751 TCTTGGCGGT CTCGCGGGTG ATGTCGGTCA GTTCGAGGAC GGTCCAGCCG

9801 GCGGCGCGGA AGATGTCGGG GTAGTCCCCG ATGTCGGTGA GCGCGGCGTA

9851 GATCGTGGTG TCGCTGACGG TGGCGGTCCG GGGCCGGCTG GGATCGGGGT

9901 TGAGGTAGAC CATGTCGGCG ATCGGCATCC GCGCGCCGGG CTTCACGACG

9951 CGGTGGGCCT CGGTGAGCAC CTGCTGCTTG TCCGGCATGT GCAGCATGGA

10001 CTCCAGGGCC CAGCAGTGGT CGAAGGAGCC GTCGTCGAAC GGCAGGTTCA

10051 TGGCGTCGAC CTGCTCGAAG CGGACCCGGT CGGCGAGGCC GGCCTCGCGC

10101 GCCCGGCGGT TGCCGCGCTC GACCTGGCGG GCGCTGACGG AGATGCCGAC

10151 CACCTCGACG TCGCGGGCGC GGGCCAGCTG CATGGCCGGG GTGCCGTTGC

10201 CGCAGCCGAT GTCGAGGACG CGGTCGCCGG GGGCCGGGTC GAGGCGGCGG

10251 ATCATCTCGT CGGTCATCTG GACCATGGCC TCGTCGAACG TGGCCTGCTG

10301 CTCGCCGCCG TCGAACCAGT AGCCGTAGTG CAGATTGCCG TCTCCGAGCT

```
10351  GAGTCATCAG GTCGAAGACC TTGTGGTCGT AGTAGTGGCC GATGTCGCTG
10401  GGCTCGGGGG CGACGGTCTT GTTCACCGTC GGGGGCTTCT TGGTCGTCGC
10451  GTTCTTCGTC ACGGCTTCAG CGTCACCGTG CGGCGGCAGG CGCCACAACC
10501  CCACCCCCGC CCCTCAAAAG CCCCTATGGG CCCTCCTCGA CCGCCCCTAG
10551  GGAGCTGCTC TTGACGCGTT CCATACGGAA CGGGTGGTAC CCCTCCGAAA
10601  AAAATGAGAG TACGCTCCCA CTAGATATTG AGCTCTCTTT AGGAGGTCGA
10651  CTCCCATGTC TGCTGATCTG GGTGCGCGGC GGTGGTGGGC CGTCGGTGCT
10701  CTCGTACTCG CCTCGATGGT CGTGGGCTTC GATGTGACGA TCCTGAGCCT
10751  GGCGTTGCCC GCCATGGCCG ACGACCTCGG CGCGAACAAC GTCGAGCTGC
10801  AGTGGTTCGT GACGTCGTAC ACGCTGGTGT TCGCGGCCGG CATGATCCCG
10851  GCCGGCATGC TCGGTGACCG GTTCGGACGC AAGAAGGTCC TGCTCACCGC
10901  CCTGGTGATC TTCGGTATCG CCTCGCTGGC CTGTGCCTAC GCGACGTCCT
10951  CCGGCACCTT CATCGGCGCG CGTGCGGTGC TCGGTCTGGG CGCCGCGCTG
11001  ATCATGCCGA CGACGCTGTC GCTGCTGCCG GTCATGTTCT CCGACGAGGA
11051  GCGGCCGAAG GCCATCGGAG CGGTGGCCGG TGCGGCGATG CTCGCCTATC
11101  CGCTCGGCCC GATCCTCGGC GGCTACCTGC TCAACCACTT CTGGTGGGGC
11151  TCCGTCTTCC TGATCAACGT GCCGGTGGTG ATCCTCGCCT TCCTCGCGGT
11201  CTCCGCCTGG CTGCCCGAGT CCAAGGCCAA GGAGGCCAAG CCGTTCGACA
11251  TCGGCGGCCT GGTGTTCTCC AGCGTCGGTC TCGCCGCGCT GACCTACGGC
11301  GTGATCCAGG GCGGCGAGAA GGGCTGGACG GACGTCACCA CGCTGGTGCC
11351  GTGCATCGGC GGTCTGCTCG CCCTCGTGCT GTTCGTGATG TGGGAGAAGC
11401  GGGTGGCGGA CCCGCTGGTC GACCTCTCGC TGTTCCGCTC GGCCCGGTTC
11451  ACCTCCGGCA CCATGCTCGG CACCGTCATC AACTTCACGA TGTTCGGCGT
11501  GCTCTTCACG ATGCCGCAGT ACTACCAGGC GGTCCTCGGC ACCGACGCGA
11551  TGGGCAGCGG CTTCCGGCTG CTCCCGATGG TCGGCGGTCT GCTCGTGGGT
11601  GTGACGGTCG CCAACAAGGT CGCCAAGGCC CTCGGCCCGA AGACCGCGGT
```

11651 CGGCATCGGC TTCGCCCTCC TCGCCGCCGC CCTGTTCTAC GGCGCCACCA

11701 CGGACGTCAG CAGCGGCACC GGCCTGGCGG CCGCCTGGAC CGCGGCCTAC

11751 GGACTCGGCC TCGGCATCGC CCTGCCGACC GCCATGGACG CCGCCCTCGG

11801 CGCGCTCTCC GAGGACTCCG CCGGCGTCGG ATCCGGCGTC AACCAGTCCA

11851 TCCGTACCCT CGGCGGCAGC TTCGGCGCGG CCATCCTCGG TTCCATCCTC

11901 AACTCCGGCT ACCGCGGCAA GCTCGACCTC GACGGCGTGC CCGAGCAGGC

11951 ACACGGCGCG GTCAAGGACT CCGTCTTCGG CGGCCTCGCG GTGGCCCGGG

12001 CGATCAAGTC CAACGGACTG GCCGACTCGG TGCGTTCCGC GTACGTCCAC

12051 GCCCTGGACG TGGTGCTCGT GGTCTCCGGC GGCCTCGGAC TGCTGGGTGT

12101 GGTGCTGGCG GTGGTGTGGC TGCCCCGCCA TGTTGGTCAG AGCACCGCCA

12151 AGACAGCAGA ATCTGAGCAT GAAGCCGCAG ACGCAGTCTG ACCAGGGCAA

12201 AACAGTGCCT GGTCTGAGAG AACGCAAGAA GGCCCGGACG AAGGCCGCGA

12251 TTCAGCGGGA GGCGGTGCGC TTGTTCAGGG AACAGGGCTA CACCGCCACG

12301 ACCATCGAGC AGATCGCCGA AGCCGCCGAG GTCGCTCCCA GCACCGTCTT

12351 CCGCTACTTC GCGACCAAGC AGGACCTGGT CTTCTCGCAC GACTACGATC

12401 TGCCCTTCGC GATGATGGTC CAGGCCCAGT CACCCGACCT GACGCCGATC

12451 CAGGCCGAGC GGCAGGCCAT CCGCTCGATG TTGCAGGACA TCAGCGAGCA

12501 GGAACTGGCC CTGCAGCGCG AGCGGTTCGT CCTGATTCTC TCCGAGCCGG

12551 AGCTCTGGGG CGCCAGCCTC GGCAACATCG GCCAGACCAT GCAGATCATG

12601 AGTGAGCAGG TGGCCAAACG GGCCGGGCGC GACCCGCGGG ACCCCGCGGT

12651 CCGCGCCTAC ACCGGAGCCG TGTTCGGAGT GATGCTCCAG GTCTCGATGG

12701 ACTGGGCCAA CGATCCGGAC ATGGACTTCG CGACCACGCT GGACGAGGCA

12751 CTCCACTACC TGGAAGACCT GCGGCCCTGA CCGAAGGGGC GGGCGCACAC

12801 CACAGAGCCC GCCCCGGCCA GACGTCGTAC GAGGCGCCAT CGGCCGTCGC

12851 GTACGACCCC CGCGCCCCGG ATTCCCCCGC GGGGCGCGGG GTCAAGGGAA

12901 AAGAGACGAC CGCACGCGGC CACTGTTCCC CCGGCTGCCG CGTCCGGTCC

12951 AACCTGGCGT GCTCCGGCTT CCCTCGACGG AGCACGCCAG GGGTCTGTCC

13001 GGCCCTCTCC CGGCGGCTCC CGTCAGACGC CCGGCCCCGC CGTCAGCGCC

13051 TCGGTCACGA CGGCCGCCAC CTGCTCCTGA CAGCCGTCGA GGTAGAAGTG

13101 CCCGCCGGGC AGCACCCGCA GATCGAACGC CGCGCCGGTC CGCTCCCGCC

13151 ACGTGGCGGC CTGCTCCGGC GACGTCCGCT CGTCGGCGTC CCCGATCAGC

13201 GCCGTGATCG GGCAGTCGAG CCGGCCGGGT CCCGGCGCCT CGTAGGTGGC

13251 CACGGCCCGG TAGTCGGCCC GCAGCGCGGG CAGGACGAGC TCCTGCAGCT

13301 CGGGACTGCG GAAGAACCGC TCGTCGGTGC CGCCCATCGC CCGCAGATGG

13351 GCCAGGATGT CCGCGTCCCC GAACGCCCCC GAACGCCCCG CGGGACGGTA

13401 GGGCCGCGCG AGCCCCCCGG AAACGAACAG GTGCACGGGA AGGCCGGGCC

13451 CGGCCGGTCC CCGCAGCCGC CGCGCCACCT CGAACGCCAC GATGGCGCCC

13501 AGGCTGTGCC CGAACAGCGC GAATGGCTTC CCGTCGCACG GCAGGTGGGG

13551 CACGACGCCG TCGGCGAGCT CGGCCACCGA CGCCAGGCAC GGCTCCGCAT

13601 GACGGTCCTG CCGCCCCGGA TACTGCACGG CGAGCACCTC GACGCCGGGC

13651 GCGAGCAGCC CGGAGAGCCC GAAGTAGTAA CTCGCCGAAC CGCCCGCGAA

13701 CGGAAAGCAG ACCAGCCGCA CCGGCGCCTC TGCCGCAGCG TGGTACCGCC

13751 GCAACCACAC CCCGTTTCCG GTGGCTGCAC CGAACTCGTC ACCGATCTGT

13801 GGTGCCCGCG CCGCCGTGCC CCTGTCCATC GTTCTCCCTC TCCTCGCGTC

13851 GCTCCGCGGG CGCTGTCCTG CCCCGCCCCG AAAGCCCGAT GCCGGCCAAG

13901 CCCCGATGCT GGCCAAACCC CGATGCCGGC CAAGCCCCGA TGCTGGCCGC

13951 GGCCCATAGC GCCCGGCTAA AGCCGCAGGC GGCTAGCCGG GGTTTGGTTC

14001 GCCTTTAGAC AGCCCACCCA CGATGAGCCC GGTACTCGAA GCGATCTCCG

14051 ATTTCGGACC GGGAGCGCCG TTGATGTTTT GTGGCAGCCA GTTGTTCAGC

14101 GCCCGACCGC AGCTGACGTG ATGGCCGCAT CCGCGTCAGC GTCCCCCTCG

14151 GGACCGAGCG CAGGACCCGA CCCGATCGCC GTCGTCGGGA TGGCCTGCCG

14201 CCTGCCCGGA GCACCTGACC CCGACGCGTT CTGGCGGCTG CTCAGCGAGG

14251 GGCGCAGCGC GGTGAGCACC GCACCGCCCG AGCGGCGGCG AGCCGACTCC

14301 GGCCTCCACG GGCCGGGCGG CTACCTGGAC CGGATCGACG GCTTCGACGC

14351 GGACTTCTTC CACATCAGCC CGCGCGAGGC CGTGGCGATG GACCCCCAGC

14401 AGCGGCTGCT CCTCGAACTG AGCTGGGAGG CCCTCGAAGA CGCGGGCATC

14451 CGGCCGCCCA CCCTGGCGCG CAGCCGCACC GGCGTCTTCG TCGGCGCGTT

14501 CTGGGACGAC TACACCGACG TCCTGAACCT GCGGGCGCCG GGCGCCGTCA

14551 CCCGCCACAC CATGACCGGC GTGCACCGCA GCATTCTGGC CAACCGCATC

14601 TCGTACGCGT ACCACCTGGC CGGTCCGAGC CTCACCGTCG ACACCGCACA

14651 GTCCTCCTCG CTCGTCGCCG TCCACCTGGC CTGCGAGAGC ATCCGCAGCG

14701 GCGACTCCGA CATCGCCTTC GCGGGCGGCG TCAACCTCAT CTGCTCGCCG

14751 CGCACCACCG AGCTGGCCGC GGCCCGCTTC GGCGGTCTCT CGGCCGCAGG

14801 CCGCTGCCAC ACCTTCGACG CCCGCGCCGA CGGTTTCGTA CGCGGCGAGG

14851 GCGGCGGCCT CGTGGTGCTC AAGCCCCTCG CGGCGGCACG GCGCGACGGC

14901 GACACGGTGT ACTGCGTGAT CCGGGGGAGC GCCGTCAACA GCGACGGTAC

14951 GACCGACGGA ATCACCCTGC CCAGCGGGCA GGCGCAGCAG GACGTGGTGC

15001 GCCTCGCCTG CCGACGGGCG CGGATCACGC CGGACCAGGT GCAGTACGTC

15051 GAACTGCACG GCACCGGCAC GCCCGTCGGG GACCCGATCG AGGCCGCCGC

15101 GCTCGGCGCC GCCCTCGGGC AGGACGCCGC CCGCGCCGTG CCGCTGGCCG

15151 TCGGCTCCGC CAAGACGAAC GTCGGCCACC TCGAAGCCGC CGCCGGAATC

15201 GTCGGACTGC TCAAGACCGC CCTGAGCATC CACCACCGGC GGCTGGCGCC

15251 GAGCCTGAAC TTCACCACCC CCAATCCGGC CATCCCGCTC GCCGACCTCG

15301 GCCTGACCGT CCAGCAGGAC CTGGCCGACT GGCCGCGCCC CGAACAGCCC

15351 CTGATCGCCG GGGTGTCGTC CTTCGGCATG GGCGGCACGA ACGGTCACGT

15401 TGTCGTGGCG GCGGCGCCCG ATTCGGTGGC GGTACCTGAG CCGGTGGGGG

15451 TGCCTGAGCG GGTGGAAGTG CCTGAGCCGG TGGTGGTTTC TGAGCCGGTG

15501 GTGGTGCCGA CGCCATGGCC CGTGAGCGCT CACAGCGCTT CCGCGCTGCG

15551 CGCGCAGGCC GGTCGCCTGC GGACGCACCT CGCCGCCCAC CGCCCCACCC

15601 CCGACGCCGC GCGGGTCGGC CACGCGCTCG CCACCACCCG TGCGCCCCTC

15651 GCCCACCGCG CGGTCCTGCT CGGCGGCGAC ACCGCCGAAC TGCTGGGCTC

15701 CCTGGACGCG CTGGCCGAGG GCGCGGAGAC CGCGTCCATC GTGCGCGGCG

15751 AGGCGTACAC CGAGGGCAGG ACGGCCTTCC TCTTCAGTGG GCAGGGAGCG

15801 CAACGCCTCG GCATGGGGCG GGAGTTGTAT GCCGTGTTCC CCGTCTTCGC

15851 CGACGCTCTC GACGAGGCGT TCGCCGCCCT GGACGTACAT CTGGACCGCC

15901 CACTGCGCGA GATCGTCTTG GGCGAGACCG ACTCGGGTGG GAACGTCTCG

15951 GGTGAGAATG TCATCGGCGA GGGTGCCGAC CATCAGGCAC TCCTCGACCA

16001 GACCGCCTAC ACCCAGCCCG CGCTCTTCGC GATCGAGACG AGCCTGTACC

16051 GGCTGGCAGC CTCCTTCGGC CTGAAGCCGG ACTACGTCCT CGGCCACTCG

16101 GTCGGCGAGA TCGCCGCCGC GCACGTCGCC GGTGTCCTCT CGTTGCCGGA

16151 CGCGAGCGCT CTGGTGGCCA CGCGGGGACG GCTCATGCAG GCGGTTCGCG

16201 CGCCCGGCGC GATGGCCGCG TGGCAGGCCA CGGCGGACGA GGCGGCCGAA

16251 CAGCTCGCCG GGCACGAGCG GCACGTCACC GTGGCCGCCG TCAACGGCCC

16301 CGACTCCGTG GTCGTCTCCG GCGACCGCGC CACCGTCGAC GAACTGACCG

16351 CCGCCTGGCG GGGACGCGGC CGCAAGGCCC ACCACCTGAA GGTCAGCCAC

16401 GCCTTCCACT CCCCGCACAT GGACCCCATC CTCGACGAGC TGCGCGCGGT

16451 CGCCGCCGGC CTGACCTTCC ACGAGCCGGT CATTCCCGTC GTCTCCAACG

16501 TCACCGGTGA ACTGGTGACC GCGACCGCGA CCGGGAGCGG CGCCGGGCAG

16551 GCCGACCCCG AGTACTGGGC GCGGCATGCG CGCGAGCCCG TGCGGTTCCT

16601 GTCCGGGGTG CGGGGGCTGT GCGAGCGCGG GGTGACCACG TTCGTCGAGC

16651 TCGGCCCGGA CGCACCGCTG TCCGCGATGG CCCGCGACTG CTTCCCCGCC

16701 CCCGCGGACC GGAGCCGTCC GCGCCCCGCC GCCATCGCCA CATGCCGCCG

16751 CGGGCGCGAC GAGGTGGCCA CGTTCCTGAG GTCGCTGGCC CAGGCGTACG

16801 TCCGCGGCGC CGATGTCGAC TTCACCCGGG CCTACGGCGC CACCGCCACG

16851 CGCCGCTTCC CCCTCCCCAC GTATCCCTTC CAGCGCGAGC GCCATTGGCC

16901 TGCCGCTGCC GGGGTGGGGC AGCAGCCGGA GACCCCGGAA CTTCCGGAAT

16951 CCTCGGAGTC CTCGGAGCAG GCAGGGCATG AGCGGGAGGA GGGGGCGCGC

17001 GCGTGGGGCG GGCCTGAAGG GCGGCTTGCC GGGCTCTCCG TGAACGACCA

17051 GGAGCGGGTC CTCCTCGGCC TGGTCACCAA GCACGTGGCC GTCGTGCTCG

17101 GGGACGCCTC GGGCACGGTA CAAGCCGCCC GCACCTTCAA GCAGTTGGGC

17151 TTCGACTCGA TGGCCGCCGC CGAGCTGAGC GAACGGCTCG GCACGGAGAC

17201 GGGCCTGCCG TTGCCCGCCA CCCTCACCTT CGACTACCCG ACCCCTCTGG

17251 CCGTCGCCGC GCACCTGCGC GCGGAGCTCA CCGGTACGCC CGCCCCGGCC

17301 GGCTCCGCGC CCGCCACGGG CGCCCTCGGC GCGGGTGACC TCGGCACGGA

17351 CGAGGACCCG GTCGCCATCG TGGCCATGAG CTGCCGCTAT CCCGGCGGCG

17401 CAGGCACGCC CGAGGACCTG TGGCGGCTGG TCGCGGACGG CGCCGACGCG

17451 ATCGGAGACT TCCCCACCGA CCGCGGCTGG GACCTGGCGC GGCTGTTCCA

17501 CCCCGACCCC GACCGGTCGG GCACCAGCTG CACGCGGCAG GGCGGATTCC

17551 TGTACGACGC CGCCGACTTC GACGCCGAGT TCTTCGACAT CAGCCCGCGC

17601 GAGGCCCTGG CCGTCGACCC GCAGCAGCGG CTGCTCCTCG AGTGCGCCTG

17651 GGAGGCCTTC GAACGGGCGG GCCTGGACCC GCGGGCGCTC AAGGGCAGCC

17701 CCACCGGCGT GTTCGTCGGC ATGACGGGGC AGGACTACGG CCCCCGTCTG

17751 CACGAGCCGT CCCAGGCCAC CGACGGCTAT CTGCTGACCG GCAGCACGCC

17801 GAGCGTGGCC TCGGGCCGCC TGTCGTTCAG CTTCGGCCTT GAGGGGCCCG

17851 CCCTGACGGT GGACACGGCC TGCTCGTCGT CGCTGGTCAC GCTCCATCTC

17901 GCGGCGCAGG CGCTGCGGCG CGGCGAGTGC GACCTGGCCC TCGCCGGCGG

17951 CGCCACCGTC CTGGCCACGC CGGGCATGTT CACCGAGTTC TCGCGGCAGC

18001 GGGGCCTGGC CCCCGACGGC CGCTGCAAGC CGTTCGCGGC GGGCGCCGAC

18051 GGCACGGGCT GGGCCGAGGG CGTGGGCCTG GTCCTCCTCG AAAGGCTCTC

18101 CGAGGCCCGG CGCAAGGGGC ACGCCGTCCT CGCGGTGATC CGGGGTTCGG

18151 CGATCAACCA GGACGGCGCG AGCAACGGCC TGACCGCGCC CAACGGCCCC

18201 TCGCAGCAAC GCGTCATCCG TGCCGCGCTC GCGGCCGCCC GGCTCACCGC

18251 GGACGAGGTC GACGTAGTGG AGGCGCACGG CACCGGCACC ACGCTCGGCG

18301 ACCCGATCGA GGCGCAGGCC CTGCTCGCCA CGTACGGCCA AGGGCGTTCG

18351 GCGGAGCGGC CGTTGTGGCT CGGGTCGGTG AAGTCGAACA TCGGTCACAC

18401 GCAGGCCGCC GCGGGTGTCG CGGGCGTCAT CAAGATGGTG ATGGCGATGC

18451 GCCACGACCT GCTCCCCGCC ACCCTGCACG TCGACGAGCC GAGTGGCCAC

18501 GTGGACTGGT CCACCGGCGC GGTGCGACTG CTCACCGAGC CGGTCGTCTG

18551 GCCGCGCGGC GAACGTCCGC GCCGCGCCGC GGTGTCGTCC TTCGGCATCT

18601 CCGGCACGAA CGCGCACCTG GTGCTCGAAG AGGCGGGGCA GGACGAGTAC

18651 GTTGCGGGAG CCGCCGACGA CGCCGGGCCG GTGGACGGTG CTGTGCTGCC

18701 GTGGGTGGTT TCCGGACGGA CCGGAGCGGC GCTGCGCGAA CAGGCCCGCC

18751 GTTTGCGTGA GTTGGTGACC GGCGGCTCGG CCGATGTCTC TGTGTCCGGG

18801 GTGGGCCGGT CGCTGGTCAC CACGCGGGCG GTGTTCGAGC ACCGGGCCGT

18851 GGTCGTGGGC CGCGACCGGG ACACGCTGAT CGGCGGCCTC GAGGCCCTTG

18901 CGGCGGGTGA CGCGTCGCCG GACGTCGTGT GCGGGGTCGC GGGCGATGTC

18951 GGCCCCGGCC CGGTGCTGGT GTTCCCCGGG CAGGGCTCGC AGTGGGTGGG

19001 CATGGGAGCC CAACTCCTTG GCGAGTCCGC GGTGTTCGCG GCGCGGATCG

19051 ACGCGTGCGA GCAGGCGCTG TCCCCGTACG TCGACTGGTC ACTGACAGAG

19101 GTCCTGCGCG GGGACGGGCG CGAACTGTCG CGCGTCGACG TCGTCCAGCC

19151 CGTGCTGTGG GCGGTGATGG TCTCGCTCGC CGCCGTCTGG GCGGACCACG

19201 GCGTCACCCC GGCCGCCGTC GTCGGGCACT CCCAGGGAGA GATCGCCGCT

19251 GTGGTCGTCG CCGGCGCGCT CACCCTGGAG GACGGCGCCA AGATCGTGGC

19301 CCTGCGCAGC CGGGCGCTGC GTCAGCTCTC GGGCGGGGGC GCCATGGCCT

19351 CCCTCGGGGT GGGCCAGGAA CAGGCAGCCG AACTCGTCGA GGGCCACCCC

19401 GGAGTGGGCA TCGCCGCCGT CAACGGCCCG TCATCGACCG TCATTTCAGG

19451 CCCGCCCGAG CAAGTCGCCG CCGTCGTCGC CGACGCCGAG GCGCGCGAGC

19501 TGAGAGGCCG CGTCATTGAC GTGGACTACG CCTCGCACAG CCCCCAGGTC

19551 GACGCCATCA CCGACGAACT CACCCACACC CTGTCCGGCG TCCGCCCCAC

19601 CACGGCCCCG GTGGCGTTCT ACTCGGCCGT GACCGGAACC CGCATCGACA

19651 CGGCGGGCCT CGACACCGAC TACTGGGTCA CCAACCTGCG CCGCCCGGTC

19701 CGGTTCGCCG ACGCCGTCAC CGCGCTCCTC GCCGACGGCC ACCGGGTCTT

19751 CATCGAGGCC AGCAGCCACC CCGTCCTCAC CCTCGGCCTC CAGGAGACCT

19801 TCGAGGAGGC CGGGGTCGAC GCCGTCACCG TCCCCACCCT GCGGCGCGAG

19851 GACGGCGGCC GGGCACGCCT GGCCCGCTCG CTGGCACAGG CCTTCGGCGC

19901 CGGGTGCGCG GTGAGGTGGG AGAACTGGTT TCCGGCCACC GGTACGTCCA

19951 CCGTGGAGCT GCCGACGTAC GCCTTCCAGC GTCGCCGTTA CTGGCTGGAG

20001 GCCCCCACGG GCACCCAGGA CGCGGCGGGC CTGGGCCTCG CCGCTGCGGG

20051 GCACCCGCTC CTCGGGGCGG CCACCGAGAT CGCGGACGGC GACATCCGCC

20101 TGCTCACCGG CCGTATCAGC AGGCACAGCC ACCCCTGGCT CGCTCAGCAC

20151 ACCCTCTTCG GTGCCGCGGT CGTGCCCGCC TCCGTCCTCG CGGAATGGGC

20201 GCTGCGCGCC GCCGACGAGG CCGGCTGCCC GCGTGTCGAC GACCTCACGC

20251 TGCGCACCCC GCTGGTGCTG CCCGAGACCG CGGGCGTGCA GGTGCAGATC

20301 GTGGTCGGCC CGGCCGACGC GCGGGACGGG CACCGCGACT TCCACGTCTA

20351 CGCCCGCCCC GACGGCAAGG ACGCCTCTGA GGGCGAGGGC ATCGCCGAGG

20401 GCGAGGGTGC CTCTGAGGGC GAGGGTGCCT CCGGCGGCAC CGATGCGCCG

20451 TGGACCTGCC ATGCCGACGG CCGACTGGTC GCCGAGCCCA CCGGCACGGC

20501 CTCGGAGGAC TCCCCGGACA CGGTGTGGCC GCCGCCCGGC GCCGAACCCG

20551 TCGACCTGGG CGACTTCTAC GAGCGGGCCG CCGCCACCGG AGTCGGCTAT

20601 GGACCGGTCT TCACGGGGCT GCGCGCCCTG TGGCGGCGGG ACGGCGAGCT

20651 GTTCGCCGAG GCGGTGCTGC CGCAAGAAGC CCCGGAAACC GCCGGGTTCG

20701 GCATGCACCC GGCGCTCCTC GACGCCGCAC TGCACCCCGC ACTCCTCGGC

20751 GAGCGGCCGG CCGAGGAGGA CAAGGTGTGG CTGCCGTTCA CGCTGACCGG

20801 AGTGACCCTG TGGGCCACCG GTGCCACCTC TGTACGCGTC CGTCTCACCC

20851 CGCTGGACGA CGACCCCGAC GCGTCGGCGG ACGGGCGGGC CTGGCGGGTC

20901 GGCGTGAGCG ACCCGACCGG CGCGGAGGTG CTGACCTGCG AGGCCCTGGT

20951 CGCGGTGGCG GCGGGCCGCC GCGAGCTGCG GGCCGCGGGG GAGCGGGTGT

21001 CCGATCTGTA CGCGGTGGAG TGGGTGCCGG TGCCGGGCCC GGGGCCGGTG

21051 GGTGAGGGTG CTGACTTCTC GGGCTGGGCC GGTCTGGGGG AGTGCGGGGA

21101 GCGTTGGGAG TGCGTGGGGC GCGTGGAGCG CTGGTACGAG GACCTGGACG

21151 CTCTCGGCGC GGCTGTCGAG GGTGGGGCTT CGGTGCCCTC TGTCGTTCTC

21201 GCCACCGCGG CTGCCGCCCC TGGTGGAGCG GGCGACGGAG CCGCCGATGC

21251 GCTGAGCGCG GTGCGGTGGA CCGGCGCGCT CCTCGATCAG TGGCTCGCCG

21301 ACGCGCGGTT CGCCGACGCC CGGCTGGTGG TGATCACGTC CGGCGCGGTC

21351 GCCACGGGTG ACGATTTCCT TCCCGACCCG GCCGCCGCGG CGGTACGAGG

21401 ACTGGTCGAG CAGGCGCAGG TCAGGCACCC CGGCCGCATC CTCCTCGTCG

21451 ACACGGAAGC CGGGGCCGGG CTCGGGGTCG GCGCCGGAGT GGATGACGCG

21501 CTCCTGGAAC AGGCCGTGGC CATGGCTCTC GGCGCCGACG AACCGCAACT

21551 CGCCCTGCGC GCGGGGCGGG TCCTGGCGCC CCGCCTCACC GCACCCCAGG

21601 ATGCGGCCGT CACCGAAGCG GCGCGACCGC TCGACCCGGA CGGCACCGTA

21651 CTCATCACAG GGCCGGCCGG TGCTCCGGTG GCCGACCTCG CCGAACACCT

21701 CGTACGCACC GGGCAGTGCA GGCATCTGCT GCTCCTGCCT GGAGACGGTG

21751 AACTGGAGGA AATGGCCGAG GAGTTGCGGG GCCTCGGCGC CACCGTGGAC

21801 CTGAGTACCG CCGACCCGGC GGACCCGACC GCCCTCGCCG AAGTGGTCGC

21851 CGCCGTCGAG GGGGACCATC CTCTTACGGG GGTCATCCAC GCCACCGGAG

21901 TCGTGGACGC GTTCGATCCC GGCGACTCGG CGAGCGACTT GATGATCGAC

21951 TCGGCGAGCG ATTCGTTCGC CGAGGCATGG TCGTCGAGGG CGGGCGTCAC

22001 CGCCGCACTG CACACCGCGA CCGCCCACCT TCCCCTGGAC CTGTTCGCCG

22051 TCCTGTCCCC GGCGGGCGCG GACCTGGGCA TTGCCCGGTC GGCGGCCGCC

22101 GCGGGCGCCG ACGCCTTCAG CGCGGCACTC GCCCTGCGCC GGCACACGAC

22151 CGTCACGACG GACACGACAG CCCCGCCGCG CACGACAGCC CCGCCGCGAA

22201 CGACAGCCTC GCCGCGCACG ACAGCCCTGT CGTCGTCGCG CACGACGGGC

22251 GTGGCCCTCG CCTACGGGCC GCCCACCGCG CCGAGGCCCG GCATCAAGGG

22301 GACGGCGCCC GGTCGGATCC CCGTGCTGCT CGACGCCGCT CGCGCTCACG

22351 GGGGCGGTTC GCCCCTGCTC GGGGCCCGCT TGGCCGCGCG TGCCCTGGCC

22401 GCCGAGTCCG CCGCCGAGGG CGTCGCCGGC CTGCCCGCGC CGCTGCGCGC

22451 GCTGGCAGTG GCCGCAGCCG CGGCCGGAGC ACCGACCCGG CGCACCGCCG

22501 CCGACCGCAA GCCCCCCGCG GACTGGCCGG CCCGACTGGC CCCCCTGTCC

22551 GCCCCCGAAC AACTCCGTCT GCTCATCGAC GCCGTACGCA CCCACGCCGC

22601 CGCGGTCCTC GGCCGCACCG ACCCGGAAGC GCTGCGCGGG GACGCCACCT

22651 TCAAGCAGCT CGGCCTTGAC TCGCTGACCG CCGTGGAGCT GCGCAACCGG

22701 CTCGTGGAGG ACACCGGTCT GCGCCTGCCC ACCGCCCTCG TCTTTCGCTA

22751 CCCGACCCCC GCGGCGATCG CCGCGCACCT CCGCGAGCGG CTGACCAGCC

22801 CGAGCGAGAC GACCGCCACA CAGAGGTCCG GAGGGCAGAC GCCCGCAGCG

22851 GGGCAGGCGT CGTCCGCGCT CGCCCCCGGC GGATCGGCCG CCGGACCGCC

22901 CGCCGCAGAC ACCGTGCTGA GCGACCTGAC CCGCATGGAG AACACCCTCT

22951 CCGTGCTCGC CGCCCAGCTG CCCCACACCG AGACGGGTGA GATCACCACC

23001 CGGCTCGAAG CGCTCCTCAC GCGCTGGAAG ACCACGAACG CCACGGCGAA

23051 CGACAGCGGC GACGGCAACG GCGGCGATGA CGACGCCGCC GAACGCCTCA

23101 AGGCCGCGTC CGCCGACCAG ATCTTCGACT TCATCGACAA CGAGCTTGGT

23151 GTCGGGCACG GCACCTCGCG CGTGACCCCC ACTCCGAAGG CCGGGTGACC

23201 GCACATGGCG AGTGAAGAGC AACTGGTCGA ATATCTGCGC AGGGTGACCA

23251 CCGAGCTCCA TGACACGCGT CGGCGCCTGG TGCAGGAGGA GGACCGCAGG

23301 CAGGAACCGG TGGCCCTGGT CGGCATGGCC TGCCGCTTCC CGGGCGGCGT

```
23351  GGCCTCACCG GAGGACCTCT GGGACCTGGT CGCCGCGGGC AAGGACGCCA
23401  TCGAGGACTT TCCCACCGAC CGGGGCTGGG ACCTGGAGGC GCTCTACGAC
23451  CCGGACCCGG CCGCGTACGG GACCAGCTAT GTCCGCCACG GCGGGTTCGT
23501  GGACGACGCG GGCTCCTTCG ACGCCGACTT CTTCGGCATC AGCCCGCGAG
23551  AAGCCCTGGC GATGGACCCG CAGCAGCGGC TGATGCTGGA GACGTCCTGG
23601  GAGCTGTTCG AGCGCGCCGG CATCGAACCC GTCTCCCTCA AGGGCAGCCG
23651  TACGGGCGTC TACGCCGGGG TGTCCAGCGA GGACTACATG TCCCAACTGC
23701  CCCGCATCCC CGAGGGGTTC GAGGGGCACG CCACCACCGG CAGCCTCACC
23751  AGCGTCATCT CGGGCCGGGT CGCGTACAAC TACGGCCTCG AAGGCCCGGC
23801  CGTCACCGTC GACACAGCCT GTTCCGCCTC GCTCGTCGCC ATCCACCTGG
23851  CGAGCCAGGC GCTGCGCCAG CGTGAGTGCG ACCTCGCCCT CGCGGGCGGT
23901  GTGCTCGTAC TGTCCAGCCC GCTCATGTTC ACCGAGTTCT GCCGCCAGCG
23951  GGGCCTTGCT CCCGACGGCC GCTGCAAGCC GTTCGCCGCC GCGGCGGACG
24001  GCACCGGCTT CTCGGAGGGC ATCGGTCTGC TCCTCCTGGA GCGCCTGTCC
24051  GACGCGCGCC GCAACGGCCA CAAGGTGCTC GCGGTGATCC GCGGCTCCGC
24101  CGTCAACCAG GACGGCGCGA GCAACGGCCT GACCGCCCCC AACGACGCCG
24151  CGCAGGAACA GGTCATCCGC GCCGCCCTCG ACAACGCCCG CCTCACCCCG
24201  TCCGAGGTGG ACGCCGTCGA GGCGCACGGC ACCGGCACCA AACTGGGCGA
24251  CCCCATCGAG GCCGGAGCGC TGCTCGCCAC CTACGGGCAA CACCGCGCCC
24301  GGCCCCTCCT CCTCGGCTCC CTCAAGTCCA ACATCGGCCA CACCCACGCC
24351  ACCGCGGGCG TCGCCGGTGT CATCAAGACC GTCATGGCGA TCCGCAACGG
24401  TCTGCTCCCC GCCACCCTCC ACGTCGAGGA ACTGAGCCCG CACGTCGACT
24451  GGGACGCGGG CGCGGTCGAG GTCGTCACGG AGCCCACCCC GTGGCCCGAG
24501  ACCGGCCACC CCCGGCGCGC GGGCGTCTCC GCGTTCGGGA TCTCCGGGAC
24551  GAATGCGCAC TTGATCCTGG AGGAGGCGCC GCCGGAGGAG GATGTGCCCG
24601  CCCCCGTGGT TGTGGAGTCG GGCGGGGTCG TTCCGTGGGT GGTGTCCGGG
```

24651 CGGACGCCGG AGGCGCTGCG TGAACAGGCC CGGCGACTCG GCGAGTTCGT

24701 GGCAGGCGAC ACGGACGCAC TGCCGAACGA GGTCGGCTGG TCCTTGGCCA

24751 CGACCCGGTC GGTGTTCGAG CACCGGGCTG TGGTCGTGGG GCGTGACCGG

24801 GATGCGTTGA CGGCTGGCCT GGGGGCGTTG GCTGCGGGTG AGGCTTCGGC

24851 GGGTGTGGTG GCCGGGGTGG CCGGTGATGT GGGTCCTGGG CCGGTGTTGG

24901 TGTTTCCGGG GCAGGGGGCG CAGTGGGTGG GCATGGGTGC CCAGCTGTTG

24951 GACGAGTCTG CGGTGTTCGC GGCGCGGATC GCGGAGTGTG AGCGGGCCCT

25001 GTCGGCGCAT GTGGACTGGT CGCTGAGTGC GGTGTTGCGC GGGGACGGGA

25051 GTGAGCTGTC CCGGGTGGAA GTGGTGCAGC CGGTGCTGTG GGCGGTGATG

25101 GTCTCGCTGG CTGCGGTGTG GGCGGATTAC GGGGTCACTC CGGCTGCCGT

25151 GATCGGGCAC TCGCAGGGTG AGATGGCTGC CGCGTGTGTG GCGGGGGCGC

25201 TGTCGCTGGA GGATGCGGCG CGGATCGTAG CGGTACGCAG TGACGCGCTT

25251 CGTCAGCTGC AAGGGCACGG CGACATGGCC TCGCTCAGCA CCGGTGCCGA

25301 GCAGGCCGCT GAGCTGATCG GTGACCGGCC GGGCGTGGTC GTCGCGGCGG

25351 TCAATGGGCC GTCGTCTACG GTGATTTCAG GGCCGCCGGA GCATGTGGCA

25401 GCCGTGGTCG CGGATGCGGA GGCACGTGGT CTGCGCGCCC GTGTCATCGA

25451 CGTCGGCTAT GCCTCGCATG GCCCCCAGAT CGACCAGCTC CACGATCTGC

25501 TGACCGAACG CCTGGCCGAC ATCCGGCCCA CGAACACGGA CGTGGCCTTC

25551 TATTCGACGG TCACCGCCGA GCGCCTGACG GACACCACGG CCCTGGACAC

25601 GGATTACTGG GTCACCAACC TCCGTCAGCC CGTCCGGTTC GCCGACACCA

25651 TCGAAGCCCT TCTCGCGGAC GGCTACCGCC TGTTCATCGA GGCCAGCGCC

25701 CACCCCGTGC TGGGCCTGGG CATGGAGGAG ACCATCGAGC AGGCGGACAT

25751 GCCCGCCACC GTCGTCCCCA CCCTCCGCCG CGACCACGGC GACACCACCC

25801 AGCTCACCCG CGCCGCCGCC CACGCCTTCA CCGCCGGCGC CGATGTCGAC

25851 TGGCGGCGCT GGTTCCCGGC CGACCCCGCC CCCCGCACGA TCGATCTCCC

25901 CACCTACGCC TTCCAGCGCC GCCGCTACTG GCTGGCCGAC ACAGTGAAGC

25951 GGGACAGCGG ATGGGACCCG GCCGGGTCGG GGCATGCCCA GTTGCCGACC

26001 GCGGTCGCCC TCGCCGACGG GGGAGTGGTG CTGAACGGCC GGGTGTCCGC

26051 CGAGCGCGGT GGCTGGCTGG GCGGGCATGT GGTGGCGGGG ACGGTTCTGG

26101 TGCCGGGTGC GGCGTTGGTG GAGTGGGTGT TGCGGGCCGG TGATGAGGCG

26151 GGTTGCCCCT CGCTTGAGGA GTTGACGCTC CAGGCGCCGT TGGTGTTGCC

26201 CGAGTCGGGT GGGTTGCAGG TTCAGGTGGT CGTGGGTGCG GCTGATGAGC

26251 AGGGCGGCCG TCGTGACGTA CATGTGTATT CGAGGTCTGA GCAGGACGCG

26301 TCGGCGGTGT GGCAGTGCCA TGCCGTCGGT GAGCTCGGGC GCGCGTCGGT

26351 GGCGCGGCCG GTGCGGCAGG CCGGGCAGTG GCCTCCGGCG GGGGCCGAGC

26401 CGGTGGAGGT GGGCGGCTTC TACGAGGGGG TCGCGGCCGC CGGTTACGAG

26451 TACGGTCCGG CGTTCCGTGG GCTGCGCGCG ATGTGGCGGC ACGGTGATGA

26501 CCTCCTTGCG GAGGTCGAGC TGCCGGAGGA GGCCGGTTCG CCGGCCGGTT

26551 TCGGCATCCA CCCGGCGCTG CTGGACGCCG CCCTGCACCC GCTGCTCGCA

26601 CAGCGGAGCC GGGACGGGGC CGGGGCGGGG GCCCACGGCG GGCAGGTGCT

26651 GCTGCCTTTC AGCTGGAGCG GTGTTTCCCT GTGGGCCAGC GAGGCCACCA

26701 CTGTGCGGGT GCGGCTCACC GGGCTGGGAG GAGGGGACGA CGAGACGGTG

26751 TCCCTGACGG TAACCGACCC CGCCGGTGGC CCCGTGGTGG ACGTGGCAGA

26801 GCTGCGGTTG CGGTCGACGA GCGCCCGGCA GGTGCGGGGT TCGGCAGGCC

26851 CCGGCGCGGA CGGGCTCTAC GAGCTGCGGT GGACACCGTT GCCCGAGCCG

26901 CTTCCCGTAC CGGCCCCCGC GAACGGTCGC GATGTGGCCG CCGACCTGTC

26951 CGGATGCGCG GTGCTCGGCG AACTGGTCGC GGAACCGGGC CCGGGCATCG

27001 ACCTGGAGGG CTGCCCCTGC TACCCGGGCG TCGGCGCGCT CGCCGACAAC

27051 GCCTCCCCGC CCTCCATGAT CCTCGCCCCC GTGCACAGCG ACACCACAGG

27101 CGGCGACGGA CTCGCCCTGA CGGAACGGGT GTTGCGCGTC ATCCAGGACT

27151 TCCTGGCTGC ACCGAGTCTG GAACAGAAAC AGACGCGCCT GGCCTTCGTG

27201 ACCCGGGGCG CGGCGGACAC AGGTAGCACG ACGGGAGGCT CGGCTGCCCC

27251 GGCAGAGGCA GTCGACCCGG CGGTCGCGGC CGTATGGGGC CTAGTACGCA

27301 GCGCGCAGTC GGAGAACCCC GGCCGCTTCG TACTGCTGGA CACCGACGCG

27351 CCCCTCGACC AGGCGTCCGT TGCCCCTCTC GTGGACGCGG TGCGGTCTGC

27401 CGTGGAGGCG GACGAGCCCC AAGTCGCCCT GCGCGGGGGA CGGTTGCTCG

27451 TGCCCAGGTG GGCGCGGGCC GGCGAGCCCG TCGAGCTGGC CGGGCCGGCC

27501 GGAGCGCGGG CGTGGCGGCT GGTGGGCGGA GACTCCGGGA CGCTGGAGGC

27551 CGTCGTGGCG GAGGCTTGCG ACGACATTGT GCTGCGCCCG TTGGCGCCGG

27601 GCCAGGTCCG CGTCGCCGTC CATACGGCCG GGGTCAATTT CCGTGACGTC

27651 CTGATCGCCC TGGGCATGTA CCCGGACCCG GACGCGCTGC CCGGCACCGA

27701 GGCGGCCGGC GTGGTGACGG AGGTCGGGCC GGGCGTCACC CGTCTGTCGG

27751 TGGGCGACCG CGTGATGGGC ATGATGGACG GCGCCTTCGG CCCGTGGGCC

27801 GTCGCCGACG CGCGCATGCT GGCCCCGGTC CCGCCCGGCT GGGGCACCCG

27851 GCAGGCGGCC GCCGCTCCCG CCGCGTTCCT GACGGCTTGG TACGGGCTGG

27901 TGGAGCTGGC CGGTCTGAAG GCGGGCGAGC GTGTGTTGAT CCATGCCGCC

27951 ACGGGTGGTG TGGGGATGGC GGCGGTGCAG ATCGCCCGGC ATGTGGGTGC

28001 CGAGGTGTTC GCCACCGCGA GTCCGGGCAA GCACGCCGTG CTGGAGGAGA

28051 TGGGCATCGA CGCCGCCCAC CGCGCCTCGT CGCGCGACCT CGCCTTCGAG

28101 GACGCCTTCC GGCAGGCCAC CGACGGCCGT GGCGTGGACG TCGTCCTCAA

28151 CAGCCTCACC GGTGAACTGC TCGACGCGTC CCTGCGATTG CTCGGCGACG

28201 GCGGGCGCTT CGTGGAGATG GGCAAGAGCG ATCCGCGCGA CCCCGAGCTG

28251 GTCGCGCTGG AGCACCCCGG GGTGTCGTAC GAGGCCTTCG ACCTCGTCGC

28301 CGACGCCGGG CCCGAGCGGC TCGGGCTGAT GCTCGACAGG CTCGGCGAGC

28351 TCTTCGCCGG CGGATCACTG GTACCGCTGC CGGTCACCGC ATGGCCGCTG

28401 GGGCGGGCGC GAGAGGCGCT CCGCCACATG AGTCAGGCGA GGCACACCGG

28451 CAAGCTGGTG CTCGACGTGC CCGCGCCGCT CGACCCCGAC GGCACCGTCC

28501 TCGTCACCGG GGGTACCGGC ACCATCGGCG CCGCCGTGGC CGAACACCTG

28551 GCGCGTACCG GGGAGAGCAA GCACCTGCTC ATCGTCAGCC GCAGCGGGCC

28601 GGCCGCCCAC GGCGCCGAGG AACTTGTCTC TCGTATAGCC GAGTTCGGGG

28651 CCGAAGCCAC CTTCGTCGCT GCCGACGTGA GTGAGCCCGA CGCGGTCGCC

28701 GCCCTGATCG AAGGGATCGA TCCGGCCCAT CCGCTGACCG GTGTCGTGCA

28751 TGCCGCCGGA GTACTCGACA ACGCTCTGAT CGGCTCCCAG ACCACCGAAA

28801 GCCTCACCCG CGTATGGGCG GCGAAGGCCG CCGCCGCGCA GCAACTCCAC

28851 GAGGCCACGA GGGAGTCGAG GCTGGGACTG TTCGTGATGT TCTCCTCCTT

28901 CGCCTCCACC ATGGGCACCC CAGGGCAGGC CAACTACTCC GCCGCCAACG

28951 CCTATTGCGA CGCGCTGGCC GCTCTCCGAC GCGCGGAGGG GCTCGCCGGC

29001 CTGTCCGTGG CGTGGGGGTT GTGGGAGGCC ACCAGCGGCC TGACCGGGAC

29051 GTTGTCGGCG GCCGACCGGG CCCGCATCGA CCGGTACGGC ATCAGGCCGA

29101 CCAGCGCGGC ACGCGGCTGC GCCCTGCTGG CAGCGGCACG CGCCCACGGG

29151 CGCCCCGACC TGCTCGCCAT GGACCTGGAC GCCCGCGTAC CCGCCGCGTC

29201 CGACGCTCCG GTCCCCGCCG TGCTGCGCAC TCTGGCGGCC GCCGGAGCGC

29251 CCGCCACCGC CCGTCCCACC GCGGCGGCGG CCGCTGACGG GGCGACGGAC

29301 TGGTCCGGCA GGCTCGCCGG CCTCACCGAG GAGGCACGGC TCGAACTCCT

29351 CACCGAGTTG GTGTGCACCC ACGCGGCAGG GGTGCTCGGG CACGCCGACG

29401 CGGGCGCGGT CCAGGTGGAC GCGCCGTTCA AGGAACTCGG CTTCGACTCG

29451 CTGACCGCCG TCGAACTGCG CAACCGGATC GCCGCCGCGA CCGGCCTGAA

29501 ACTGCCCGCC GCCCTCGTCT TCGACTACCC GCAGGCTCGC GTTCTCGCCG

29551 CCCACCTGGC CGAACGGCTC GTCCCGGAGG GCGCGGGGGC CATGGGCGGT

29601 GTGAGCGGTG CGGAGGGCGT GAGGGACGCG TACGGGGCAG GCGGTCCGGG

29651 CGGCGACATG ACCGCCCAGG TCTTGCTGGA GGTGGCCCGC GTCGAGCACA

29701 CCCTGTCCGC CGCCGTCCCG CACGGCCTGG ACCGGGCGGC CGTCGCGGCC

29751 CGCCTGGAGG CGCTGCTCGC CCGCTGCACG GCGACGACGG CGGCCACGGG

29801 GGCCGCGGGA GCCGCGGTGG AGGGTGACGG CGACAGCGAC GGCGACGGCG

29851 CCGTGGATCA GCTGGAGACG GCCACCGCCG AGCAAGTACT GGACTTCATC

29901 GACAACGAAC TCGGGGTGTG AGCCGCGTGC CGGCCGCACA CCAGGCGATC

29951 ACGGGCGGGG AGCTGCAGCG CACATGGTGA GCGAAGAGAA ACTGGTCGAC

30001 TACCTCAAGC GTGTCTCCGC GGACCTGCAC GCCACCCGGC AGCGGCTGCG

30051 CGAGGCGGAG GAGCGCGGCC AGGAACCCGT GGCCGTGGTG GAGGCCGCCT

30101 GCCGCTACCC CGGCGGCATC CGCACCCCCG AAGACCTGTG GGACCTGGTC

30151 GCCGCGGGCG GCAACGCCCT GGGCGCCTTC CCCGACAACC GCGGCTGGGA

30201 CCTGCGACGC CTCTTCCACC CCGACCCCGA CCACCCCGGG ACGACCTACG

30251 CCCGCGAGGG CGGCTTCCTC CACGACGCCG ACCTGTTCGA CCCGGAGTTC

30301 TTCGGCATCA GCCCCCGCGA GGCCGCGGTC CTCGACCCGC AGCAGCGACT

30351 GCTCCTGGAG TGCGCCTGGG AGGCACTGGA GCGCGCGGGC ATCGACCCGC

30401 GGTCCCTCCA GGGCAGCCGT ACCGGCGTGT ACGCGGGTGC CGCCCTGCCC

30451 GGCTTCGGCA CCCCGCACAT CGACCCCGCC GCCGAGGGCC ACCTGGTCAC

30501 CGGCAGCGCC CCGAGCGTCC TCTCGGGCCG GCTCGCCTAC ACCTTCGGCC

30551 TCGAAGGGCC CGCGGTGACG ATCGACACCG CCTGCTCGTC GTCGCTCGTC

30601 GCCGTGCACC TGGCGGCCCA CGCGCTGCGG CAGCGCGAGT GCGATCTGGC

30651 GCTCGCGGGC GGTGTCACCG TCATGACCAC CCCGTACGTG TTCACCGAGT

30701 TCTCGCGCCA GCGCGGCCTG GCCGCCGACG GCCGGTGCAA GCCCTTCGCG

30751 GCCGCCGCGG ACGGCACGGC CTTCTCCGAG GGCGCCGGAC TCCTCGTACT

30801 GGAACGCCTC TCCGACGCCC GCCGGGCCGG CCACCGGGTG CTCGCCGTCA

30851 TCCGCGGCTC GGCCGTCAAC CAGGATGGCG CGAGCAACGG CCTCACCGCC

30901 CCCAACGGCC CCGCCCAGCA GCGCGTGATC CGCGCCGCCC TCGCCGGGGC

30951 GCGGCTCTCG CCCGCGGAGG TGGACGCGGT CGAGGCGCAC GGCACCGGCA

31001 CCCGGCTGGG CGACCCCATC GAGGCCGACG CGCTCCTCGC CACCTACGGT

31051 CAGGAGCGCC ACGGGGGCCG GCCGCTGTGG CTCGGCTCGG TGAAATCCAA

31101 CATCGGCCAC ACGCAGGGCG CGGCCGGTGC CGCGGGCCTG ATCAAGATGG

31151 TCCAGGCACT GCGGCACGAG ACGCTGCCCG CCACGTTGTA CGCCGACGAG

31201 CCCACCCCGC ACGCCGACTG GGAGTCGGGC GCGGTGCGCC TGCTCAGCGC

31251 GCCGGTCGCC TGGCCGCGCG GGGAGCACGG GGAGCACACC CGCAGGGCCG

31301 GCATCTCCTC CTTCGGCATC TCCGGCACGA ACGCCCACCT CATCCTGGAG

31351 GAGGCGCCCG CGGCCGACGC CGAAGGAGCG GGTGGCGACG GCGATGGCGA

31401 CGGGGGAGGG GTGCGGCCGG TGGTGCGGGT CGGCGCCACG GGCCCCCGCG

31451 AAGAGCAGGG CCAAGGACAG GGCCAAGAGC AGCACCAACA GCAACGTCAG

31501 CAGCGGCAGC GGTCGTCGAT GATGCCGACG CCGCACCTCC CGTGGCTGCT

31551 GTCCGCCCGC AGCCCCGCCG CGCTCCGCGC CCAGGCCGAC GCGCTGGCGA

31601 ACCATGTCGC CCACGCGGAC CACTCCATCG CCGACATCGG CGGCACACTG

31651 CTGCGCCGCA CCCTGTTCGA GCACCGGGCG GTCGTCCTCG GAACCGACCG

31701 TGATGAGCGT GCCGCAGCGC TTGCCGCCCT CGCGGCAGGA CGCGCACACC

31751 CCGCGCTGAC CCGGGCCGCA GGGCCGGCGA GGAACGGCGG CACCGCCTTC

31801 CTGTTCACCG GCCAGGGAAG CCAACGCCCA GGCATGGGCA GGCAGTTGTA

31851 CGACACCTTC GACGTCTTCG CCGAGTCGCT CGACGAGACC TGCGCCCGGC

31901 TCGACCCCCT GCTCGAACAG CCGCTGAAGC CCGTCCTGTT CGCCCCCGCC

31951 GACACCGCGC AGGCCGCCGT GCTGCACGGG ACCGGCATGA CGCAGGCCGC

32001 GCTGTTCGCC CTCGAAGTCG CCCTGTACCG CCAGGTCACC TCCTTCGGGA

32051 TCGCCCCCAG CCACCTGACC GGGCACTCCG TCGGCGAGAT CGCCGCCGCC

32101 CACGTCGCCG GGGTGTTCTC CCTGGCGGAC GCCTGCACGC TGGTCGCGGC

32151 CCGGGGCCGC CTCATGCAGG CCCTGCCCGC AGGTGGCGCC ATGCTCGCCG

32201 TCCAGGCGGC CGAGGACGAC GTACTGCCGC TGCTCGCCGG GCAGGAGGAA

32251 CGTCTCTCCC TCGCCGCCGT CAACGGCCCC ACCGCCGTCG TCGTGTCCGG

32301 TGAGGCCGCT GCCGTCGGGG AGGTGGAGAA GGCGCTGCGC GGGCGCGGAC

32351 TGAAGACCAA GCGGCTCAAC GTCAGTCACG CCTTCCACTC GCCGCTCATC

32401 GAGCCGATGC TCGACGACTT CCGCGAAGTG GCCCGCGGGC TGACCTTCCA

32451 CGCGCCGACG CTGCCCGTCG TCTCCAACCT CACCGGCCGC CTCGCCGACG

32501 CGGAGCTGAT GGCCGACGCC GAGTACTGGG TGCGGCACGT ACGCCGGCCG

32551 GTGCGGTTCC ACGACGGGCT GCGCGCTCTC AGCGAGCAAG GCGTCGTGCG

32601 CTACCTGGAG TTGGGGCCCG ACCCGGTCCT CGCCACCATG GTCCAGGACG

32651 GTCTCCCGGC CCCGGCGGAG GGAGAGGAGC CCGAGCCGGT CGTCGCCGCG

32701 GCGCTGCGCT CCAAGCACGA CGAGGGACGC ACCCTGCTGG GTGCCGTCGC

32751 CGCGCTCCAC ACCGACGGAC AGCCGGCCGA CCTCACCGCC CTCTTCCCCG

32801 CCGACGCCGG GCAAGTGCCG CTCCCCACCT ACCGGTTCCA GCGGCGACGG

32851 TACTGGCGCG TCGCGCCCGA CGCCGCCGCG CCGGCCCGCG CCGCCGGCCT

32901 CCAGGAGACC GGCCACCCGC TGCTGCCCGC CGTCATCCGG CAGGCCGACG

32951 GCGGCATCCT GCTCGCGGGA CGCCTGTCCC TGCGTACGCA TCCATGGCTC

33001 GCCGACCACA CCATCGCGGG CGGCGTCCCG CTGCCCGCCA CCGCCTTCGT

33051 CGAACTCGCC CTGCTCGCAG GGCGGCACGC CGCCTGCGAC ACGATCGACG

33101 ATCTGACGCT GGAGACGCCG CTGCTGCTCG ACGACACCGG TACCGGTGTC

33151 GGGGCGGCTG TGGGCGCGGG CGCCGATGCC CTCGTCGATG CCATAGAAGT

33201 GCAGCTTGCC CTCGGCGCTC CCGACGGTTC CGGCCGCCGT GCTCTCACCG

33251 TCCACTCCCG TCCTGCCGAC GATGCGGCTG ACGACGGCGA CGCGGCCGAC

33301 GCGGCCGATG CGGCAGGCCG GGGAGGCCCG GGCGGCTCGG GTGACCTGGG

33351 CGATCCTGGC GATCCGGGCG ATCTGGGCGA CGGCGGGGGC TCCCGCGGCT

33401 GGCGCCGTCA CGCCACCGGC ATCCTCAGCG CCGGCCCGGC CGCCGAACCG

33451 GCCGCCCCCG ACGCCGCTCC CTGGCCGCCC GCCGACGCCA CCGCCCTCGA

33501 CGTCGACGCG CTGTACGCCC GGCTCGACGC GCAGGGCTAC AGCTACGGGC

33551 CCGCCTTCCG GGCCGTCCAC GCCGCCTGGC GGCACGGCGA CGACCTCTAC

33601 GCCGATGTCC GCCTCGCCGA CGAACAGCGC GCTGAAGCCG ACGCGTTCGC

33651 CCTCCACCCG GCCCTGCTCG ACGCCGCCCT GCATGCCGTC GACGAGCTGT

33701 ACCGCGGCAG TGAGGGGCGG GGGCAGGAGC AGGGGCAGGG TGGTCAGGAG

33751 CCGGAGCAGG GCCGTGGCGA CGCGGACGCC CCGGTACGGC TGCCGTTCTC

33801 CTTCAGCGAC ATACGCCACC ACGCCACCGG GGCCACACGG CTGTGGGTCC

33851 GCCGAGCCC CCAGGGCGAC GATCGGCTGC GGCTGTCCCT GACCGACGGC

33901 GAGGGCGGGC AGGTCGCGAC AGTCGACGCC CTCCAACTGC GGTTGATCCC

33951 CGCCGACCGG TGGCGCGCGG CCCGCCCCAC CACAGCCGCC CCCCTGTACC

34001 ACCTGGACTG GCACGAGCTG CCGTTGCCCG AGCCGGCCGA GACGGACCCG

34051 GCCGCCCACT CCTGGGCTGT GCTCGGAGCG CACGACGCGG GCCTCGCTCC

34101 CGCCGCGCAC TACCCGGACC TGGCGGCCCT GAAAGCCGCC GTCGAGGCCG

34151 GCGAGCCCGT GCCGGACATC GTCTTCGCAC CGTTCCCCGC GCAGGGGACG

34201 GAGACCGATG TCCCGGCTCA GGTACGAGCC CACGCCCGGC ACGCCCTGGA

34251 GCTGCTGCGC GACTGGCTCA CCACGGAAGC TTTCGCCGCC GCCCGCCTCG

34301 TCGTCCTCAC GACCGGTGCG GTCACCGCCC GCCCAGAGGA CGGGCCCGCC

34351 GACCTGGCCA CCGCACCTGT ATGGGGCCTG GTCCGAGCCG CCCAGGCCGA

34401 ACAACCCGAC CATGTCGTCC TGGTGGACAT CGACAAGGAC ATCGATAAGG

34451 ACACCGACGA GGAGACCGAC CAGGCCACCG ACGCGGGCAC CGCATCGCGC

34501 CACGCTCTGC CCGCCGCCTT GGCCGCGGCG GCCGCCCAAG CCGAGACACA

34551 GCTCGCCCTG CGCGCGGGCA CCGTGCTCGT GCCGCGCCTC GCCGTCGTCC

34601 CGCCCCGGAC CGACACCCCA GCGCTGCACG CCACCGCCCC GGAGAGCACC

34651 ACGGACACTG TGGACTCCAC GGGCATCGCG GGCGCTGCGG AATCCGGCGG

34701 CACCGTCCTG ATCACCGGCG GAACCGGCGG CCTCGGGCAG GCCGTCGCCC

34751 GTCACCTCGC CGCCGCGCAT GGCGCCCGCC ACCTGCTCCT CGTCAGCCGC

34801 AGGGGCGACG CCGCCGAGGG CGTCGCCGAG TTGCGCGCCG ACCTCGCGGA

34851 CGACGGCGTC GACGTACGCG TCGCCGCCTG CGACATCACC GACCGCGACG

34901 CGCTGGCCGG GCTCCTCGCG GACATCCCCG CCGCGCACCC GCTCACCGCG

34951 GTCGTGCACA CCGCGGGCGT CATCGACGAC AGCCTCATCA CGGCGATGAC

35001 CCCCGAGCGG CTCGACGCCG TCCTCGCACC CAAGGCCGAC GCGGCCTGGC

35051 ACCTGCACGA ACTCACCCGC GACAAGGACC TGTCGGCCTT CGTCCTCTTC

35101 TCCTCGGGCG CCTCCGTCCT CGGCAACGGC GGCCAGGCCA ACTACGCGGC

35151 CGCCAACACC TTCCTCAACA CCCTCGCCGA ACACCGCCGC GCGGCCGGCC

35201 TCGCCGCCAC CTCCGTGGCC TGGGGCCTGT GGGAGTCCGC GTCCGGCGGC

35251 ATGGCCGCCC GGCTCGGCGA CGCCGACCGC GCCCGCATCC ACCGCACCGG

35301 CGTGACGGGC CTGACCGACG AGCAGGCCCT GGCCCTCTTC GACGCGGCCC

35351 TGACCGCCGA GCACCCCACG GTCCTCGCCA CCCGCTTCGA CCGCGCCGTG

35401 CTGCGCGGCC AGGCCGCCGC CCGCACCCTG CAGCCCGCCC TGCGCGGCCT

35451 GGTACGCACT CCGCGCCCCA CCGCGTCCGC CGGGGCCATC GGGTCCACCG

35501 CAGCCACCGG GTCCGCCACG GACGAGAACG CGCCCTCCTC GTGGGCCGCC

35551 CGGCTCGCCC GGCTGTCCGC CGCCGACCGC GACCGCGCCC TCAACGAACT

35601 CATTCGCGAG CAGATCGCGA CCGTCCTGGC ACACCCCTCA CCCGACACCA

35651 TCGAACTGGG CCGCGCCTTC CAGGAGTTGG GCTTCGACTC GCTCACCGCC

35701 CTGGAACTCC GCAACCGCCT CTCCACGGCC ACCGGCATCC GGCTGCCCGC

35751 CACCCTCGTC TTCGACCACC CGAGCCCCAC CGCCCTCGTA CGCCATCTCC

35801 ACAGCCATCT CCCCGACGAG GCCCAGCACA CGTCCCCGAC CGCCCCCGGC

35851 GCCTCTGCGG AGGGCACCGC CGCCACGGCC ACCGGCATCG ACGACGACCC

35901 GATCGCCATC GTCGGCATGG CGTGCCGCTA CCCGGGCGGC GTGACCTCGC

35951 CCGAGCAGCT GTGGCAGCTC GTGGCCACCG GCACCGACGC CATCGGCCCG

36001 TTCCCCGAGG ACCGCGGCTG GGACACGGCC GGACTGTTCG ATCCCGACCC

36051 CGACCAGGTC GGCCACAGCT ACACCCGCGA AGGCGGCTTC CTCTACGACG

36101 CCGCCCGCTT CGACGCGGGC TTCTTCGGCA TCAGCCCGCG CGAGGCCGCC

36151 GCCACCGACC CGCAGCAGCG CCTGCTCCTG GAAACCGCCT GGCAGGCGTT

36201 CGAACACGCG GGCATCGACC CCGCCGCCCT GCGCGGCACC CCGTGCGGCG

36251 TCATCACCGG AATCATGTAC GACGACTACG GATCCCGCTT CCTCGCGCGC

36301 AAACCGGACG GCTTCGAGGG CCGCATCATG ACCGGCAGCA CGCCGAGCGT

36351 GGCCTCCGGC CGGGTCGCGT ACACCTTCGG CCTGGAGGGC CCCGCCATCA

36401 CGGTGGACAC CGCGTGCTCC TCCTCGCTGG TCGCGATGCA CCTGGCGGCG

36451 CAGGCGCTGC GGCAGGGCGA GTGCGAACTG GCCCTGGCCG GGGGTGTGAC

36501 CGTGATGGCC ACCCCGAACA CCTTCGTGGA GTTCTCCCGC CAGCGCGGCC

36551 TGGCCCCCGA CGGCCGCTGC AAGCCGTTCG CCGCCGCGGC GGACGGCACC

36601 GGCTGGGGCG AGGGCGCCGG ACTCGTCGTC CTGGAGCGCC TCTCCGACGC

36651 GCGCCGCAAG GGACACCGCG TCCTCGCCCT GCTGCGCGGT TCGGCCGTGA

36701 ACCAGGACGG CGCGAGCAAC GGCATGACCG CCCCGAACGG TCCCTCGCAG

36751 GAACGGGTCA TCCGCACCGC CCTGGCCGGC GCGGGCCGTG GTCCCGAGGA

36801 CATCGACGTG GTGGAGGCGC ACGGCACCGG CACCACGCTC GGCGACCCGA

36851 TCGAGGCGCA GGCCCTGCTC GCCACGTACG GGCAGGGGCG CCCGGAGGAC

36901 CGCCCGCTCT GGCTCGGCTC GGTGAAGTCG AACATCGGCC ACACGCAGGC

36951 CGCCGCCGGT GTCGCGGGCG TCATCAAGAT GGTCATGGCA CTGCGCCACG

37001 AGCAACTGCC CACGACCCTG CACGCCGACG AGCCGACCCC CCACGTGCAA

37051 TGGGACGGCG GCGGCGTACG TCTCCTGACC GAACCGGTCC CGTGGTCGCG

37101 CGGCGAGCGC ACGCGGCGCG CCGGGGTGTC GTCCTTCGGG ATCTCCGGGA

37151 CGAACGCGCA CCTGATCCTG GAGGAGCCGC CGGAGGAGGA CCTGCCCGAG

37201 CCCGTGGCGG CGGAGCCGGG TGGGGTGGTG CCGTGGGTGG TGTCCGGGCG

37251 GACGCCGGAC GCGTTGCGTG AACAGGCGCG GCGGCTCGGC GAGTTTGTCG

37301 TCGGTGCCGG GGATGTGTCG GCAGCCGAGG TGGGATGGTC ACTGGCCACG

37351 ACGCGGTCGG TGTTCGAGCA CCGGGCCGTG GTGGCGGGCC GGGACCGGGA

37401 CGATCTGGTT GCCGGGATGC AGGCGCTGGC GGCAGGGGAG ACGCCGACAG

37451 ATGTCGTGTC CGGTGCGGCG GCTTCCTCCG GTGCGGGGCC GGTGTTGGTG

37501 TTCCCGGGGC AGGGGTCGCA GTGGGTGGGC ATGGGTGCCC AGCTCCTTGA

37551 CGAGTCCCCC GTCTTCGCGG CGCGGATCGC GGAGTGTGAG CAGGCGCTGT

37601 CGGCGTACGT GGACTGGTCG CTGAGTGATG TCCTGCGCGG GGACGGGAGT

37651 GAGCTGTCCC GGGTCGAGGT CGTGCAGCCC GTGTTGTGGG CGGTAATGGT

37701 CTCGCTGGCT GCCGTCTGGG CGGATTACGG GGTCACTCCG GCCGCTGTGG

37751 TGGGGCATTC GCAGGGTGAG ATGGCTGCCG CGTGTGTGGC GGGGGCGCTG

37801 TCGCTGGAGG ATGCGGCGCG GATTGTGGCG GTACGCAGTG ACGCGCTTCG

37851 TCAGCTGCAA GGGCACGGCG ACATGGCCTC ACTCGGCACT GGTGCCGAGC

37901 AGGCCGCTGA GCTGATCGGT GATCGGCCGG GAGTGGTCGT CGCGGCAGTC

37951 AACGGGCCGT CGTCTACCGT GATTTCGGGG CCGCCGGAGC ATGTGGCCGC

38001 TGTGGTCGCG GAGGCGGAGG CACGTGGTCT GCGCGCCCGT GTGATCGACG

38051 TCGGGTATGC CTCGCACGGC CCCCAGATCG ACCAGCTCCA CGACCTCCTC

38101 ACCGAGGGCC TGGCTGACAT CCGGCCCGCG AACACGGACG TGGCCTTCTA

38151 TTCGACGGTC ACCGCCGAGC GCCTGACGGA CACCACAGCC CTGGATACGG

38201 ATTACTGGGT GACCAACCTC CGCCAGCCGG TCCGGTTCGC CGACACCATC

38251 GAAGCGCTTC TCGCGGACGG CTATCGCCTG TTCATCGAGG CCAGCGCGCA

38301 CCCGGTGTTG GGCCTGGGCA TGGAGGAGAC CATCGAGCAG GCGGACATCC

38351 CTGCCACGGT CGTCCCCACC CTGCGCCGCG ACCACGGCGA CACCACCCAG

38401 CTCACCCGCG CCGCCGCCCA CGCCTTCACC GCCGGCGCCG ATGTCGACTG

38451 GCGACGCTGG TTCCCGGCCG ACCCCACCCC CCGTACCGTC GACCTCCCCA

38501 CCTACGCCTT CCAGCACCAG CACTACTGGC TGGAGGAGCC CAGTGGGCTC

38551 ACCGGAGACG CCGCCGACCT CGGCATGGTG GCCGCCGGGC ATCCGCTGCT

38601 CGGTGCCTGT GTGGAACTCG CGGAGAGCGA CTCGTACTTG TTCACCGGGC

38651 GGCTCTCGCG CAGGGCTCCG TCCTGGCTGG CCGAACACGT GGTGGCGGGG

38701 ACGGTTCTGG TGCCGGGTGC GGCGTTGGTG GAGTGGGTGC TGCGGGCCGG

38751 CGATGAGGCG GGATGCCCGA CGATTGAGGA ACTGACGCTC CAGGCGCCGT

38801 TGGTGCTGCC CGAGTCGGGC GGGTTGCAGG TTCAGGTGGT CGTGGGTGCG

38851 ACCGATGAGC AGAGCGGCCG TCGTGACGTA CACGTGTATT CGAGGTCTGA

38901 GCAGGACGCG TCGGCGGTGT GGGTGTGCCA TGCCGTCGGT GTGGTGAGCT

38951 CCGAAATGCC AGAAGCGGCA GCCGAGTTGA GTGGGCAGTG GCCTCCTGCC

39001 GGGGCCGAAG CCGTGGATGT CGAGGACTTC TACGCGCGGG CCGCGGAGGC

39051 CGGATACGCC TACGGTCCGG CGTTCCAGGG GCTGCGGGCG CTGTGGCGGC

39101 ACGGGACGGA GCTGTTCGCC GAGGTGGTGC TGCCCGAACA GGCGGGTGGG

39151 CACGACGGTT TCGGCATCCA CCCGGCGCTG CTGGACGCCG CCCTGCATCC

39201 GCTGATGCTC CTCGACCGGC CCGCGGACGG GCAGATGTGG CTGCCGTTCG

39251 CGTGGAGCGG GGTGTCGCTG AACGCGGACC GGGCGACCCA CGTCCGTGTC

39301 CGGCTCTCCC CGCGGGGGGA GGCGGCCGAG CGTGACCTGC GGGTCGTCAT

39351 CGCCGACGCG ACCGGCGCGC CCGTCCTGAC GGTCGACGCC CTGACCCTGC

39401 GCGCGGCCGA TCCCGGCCGG CTGGGTGCGG CGGCCCGTGG CGGTGTCGAC

39451 GGCCTCTACA CCGTCGACTG GACCCCGCTG CCCCTGCCCC AGCCCCTTCC

39501 GCTGCCGCGG ACGGATGCAG GGGGGAGTGC CGACTGGGTC ATACTCTCGG

39551 ACAACTCCAG TGCAGCTCTG GCTGATGCCG TGTCGTCCGC GACGGCGGCA

39601 GGTGGCGGAG CGCCGTGGGC ATTGCTCGCT CCCGTGGGTG GCGGCTCTGC

39651 CGATGACGGG CTGCCGGTGG TGCGGCGGAC CCTCTCCCTC GTACAGGAGT

39701 TCCTGGCCGC CCCGGAGCTG ACCGAGTCCC GTCTCGTCAT CGTGACACGC

39751 GGTGCCGTGG CCACCGACGC CGATGGTGAC GTCGCGGCGT CCGCGGCAGC

39801 GGTATGGGGC CTGATCCGCA GCGCCCAGTC GGAGAACCCG GGCCGCTTCG

39851 TCCTGCTCGA CGTCGAGGAG GAGCACCTCC ACCCGGACGG CGGGGAACTG

39901 CCGTACGCCG CCCTGCGCCA CGCCGTAGAG GAGCTCGACG AGCCTCAACT

39951 TGCCCTCCGC AGCGGCAAAT TCCTCGTACC GCGCATGACG CCCGCCGCCG

40001 CCCCCGAGGA GCTCGTCCCG CCGGTCGGTA CGTCCGGCTG GCGCCTCGGC

40051 ACCTCCGGTA CGGCCACCCT GGAGAATCTG TCGGTGATCG ACGCTCCCGA

40101 GGCGTTCGCG CCGCTGGAGC CCGGGCAGGT GCGGATCTCC GTACGGGCGG

40151 CGGGCATGAA CTTCCGTGAC GTGCTGATCG CGTTGGGCAT GTATCCCGAC

40201 AAGGGCACGT TCGCGGGAAG CGAGGGCGCC GGACATGTGA CGGAGGTGGG

40251 ACCGGGCGTC ACTCATCTGT CGGTCGGTGA CCGGGTGATG GGTCTGTTCG

40301 AGGGCGCGTT CGCTCCGCTG GCCGTCGCGG ACGCCCGGAT GGTCGTCCCG

40351 ATTCCGGAGG GCTGGAGCTT CCAGGAGGCC GCGGCGGTGC CCGTGGTGTT

40401 CCTCACGGCC TGGTACGGCC TCGTGGACCT CGGCCGCCTC CGGGCGGGCG

40451 AATCGCTGCT CATCCACGCG GGCACCGGCG GAGTGGGCAT GGCCGCCACC

40501 CAGATCGCCC GCCACCTGGG CGCCGAGGTG TTCGCCACCG CGAGCCCCGC

40551 CAAGCACGGC GTGCTCGACG GCATGGGCAT CGACGCGGCC CACCGCGCCT

40601 CCTCCCGTGA CCTCGACTTC GAGGAGACCT TGCGGGCGGC GACGGGCGGG

40651 CGCGGCATGG ACGTCGTACT CAACAGTCTG GCCGGGGAGT TCACCGACGC

40701 CTCGCTGCGG CTGCTCGCCG AGGGCGGGCG CATGGTGGAC ATGGGCAAGA

40751 CCGACAAGCG CGACCCCGAC CGGGTCGCGG CCGAGCACGC GGGCGCGTGG

40801 TACCGGGCCT TCGACCTCGT GCCGCACGCG GGGCCCGACC GGATCGGGGA

40851 AATGCTGGCG GAGCTGGGCG AGTTGTTCGC CTCCGGCGCC CTGGCGCCGC

40901 TGCCCGTCCA GACCTGGCCG CTGGGCCGGG CGCGTGAGGC GTTCCGGTTC

40951 ATGAGCCAGG CGAAGCACAC CGGCAAGCTG GTGCTGGAGA TCCCGCCCGC

41001 CCTCGATCCG GACGGCACGG TGCTCATCAC CGGCGGCACC GGGGTCCTCG

41051 CCGCCGCGGT GGCCGAGCAT CTGGTGAGGG AGTGGGGCGT ACGACACCTG

41101 CTGCTGGCCG GGAGGCGCGG TTCCGAGGCG CCCGGGAGCA GTGAACTCGC

41151 CGAGGAACTG ACCGAGTTGG GGGCCGAGGT GACCTTTGCC GCGGCCGATG

41201 TCAGTGATCC GGACGCCGTG GCGGAGCTCG TCGGCAAGAC CGATCCGGCG

41251 CACCCGCTGA CCGGTGTGAT CCACGCGGCC GGTGTGCTGG ACGACGCCGT

41301 GGTCACCGCA CAGACCCCGG AGAGCCTCGC GCGGGTGTGG GCGGCGAAGG

41351 CGACGGCCGC ACACCTGCTG CACGAGGCGA CCCGGGAGGC GCGCCTCGGT

41401 CTCTTCCTGG TGTTCTCCTC GGCGGCGGCG ACACTCGGCA GTCCGGGACA

41451 GGCCAACTAC GCGGCGGCCA ACGCCTATTG CGACGCCCTC GTCCGGCAAC

41501 GGCGTGCCGA GGGCCTGGCC GGTCTCTCGA TCGGCTGGGG TCTGTGGCAG

41551 ACGGCGAGCG GCATGACCGG ACACCTCGGC GAGACGGACC TGGCACGCAT

41601 GAAGCGCACC GGGTTCACCC CGCTGACCAC CGAAGGTGGC TTGGCCCTCC

41651 TCGACGCCGC CCGCGCCCAC GGCCGCCCGC ACGTGGTCGC GGTGGACCTC

41701 GACGCGCGCG CCGTCGCCGC GCAGCCCGCC CCGTCCCGGC CCGCGCTCCT

41751 GCGCGCCCTG GCCGCGGGTG CGACCCCGGG GGCCCGCACC GCCCGGCGCA

41801 CCGCGGCCGC GGGCAGCGTC GCCCCGGCGG GCGGTCTCGC CGACCGGCTC

41851 GCCGGCCTGC CGCATCCCGA ACGGCGCCGG CTGCTGCTCG ACCTCGTACG

41901 TGGCAACGTC GCCGGCGTCC TCGGGCACAG CGACCACGAC GCCGTCCGCC

41951 CGGACACGTC GTTCAAGGAG CTCGGCTTCG ACTCCCTGAC CGCCGTGGAA

42001 CTGCGCAACC GGCTGGCCGC CGCCACCGGC CTGAAGCTGC CCGCGGCGCT

42051 CGTCTTCGAC TACCCCGAGT CGGCCACCCT CGTCGACCAC CTCCTGGAGC

42101 GTCTGTCGCC CGACGGCGCG CCGCCGCCCG TCAAGGACGC CGCGGACCCC

42151 GTTCTCAACG ACCTCGGCAG GATCGAGTCC TCCCTGGACG CGCTCGCCCT

42201 CGACGCGGAC GCGCGCAGCC GGGTCACCAG GCGTCTGAAC ACCCTGCTGT

42251 CGAAGCTGAA CGGAGCCGCC ACCGCCGGCT CCCCGGCGGA CGTCACGGAC

42301 CTGGACGCGC TGGACGCGCT GGACGACGTG TCCGACGACG AGATGTTCGA

42351 GTTCATCGAC CGAGAGCTGT GACCCCCCTG CCCGCCCCGT CCCCCTTCCC

42401 CGCCCCCACG TTCCCCGTGC CCTTCGCTGA TGGAGAAGTG ACGTTCGATG

42451 TCGAGTGCTG AAGAGTCGAG TCCTGATGTG TCCGGCACGG GTGTGTCCGG

42501 TACGGGAGAG TCCGCTACGG GTACGTCGAG TACGGAAGCC AAGCTTCGGC

42551 AGTATCTGAA GCGGGTCACG GTGGACCTCG GCCAGGCCCG CCGGCGGCTG

42601 CGCGAGGTGG AGGAGCGGGC CCAGGAGCCG ATCGCCATCG TCTCCATGGC

42651 GTGCCGCTTC CCCGGCGACA CCCGCACGCC CGAGGCCCTG TGGGACCTGG

42701 TCGCCGAGGG CGGCGACGCC ATCGACGACT TCCCCACCAA TCGCGGCTGG

42751 GACCTGGAGA GCCTCTACCA CCCCGACCCC GACCACCCCG GCACCAGCTA

42801 CGTCCGACGC GGCGGGTTCC TGTACGACGC CCCCGCCTTC GACGCGTCGT

42851 TCTTCGGGAT CAGCCCGCGC GAAGCCCTGG CCATGGACCC GCAGCAGCGG

42901 GTGCTCATGG AGACGGCCTG GCAGCTCCTG GAGCGGGCCG GCATCGACCC

42951 GGCCTCGCTG AAGCTGAGCG CCACCGGCGT CTACATCGGC GCGGGCGTGC

43001 TCGGGTTCGG CGGCGCGCAG CCCGACAAGA CGGTAGAGGG CCACCTCCTG

43051 ACCGGCAGCG CGCTGAGTGT CCTGTCCGGC CGCATCTCCT TCACGCTCGG

43101 CCTCGAGGGC CCGTCGGTCA GTGTCGACAC GGCGTGCTCC TCCTCGCTGG

43151 TCTCCATGCA CCTGGCGGCC CAGGCGCTGC GGCAGGGGGA GTGCGATCTC

43201 GCGCTGGCCG GCGGTGTCAC CGTGATGTCG ACGCCCGGCG CGTTCACCGA

43251 GTTCTCCCGC CAGGGCGCGC TGTCTCCGGA CGGCCGCTCG AAGGCTTTCG

43301 CGGCCTCGGC CGACGGCACC GGTTTCTCGG AGGGCGCGGG ACTGCTCCTC

43351 CTGGAGCGGC TCTCCGACGC GCGCCGCAAC GGCCACAAGG TGCTCGCGGT

43401 GATCCGCGGC TCGGCCGTCA ACCAGGACGG CGCGAGCAAC GGTCTCACCG

43451 CCCCCAACGG CCCCTCCCAG GAACGCGTGA TCCGCGCCGC CCTCGCCAAC

43501 GCGGGCCTGG GCGCCGCCGA GGTCGACGCG GTCGAGGCAC ACGGCACCGG

43551 CACGAAGCTC GGCGACCCCA TCGAGGCCGG TGCGCTGCTC GCCACCTACG

43601 GCCGCGACAG GGACGAGGAC CGGCCGCTGT GGCTGGGCTC GGTCAAGTCG

43651 AACATCGGTC ACCCGCAGGG CGCAGCAGGC GTCGCGGGCG TCATCAAGAT

43701 GGTGATGGCG CTGCAGCGCG AACTGCTCCC CGCCACCCTG TACGTCGACG

43751 AGCCCACCCC GCACGTCGAC TGGTCCTCGG GCTCCGTCAG GCTCCTCACC

43801 GAACCGGTCC CGTGGACCCG CGGCGAGCGC CCGCGCCGCG CGGGCGTGTC

43851 CGCCTTCGGC ATGTCCGGGA CGAACGCCCA CGTGATCCTG GAGGAGGCAC

43901 CGCCCGAGGA GGCAGCGGCC GCGGAGACAC CGGCGGAAGG GACAGGCGCA

43951 GTCGTCCCGT GGGTCGTCTC CGGCCGGGGC GAGGAAGCGC TGCGGGCCCA

44001 GGCCGCACAG CTCGCCGAGC ACGTGCGCGA CGACGACCAG CGGCCGGCGT

44051 CACCGCTGGA GGTGGGGTGG TCGCTCGCCA CGACACGGTC GGTGTTCGAG

44101 AACCGGGCCG TCGTCGTCGG GGACGACCGC GACGCGCTCC TCGACGGCCT

44151 CCGGTCGCTG GCGGCAGGTG AGGCGTCGCC GGACGTGGTG TCCGGGGCGG

44201 TCGGCCCCAC GGGGCCCGGG CCGGTCATGG TGTTCCCCGG CCAGGGCGGC

44251 CAGTGGGTGG GCATGGGGGC CCGGCTCCTC GACGAGTCCC CGGTGTTCGC

44301 GGCCCGGATC GCCGAGTGCG AGCAGGCCCT GTCGGCGTAC GTGGACTGGT

44351 CCCTGACCGA CGTGCTGCGC GGGGACGGGT CGGAGCTGGC CCGGATCGAC

44401 GTCGTCCAGC CCGTGCTGTG GGCCGTCATG GTCGCGCTCG CCGCCGTCTG

44451 GGCGGACCAG GGAATCGAAC CCGCCGCCGT CGTCGGCCAC TCGCAGGGCG

44501 AGATAGCCGC GGCGTGCGTC GTGGGCGCCA TCTCCCTGGA CGAGGCGGCC

44551 CGCATCGTCG CCGTACGCAG TGTGCTGCTG CGGCAGCTGT CCGGACGCGG

44601 CGGCATGGCG TCCCTGGGGA TGGGCCAGGA GCAGGCCGCC GACCTGATCG

44651 ACGGACACCC GGGTGTGGTC GTCGCGGCCG TCAACGGGCC GTCGTCCACC

44701 GTCATCTCGG GCCCGCCCGA GGGCATCGCC GCCGTCGTCG CCGACGCCCA

44751 GGAGCGGGGC CTTCGCGCCA GGGCCGTCGC CTCCGACGTC GCGGGCCACG

44801 GCCCGCAGCT GGACGCGATC CTGGACCAGC TCACGGAGGG CCTGGCCGGC

44851 ATCCGGCCCG CCGCGACCGA CGTCGCGTTC TACTCCACCG TCACCGCCGG

44901 GCACCTCACC GACACCACCG AACTCGACAC CGCGTACTGG GTGCGGAACG

44951 TGCGCCGGAC GGTGCGTTTC GCCGACACGA TCGACGCGCT GCTCGCGGAC

45001 GGGTACCGCC TGTTCATCGA GGTGAGCCCC CACCCCGTCC TCAACCTCGC

45051 GCTGGAAGGC CTCATCGAAC GGGCGGCCGT GCCCGCCACG GTCGTGCCCA

45101 CCCTGCGCCG CGACCACGGC GACACCAGCC AGCTCGCCCG CGCCGCGGCC

45151 CACGCCTTCG CCGCCGGCGC GGACGTCGAC TGGCGGCGCT GGTTCCCGGC

45201 CGACCCCGCC CCCCGTACCG TCGACCTGCC CACCTACGCC TTCCAGCGCC

45251 AGGACTTCTG GCCGGCCCCC GCCGGCGGGC GGTCCGGCGA CCCTGCCGGG

45301 CTCGGCCTCG CCGCCTCCGG ACACCCGCTC CTGGGCGCCT CCGTGGGCCT

45351 CGCGAGCGGG GACGTACACC TGCTGAGCGG GCGGGTGTCC CGGCAGTCCG

45401 CCGCGTGGCT GGACGACCAC GTCGTGGCGG GCCAGGCCCT GGTGCCCGGC

45451 GCGGCGCAGG TGGAGTGGGT GCTGCGGGCC GGCGACGACG CGGGCTGCTC

45501 CGCCCTGGAG GAGCTGACGC TCCAGACGCC GCTCGTGCTG CCCGACACCG

45551 GCGGCCTGCG GATCCAGGTC GTCGTCGAAG CGGCCGACGC ACACGGCCGG

45601 CGCGACGTCC GGCTGTTCTC CCGCCCCGAT GACGACGACG CCTTCGCGTC

45651 GACGCACCCC TGGACCTGCC ACGCCACGGG CGTGCTCGCC CCCGCCCCGA

45701 CGGACGGCAC CAACGGAACG CGGGACGCCG CCGACACCCT GGACGGCGCA

45751 TGGCCCCCGG CCGACGCCGA ACCCGTCCCC GCCGACGACC TCTACGCGCA

45801 GGCCGACCGC ACCGGATACG GCTACGGCCC CGCCTTCCGG GGCGTACGGG

45851 CGCTGTGGCG CCACGGCAAG GACGTCCTGG CCGAGGTGAC GCTGCCCAAG

45901 GAGGCCGGCG ACCCGGACGG CTTCGGTATC CACCCGGCCC TCCTCGACGC

45951 CGTCCTGCAA CCCGCCGCAC TGCTGCTGCC CCCGACCGAC GCCGAACAGG

46001 TCTGGCTGCC GTTCGCCTGG AACGACGTGG CGCTGCACGC CGTACGGGCC

46051 ACCACGGTCC GGGTGCGCCT CACCCCGCTC GGCGAGCGGA TCGACCAGGG

46101 GCTGCGCATC ACCGTGGCCG ACGCCGTGGG CGCGCCCGTG CTCACCGTCC

46151 GCGACCTGCG CTCGCGCCCG ACCGACACAG GCCGCCTCGC CGCGGCCGCG

46201 ACCCGCGACC GGCACGGGCT GTTCGACCTG GAGTGGATCG CGCCGGAGAA

46251 CGCGGCGGAG AACGCGGCGG GTCCGGCCCG GGACGCGTCC GAAGGGTGGG

46301 TGACACTCGG CGAGGACGCC GCGAGCCTCG CGGACCTGCT GGCGTCCGTC

46351 GAGGCGGGCG CTCCGGCGCC GCAGCTCGTG GCCGCCCCCG TCGAACCCGA

46401 CCGGACCGAC GACGGCCTGG CACTCGCCAC CCACGTCCTC GACCTCGTAC

46451 AGACCTGGCT CGCCTCGCCC CTGCACGACT CCCGCCTGGT CCTGGTGACG

46501 CGAGGGGCAG TGACGGATGC GGATGTGGAT GTGGCTGCCG CGGCCGTTTG

46551 GGGTCTGGTA CGCAGCGCCC AGTCGGAGCA CCCCGGCCGC TTCACGCTGA

46601 TCGACCTCGG CCCCGACGAC ACGCTTGCCG CAGCCATGCA GGCGGCGCAC

46651 CTGGAAGAGC CGCAACTGGC GGTGCACGGC GGCGAGATAC GAGTGCCGCG

46701 ACTGGTCCGC GCCACGACCG ACCCGACCGC CCCGAACGGG ACACCGGAGG

46751 CCGACCGGAC GGCGGACCCG TCCGAAGGAC TCCACCGGAA CGGTACGGTT

46801 CTCATCACCG GCGGCACCGG CGTACTCGGC CGACTGGTGG CCGAACACCT

46851 GGTCACGGAG TGGGGCGTAC GCCACCTGCT GCTCGCGAGC CGACGCGGCG

46901 ACCAGGCGCC GGGTAGCGCC GAACTCCGCG CCCGCCTGAG CGAATTGGGA

46951 GCATCGGTCG AGATCGCCCC GGCCGATGTC GGCGACGCGG AAGCGGTCGC

47001 CGCACTGATC GCGTCGGTCG ACCCGGCGCA CCCGCTCACC GGTGTGATCC

47051 ACGCGGCCGG TGTCCTGGAC GACGCCGTGA TCACCGCCCA GACCCCCGAG

47101 AGCCTCGCGC GGGTGTGGGC GACGAAGGCG ACGGCGGCCC GCCATCTGCA

47151 CGAGGCGACA CGGGAGACAC CCCTCGACTT CTTCGTGGTG TTCTCCTCGG

47201 CGGCCGCCTC GCTCGGCAGC CCCGGCCAGG CCAACTACGC GGCGGCCAAC

47251 GCCTATTGCG ACGCCCTCGT CCAGCACCGC CGCGCCCAAG GGCTCGCGGG

47301 CCTCTCGATC GCCTGGGGCC TGTGGCAGGC GACCAGCGGC ATGACCGGGC

47351 AGCTGAGCGA GACCGACCTG GCGCGCATGA AGCGCACCGG GTTCGCCGCG

47401 CTGACCGACG AGGGCGGCCT GGCCCTGCTC GACGCCGCCC GTGCCCACGA

47451 CCGGGCCTAC GTGGTCGCGG CCGACCTCGA CCCGCGCGCC GTGACCGATG

47501 GCCTGTCCCC GCTCCTGCGC GCCCTCACGG CGCCCGCCAC GCGGCGGCGC

47551 GTGGCCTCCG AAGGCCTCGC CGACGGGGCG CTCGCGACCC GCCTGGCCGG

47601 CCTCGACGCG GACGGCCGCC TAAGGCTCCT CACCGATGTC GTACGCGAGT

47651 ACGTCGCGGC CGTCCTCGGC CATGGTTCCG CCGCCCGGGT GGGCGTCGAC

47701 ATCGCCTTCA AGGACCTGGG TTTCGACTCG CTGACCGCGG TGGAGCTGCG

47751 CAACCGGCTG TCGGCCGCCT GTGACGTGCG GCTGCCCGCC ACACTGATCT

47801 TCGACCACCC CACCCCGCAG GCTCTCGCCA CCCACCTGGT GGACCGCTTG

47851 GCGGGCAGCA CCTCCGCGAC CACGACGGTG AATGCGACGG CGCCGGCAGC

47901 CGCCCACGTC GCCGCAGGGG CCGACGTCGA CGCAGACACC GACGACCCGG

47951 TCGCCATCGT CGCCATGACG TGCCGGTTCC CGGGCGGCGT CGCGTCCCCG

48001 GACGACCTGT GGGACCTGCT CGACGCACGC AAGGACGCGA TGGGCGCCTT

48051 CCCCACCGAC CGCGGCTGGG ACCTGGAACG CCTCTTCCAC CCCGACCCGG

48101 ACCACCCCGG CACCAGCTAC ACCGACCAGG GCGGATTTCT TCCCGACGCG

48151 GGTGATTTCG ATGCGGCGTT CTTCGGGATC AATCCGCGGG AGGCGCTGGC

48201 GATGGATCCG CAGCAGCGGT TGTTGCTGGA GGCGTCGTGG GAGGTGTTGG

48251 AGCGTGCGGG TATCGATCCG ACGACGCTCA AGGGCACCCC GACCGGCACC

48301 TACGTGGGCC TCATGTACCA CGACTACGCC AAGTCCTTCC CCACGGCCGA

48351 CGCCCAGTTG GAGGGCTACT CCTACTTGGC GAGCACCGGC AGCATGGTCT

48401 CCGGCCGCGT CGCCTACACC CTGGGCCTTG AAGGTCCGGC GGTGACGGTC

48451 GACACCGCGT GCTCCTCCTC CCTGGTCTCC ATCCACCTGG CGACGCAGGC

48501 ACTCCGGCAC GGCGAGTGCG ACCTCGCCCT GGCAGGCGGT GTGACCGTCA

48551 TGGCCGACCC GGACATGTTC GCGGGCTTCT CGCGCCAGCG CGGCCTCTCA

48601 CCTGACGGCC GCTGCAAGGC CTACGCCGCC GCGGCCGACG GAGTCGGATT

48651 CTCCGAGGGA GTGGGCGTAT TGCTCCTTGA GCGGTTGTCG GATGCGCGGC

48701 GTCATGGGCG TCGGGTGTTG GGTGTGGTGC GGGGTTCGGC GGTGAATCAG

48751 GACGGTGCGA GTAATGGGTT GACGGCGCCG AATGGTCCGT CGCAGGAGCG

48801 GGTGATTCGT CAGGCGTTGG CCAGTGGTGG GTTGTCGTCG GTGGATGTTG

48851 ATGTGGTGGA GGGGCATGGG ACGGGGACCA CGTTGGGTGA TCCGATCGAG

48901 GCGCAGGCTC TGCTGGCCAC ATATGGGCAG GGGCGTCCGG AGGACCGTCC

48951 GTTGTGGTTG GGGTCGGTGA AGTCGAACAT TGGTCATACG CAGGCGGCTG

49001 CGGGTGTTGC GGGTGTCATC AAGATGGTGA TGGCGATGCG GCATGGTGTG

49051 GTGCCGGCGA GTTTGCATGT GGATGTGCCG TCGCCGCATG TGGAGTGGGA

49101 TTCGGGTGCG GTGCGGTTGG CGGTTGAGTC GGTGCCATGG CCGCAGGTGG

49151 AGGGTCGTCC GCGTCGGGCG GGTGTGTCGT CGTTCGGCGC TTCGGGGACG

49201 AATGCGCACG TGATCGTGGA GTCTGTTCCC GATGGGCTGG AGGAGGACTC

49251 GGTATCGGTC GGCGGTGAGG CTCTTGAGAC GGAGACTGAC GGGCGCTTGG

49301 TGCCGTGGGT GGTGTCGGCC CGCAGCCCGC AGGCCCTGCG CGACCAGGCA

49351 CTACGCCTGC GTGACTTTGC CAGTGACGCG TCGTTCCGCG CGCCGCTCGC

49401 CGACGTGGGC TGGTCGCTGC TGAAGACGCG TGCGCTGCAT GAGCATCGCG

49451 CCGTTGTGGT GGGCGCGGAG CGGGCAGAGC TGATCGCCGC TCTGGAGGCG

49501 CTGGCGACGG GTGAGCCGCA TGCGGCGCTG GTCGGCCCGG CTTGCTCGCA

49551 GGCTCGGGTG GGTGGCGATG ACGTGGTGTG GCTGTTCAGT GGTCAGGGCA

49601 GTCAGTTGGT CGGTATGGGT GCTGGTTTGT ATGAGCGGTT CCCGGTGTTT

49651 GCGGCTGCGT TTGATGAGGT GTGCGGCCTG TTGGAGGGGC CGTTGGGCGT

49701 GGAGGCGGGT GGGTTGCGGG AGGTGGTGTT CCGTGGCCCG CGGGAGCGGT

49751 TGGATCACAC GGTGTGGGCG CAGGCGGGGT TGTTTGCGCT GCAGGTGGGG

49801 TTGGCCCGGT TGTGGGAGTC GGTCGGGGTG CGGCCGGATG TGGTGCTCGG

49851 GCATTCGATC GGTGAGATCG CGGCCGCGCA TGTGGCGGGG GTTTTTGATC

49901 TGGCGGATGC GTGTCGGGTG GTGGGTGCGC GGGCGCGTTT GATGGGTGGG

49951 CTGCCTGAGG GTGGGGCGAT GTGCGCGGTG CAGGCCACGC CCGCCGAGCT

50001 GGCCGCCGAC GTGGACGGAT CGGCTGTAAG TGTGGCGGCA GTCAACACCC

50051 CCGACTCCAC GGTGATTTCG GGCCCGTCGG ACGAGGTGGA CCGGATTGCT

50101 GGGGTGTGGC GGGAGCGTGG GCGCAAGACG AAGGCGCTGA GCGTCAGTCA

50151 TGCCTTCCAT TCGGCGTTGA TGGAGCCGAT GCTCGCGGAG TTCACCGAAG

50201 CGATACGAGG GGTCAAGTTC AGGCAGCCGT CGATCCCGCT CATGAGCAAT

50251 GTCTCCGGAG AGCGGGCCGG CGAGGAGATC ACGGATCCGG AGTACTGGGC

50301 GAGGCATGTA CGTAATGCGG TGCTCTTCCA GCCCGCCATC GCCCAAGTAG

50351 CGGATTCAGC GGGCGTGTTT GTGGAGCTCG GCCCCGCGCC TGTGCTGACC

50401 ACGGCCGCCC AGCACACCCT GGACGAGTCG GACAGCCAGG AGTCGGTGCT

50451 GGTCGCGTCT CTCGCCGGTG AGCGTCCTGA GGAGTCGGCG TTTGTGGAGG

50501 CGATGGCTCG TCTGCATACC GCTGGTGTTG CTGTGGACTG GTCGGTGTTG

50551 TTCGCGGGTG ATCGTGTGCC TGGGCTGGTG GAGTTGCCGA CGTATGCGTT

50601 CCAGCGGGAG CGGTTCTGGT TGAGTGGCCG TTCTGGGGGT GGGGATGCGG

50651 CGACTTTGGG GTTGGTGGCG GCGGGGCATC CGTTGTTGGG TGCGGCGGTG

50701 GAGTTCGCGG ACCGGGGTGG GTGTCTGCTG ACCGGTCGTC TGTCGCGGTC

50751 TGGGGTGTCG TGGCTTGCTG ATCATGTGGT GGCGGGTGCG GTTTTGGTGC

50801 CGGGTGCTGC GTTGGTGGAG TGGGCGTTGC GGGCCGGTGA TGAGGTCGGT

50851 TGTGTGACGG TGGAGGAGTT GATGTTGCAG GCGCCTTTGG TGGTGCCTGA

50901 GGCGTCGGGT CTGCGGGTTC AGGTGGTGGT TGAGGAGGCG GGTGAGGACG

50951 GGCGGCGCGG TGTTCAGATC TACAGCCGGC CCGACGCGGA CGCCGTGGGC

51001 GGCGATGACT CGTGGATCTG CCACGCGACC GGCGTACTGT CACCCGAAAG

51051 CGCTCGTCTG GACACGGAGT TGGGTGGCGT CTGGCCACCG GCCGGTGCCG

51101 AACCGCTGGA TGTCGACGGC TTCTACGCGC AGGCCGGTGA GGCCGGGTAC

51151 GGATACGGTC CGGCGTTCCG GGGGCTGCGT GCCGTGTGGC GGCACGGCCA

51201 GGACCTGCTG GCCGAGGTCG TCCTGCCCGA AGCCGCCGGT GCCCATGACG

51251 GCTACGGGAT CCACCCCGCC CTCCTCGACG CCACCCTCCA TCCGCTGCTC

51301 GCCGCCCGCT TCATGGACGG TTCCGAGGAC GATCAGCTCT ACGTACCGTT

51351 CGGGTGGGCC GGAGTGTCTC TGCGGGCGGT GGGAGCCACG ACTGTGCGCG

51401 TGCGCCTCCG TCCGGTCGGG GAGAGCGTCG ACCAAGGGCT GAGCGTGACG

51451 GTCACCGATG CGACCGGCGG TCCCGTTCTG AGCGTCGACT CCCTCCAGAC

51501 CCGCCCCGTG AAGCCGAGCC AATTGGCTGC GGCCCAACAG CCGGACGTAC

51551 GCGGTCTGTT CACTGTGGAG TGGACGCCGC TGCCGCAGAC GGATGCCGAC

51601 GGGGAGGCCG ACTGGGTTGT GCTCTCGGAC GGTGTTGGCC GTCTGGCTGA

51651 TGTGGTGTCG GCGGCGGGTG GTGAAGCGCC GTGGGCAGTG GTCGCTCCTG

51701 TCGATGCGTC TGTGGGCGAC GGCCGTGAGG GTCTTGACGG TCGGCTGGTC

51751 GTGGAGCGGG TGCTGTCACT CGTACAGGAG TTCCTGGCCC TGCCGGAGCT

51801 GGCCGAGTCC CGTCTCCTCG TGGTGACGCG CGGTGCGGTG GCCACCGGCG

51851 TCGACGGTGA CGGTGACGTG GACGCGTCCG CCGCAGCTGT ATGGGGCCTG

51901 GTCCGCAGTG CTCAGTCCGA GAATCCGGGC CGCTTCATCC TGCTCGACGT

51951 GGACGGCGAC GGCGACGACC AGGGCCCGGA CCTGAACGGC CGGCATCTGC

52001 CCCACGCCAC CCTGCGTCAC GCCGCCGAGG AACTCGACGA GCCCCAACTC

52051 GCCCTGCGGG AAGGGACGCT CTACGTCCCC CGACTGACCC AGGCGCGCCA

52101 GTCCGCCGAA CTCGTCGTGC CGCCCGGTGA ACCGGCGTGG CGCCTGCGGA

52151 TGGTGCACGA CGGCTCGCTG GACGCCCTGG CGGCAGTGGC CTGCCCGGAG

52201 GCCCTGGAGC CCTTGGCGCC GGGGCAGGTG CGTATCGCCG TACACGCCGC

52251 GGGCATCAAC TTCCGTGACG TACTGGTGGC CTTGGGTATG GTCCCCGCGT

52301 ACGGGGCCAT GGGTGGCGAA GGTGCCGGTG TCGTGACGGA GGTCGGTCCC

52351 GAGGTCACCC ATGTCTCGGT GGGCGACCGC GTGATGGGCG TGTTCGAGGG

52401 CGCGTTCGGC CCTGTGGTGA TCGCCGAGGC GCGGATGGTC ACACCTGTCC

52451 CGCAGGGCTG GGACATGCGG GAGGCGGCCG GTATTCCGGC GGCCTTCCTG

52501 ACGGCTTGGT ACGGGTTGGT GGAGCTGGCC GGTCTGAAGG CGGGCGAGCG

52551 GGTGCTGGTC CATGCCGCGA CGGGTGGTGT GGGGATGGCG GCGGTGCAGA

52601 TCGCCCGGCA TGTGGGTGCC GAGGTGTTCG CCACCGCGAG TCCGGGCAAG

52651 CACGCCGTGC TGGAGGAGAT GGGCATCGAC GCCGCCCACC GCGCCTCCTC

52701 CCGGGACCTC GCCTTCGAGG GCACGTTCAG GGAAGCAACG GGCGGCCGCG

52751 GCATGGACGT CGTGCTCAAC AGCCTTGCCG GCGAGTTCAT CGACGCCTCT

52801 CTGCGGTTGC TCGGCGACGG CGGCCGGTTC CTGGAGATGG GCAAGACCGA

52851 TGTGCGGGCC GCCGAAGAGG TGGCTGCGGA GCACGCGGAC GTCTCGTACA

52901 CGGCGTACGA CCTCGTCGGT GATGCCGGAC CCGACCGCAT CAGCAACATG

52951 CTGGACAAGC TCGTCGAATT GTTCGCCTCA GAACGGCTTA AGCCGCTGCC

53001 GGTACGTTCC TGGCCGCTGG ACAAGGCGCA GGAGGCGTTC CGGTTCATGA

53051 GTCAGGCGAA GCACACCGGC AAGCTGGTGC TTGAGATCCC GCCTGCCCTC

53101 GACCCCGAGG GCACGGTTCT GGTCACCGGG GGCACCGGTG CGCTGGGGCA

53151 GGTCGTGGCC GAGCATCTGG TCCGGGAGTG GGGCGTACGG CACCTGCTGC

53201 TGGCCAGCCG TCGCGGTCCG GAGGCGCCGG GCAGCGACGA ACTGGCCTCG

53251 AAGCTCACCG GGTTGGGTGC CGAGGTCACC ATTGTCGCGG CCGATGTCAG

53301 CGACCCGGCC TCGGTGGTGG AGCTGGTCGG CAAGACGGAT CCCTCGCATC

53351 CGTTGACGGG TGTCGTGCAC GCGGCGGGCG TGTTGGAGGA CGGTGTCGTG

53401 ACCGCTCAGA CGCCTGAGGG GCTGGCGCGG GTGTGGGCGG CCAAGGCTGC

53451 TGCGGCGGCG AATCTCCATG AGGCGACCCG GGAGATGCGT CTCGGCCTGT

53501 TCGTGGTGTT CTCCTCGGCG GCCGCCACGC TCGGCAGTCC GGGCCAGGCC

53551 AACTACGCGG CCGCCAATGC CTATTGCGAC GCGCTGATGC AGCACCGACG

53601 GGCGGTGGGC CAGGTCGGCC TGTCGGTCGG CTGGGGTCTC TGGGAGGCGC

53651 CGGACGCCAA GCCGGGTGTT GCCGCCGACG CCAAGGCGAG TGCTGCCACC

53701 GTCGGCAAGG CGAGTGCTCT ATCCGACGGC ACGAACGGCA GCGCTCCCCA

53751 GGACACGACC GGCACCGCCC CCCAGGGCAT GACCGGCGGA CTCACCGACA

53801 CCGACGTAGC CCGCATGGCA CGTATCGGCG TCAAGGGCAT GAGCAACGCC

53851 CACGGTCTCG CCCTGTTCGA CGCCGCGCAC CGCCACGGCC GCCCCCACCT

53901 GGTCGGCTTC AACCTCGACC TGCGCACCCT GGCCACGCAC CCCCTGCACA

53951 CCCGGCCCGC CCTTCTGCGC GGCCTGGCCA CCCCCACCGC CGGCGGGGCG

54001 AGCAGGCCGA CCGCGACGGC GGGCGGACAG CCCGCCGACC TGGCGGGCCG

54051 GCTGGCCGCG CTGTCGCCGT CGGACCGGCA CCACACGCTG GTCCGGCTCA

54101 TCAGGGAACA GGCCGCCACC GTGCTCGGGC ACCACCCGGA CAGTCTCACC

54151 ACGGGCAGCA CCTTCAAGGA ACTCGGATTC GACTCCCTGA CCGCGGTCGA

54201 ACTGCGCAAC AGGCTGTCCG CCGCCACCGG TCTCCGGCTC CCCGCCGGCC

54251 TGGTCTTCGA CCACCCGGAC GCCGACATCC TGGCCGAACA CCTCGGCGCG

54301 CAACTCGCCC CCGACGGGGA CACCCCCGCC GGTGCGGAAG CCACCGACCC

54351 GGTCCTCCGC GACCTGGCGA AACTCGAGAA CGCCCTCTCC TCCACCCTCG

54401 TCGAGCACCT CGACGCCGAC GCGGTCACGG CCCGACTGGA AGCACTCCTG

54451 TCGAACTGGA AGGCGGCGAG CGCGGCGCCC GGCTCGGGCA GCACGAAGGA

54501 GCAGCTCCAG GTTGCCACGA CCGACCAGGT CCTCGACTTC ATCGACAAAG

54551 AACTGGGTGT GTGAAACGAC CGTGCACGGC GCGACAACCA CGCTGAAGGC

54601 TGGGTGAACT CTCATGGCGA GTGAAGAGGA ACTGGTCGAC TACCTCAAGC

54651 GGGTCGCCGC CGAACTGCAC GACACCCGGC AGCGCCTGCG CGAGGTCGAG

54701 GACCGGCGGC AGGAGCCGGT GGCCGTCGTC GGCATGGCCT GCCGTTTCCC

54751 CGGCGGCATC GAGACGCCCG AGGGACTGTG GGAGCTGGTC GCGGCCGGCG

54801 ACGACGCCAT TGAGCCCTTC CCCACCGACC GGGGCTGGGA CCTGGAAGGC

54851 ATCTACCACC CGGACCCCGA CCACCCGGGT ACCTGCTACG TCCGGGAGGG

54901 CGGGTTCCTA GCCGCCCCTG ACCGGTTCGA CTCCGACTTC TTCGGCTTCA

54951 GCCCGCGCGA GGCCCTGGCC AGCAGCCCGC AACTGCGACT GCTCCTGGAG

55001 ACGTCCTGGG AGGCCCTCGA ACGGGCGGGC ATCAACCCCG CCTCGCTCAA

55051 GGGCAGCCCC ACCGGCGTCT ACGTCGGCGC CGCGACCACC GGCAACCAGA

55101 CGCAGGGCGA CCCCGGCGGC AAGGCGACCG AGGGTTACGC GGGCACCGCG

55151 CCCAGCGTCC TCTCGGGCCG CCTCTCGTTC ACGCTCGGCC TGGAGGGCCC

55201 GGCGGTGACC GTCGAGACAG CGTGCTCCTC CTCGCTGGTG GCGATGCACC

55251 TGGCGGCCAA CGCCCTGCGC CAGGGCGAGT GCGACCTCGC CCTCGCGGGC

55301 GGCGTCACCG TCATGTCCAC CCCCGAGGTG TTCACAGGCT TCTCGCGTCA

55351 GCGGGGACTG GCCCCCGACG GCCGCTGCAA GCCGTTCGCC GCCGCGGCCG

55401 ACGGCACGGG CTGGGGCGAG GGCGCGGGCC TGATCCTCCT GGAGCGCCTC

55451 TCCGACGCCC GCAGGAAGGG CCACAAGGTC CTCGCGGTGA TCCGGGGCTC

55501 GGCGATCAAC CAGGACGGCG CGAGCAACGG CTTCACCGCG CCCAACGGCC

55551 CCTCGCAGCG CCGCGTCATC CGCCAGGCAC TCTCCAGCGC CCACCTCTCC

55601 ACGTCGGAGA TCGACGTCGT CGAGGCGCAC GGCACCGGCA CCAGGCTCGG

55651 CGACCCCATC GAGGCCGAGG CGCTCATCGC CACCTACGGC AAGGAGCGCG

55701 AGGACGACCG TCCCCTGTGG CTCGGCTCGG TCAAGTCCAA CATCGGCCAC

55751 ACGCAGGCCG CCGCGGGCGT CGCCGGAGTC ATCAAGATGG TGATGGCGCT

55801 ACAGCGCGAA CTGCTTCCCG CCACCCTGAA CGTCGACGAG CCGACCCCGC

55851 ACGTCCAGTG GGAGGGCGGC GGCGTACGCC TCCTGACCGA ACCGGTCCCG

55901 TGGTCGCGCG GCGAACGCCC GCGCCGCGCC GGAATCTCCT CCTTCGGCAT

55951 ATCGGGCACG AACGCGCACG TGGTCCTGGA GGAGGCGCCG CCGGAGGAGG

56001 ACGTGCCGGG CCCCGTGGCT GCGGAGCCGG AAGGGGTGGT GCCGTGGGTG

56051 GTCTCCGCGC GGACCGAGGA GGCGTTGAGC GAACAGGCGC GGCGCCTGGG

56101 CGAGTTCGTG GCCGACACGG ACCCGTCGAC CGCTGACGTC GGGTGGTCAC

56151 TGACCACGAG CAGGGCGATC CTTGAACACC GCGCTGTGGT GGTGGGGCGT

56201 GATCGGGATG CGCTGACGGC CGGCCTGGCG GCGTTGGCCG CGGGTGAGGA

56251 GTCGGCGGAT GTGGTGGCTG GGGTGGCCGG TGATGTGGGT CCTGGGCCGG

56301 TGTTGGTGTT TCCGGGGCAG GGGTCGCAGT GGGTGGGCAT GGGCGCCCAG

56351 CTCCTTGACG AGTCGCCCGT CTTCGCGGCG CGGATCGCGG AGTGTGAGCA

56401 GGCGCTGTCG GCGTACGTGG ACTGGTCGCT GAGTGCGGTG TTGCGCGGGG

56451 ATGGGAGTGA ACTGTCCCGG GTCGAGGTCG TGCAGCCGGT GTTGTGGGCG

56501 GTGATGGTCT CGCTGGCTGC CGTCTGGGCG GATTACGGGG TCACCCCGGC

56551 CGCTGTGATC GGGCACTCGC AGGGCGAGAT GGCCGCCGCG TGCGTGGCGG

56601 GGGCGCTGTC TTTGGAGGAT GCGGCGCGCG TCGTGGCCGT ACGCAGTGAC

56651 GCGCTTCGTC AGCTGATGGG GCAGGGCGAC ATGGCGTCGT TGGGCGCCAG

56701 CTCGGAGCAG GCGGCTGAGC TCATCGGTGA TCGGCCGGGC GTATGCATCG

56751 CAGCGGTCAA CGGGCCGTCC TCGACAGTCA TTTCAGGACC GCCGGAGCAT

56801 GTGGCAGCCG TGGTCGCGGA TGCGGAGGAA CGTGGTCTGC GCGCCCGTGT

56851 CATCGATGTC GGCTATGCCT CGCACGGTCC CCAGATCGAT CAGCTCCACG

56901 ACCTCCTCAC CGACCGGCTC GCCGACATCC GGCCCGCGAC CACGGACGTG

56951 GCCTTCTATT CGACGGTCAC CGCCGAGCGC CTGACGGACA CCACGGCCCT

57001 GGATACGGAT TACTGGGTTA CCAACCTCCG CCAGCCGGTC CGTTTCGCCG

57051 ACACCATCGA TGCGCTTCTC GCGGACGGCT ATCGCCTGTT CATCGAGGCC

57101 AGCGCGCACC CGGTGCTGGG TCTGGGCATG GAGGAGACCA TCGAGCAGGC

57151 GGACATCCCC GCCACGGTCG TCCCCACCCT GCGCCGCGAT CACGGTGACA

57201 CCACCCAGCT CACCCGTGCC GCAGCGCACG CCTTCACCGC CGGCGCCACC

57251 GTCGACTGGC GGCGCTGGTT CCCGGCCGAC CCCACCCCCC GCACGATCGA

57301 CCTGCCCACC TACGCCTTCC AGCGCCGCAG CTACTGGTTG CCGGTGGACG

57351 GTGTCGGAGA TGTGCGGTCG GCCGGGCTGC GGCGGGTGGA ACACTCGCTG

57401 TTGCCCGCGG CGCTCGGTCT CGCCGATGGT GCGCTCGTGC TGACCGGACG

57451 GCTCGCGGCG TCCGGTGGTG GTGGCGGTTG GCTCGCGGAT CACGCGGTGG

57501 CGGGCACGAC GCTCGTCCCC GGTGCCGCGC TGGTCGAGTG GGCGTTGCGG

57551 GCCGCCGACG AGGCGGGCTG CCCCTCCCTT GAGGAGCTGA CGCTCCAGGC

57601 ACCTCTGGTG CTGCCCGGCT CCGGGGGCCT CCAGGTCCAA GTGGTCGTGG

57651 GTCCGGCCGA CGGACAGGGC GGCCGGCGTG AGGTGCGCGT CTTCTCGCGT

57701 GTCGACTCGG ACGACGAGGC AGCGGGGCAG GACGAGGGGT GGTCGTGTCA

57751 CGCGACCGGT GTGCTGAGCC CCGAGCCCGG TGCGGTACCG GACGGGCTCA

57801 GCGGACAGTG GCCCCCGACG GGCGCCGAGC CGCTGGAGAT CAGTGATCTC

57851 TACGAGCAGG CGGCATCGGC GGGATACGAG TACGGGCCGT CGTTCCGGGG

57901 CCTGCGCTCC GTGTGGCGGC ACGGGCATAA CCTGCTGGCA GAGGTGGAGC

57951 TGCCCGAACA GGCAGGTGCG CACGACGACT TCGGCATCCA CCCCGTACTG

58001 CTGGACGCCG CGCTGCACCC GGCGCTGCTG CTCGACCAGA ACGCGCCCGG

58051 CGAAGAGCAA GAGCCAGCCC AGCCCGCTCT TCGCCTGCCG TTCGTGTGGA

58101 ACGGCGTCTC CCTGTGGGCC ACCGGCGCCG CGACCGTGCG GGTACGGCTG

58151 GCCCCGCACG GGGGAGGGGA GACGGACGAT AGCGCCGGGC TGCGCGTGAC

58201 GGTCGCCGAC GCCACCGGAG CACCGGTGCT GAGCGTGGAC TCCCTCGCTC

58251 TGCGCCCCGC TGACCCCGAA CTGCTGCGCA CGGCCGGTCG GGCGGGCAGC

58301 GGCACCAACG GCTTGTTCAC GGTGGAGTGG ACCGCTCTGC CCCCGGCGGA

58351 CGTGGCCGAC CACGCCGCAG GCGACGGCTG GGCGGTGCTC GGTCAGGACG

58401 TACCCGACTG GGCCGGAGCG GACATGCCCC GGCATCCCGA CATGGCCTCC

58451 CTGTCGGCCG CGCTGGACGA GGGAACGCAG GCCCCTGCGG CCGTCTTCGT

58501 GGAGACCACA GCCACATCGC ACGCCACACC GAACACCGCA GCGGACGTGA

58551 CGCTCGACGC GTCCGGCCGG GCGGTCGCCG AGCGCACCCT GCACCTGCTG

58601 CGGGACTGGC TCGCCGAACC GCGCCTCGCC GAGACCCGGC TCGTCCTCAT

58651 CACCCACCAC GCGGTGACGA CCCCGGCGGA CGACGACGTG AACGCCGCAC

58701 CCCTCGACGT CCCGGCCGCC GCCCTGTGGG GACTGATCCG CAGCGCACAG

58751 GCCGAACACC CGGACCGCTT CGTTCTGTTG GACACCGACG CGAAGGCCAA

58801 CACCGACCCC GGCCCCGACA CCAGTACTGA CCACAGCACC GCATCGGGTA

58851 CGTACCGAAC CGTCATCGCG CGGGCCCTCG CCACCGGGGA GCCACAGCTG

58901 GCCGTGCGCG CGGGAGAACT GCTGGCTCCC CGCCTCGCCC GAGCCGCCAC

58951 CCCCACACCC GAGACCCCCA CACCCGAGAC ACAGCCCGAC ACCGGATCCG

59001 GGTCCGAGGC CGGGGCCGGG TCCGGATCTG GACCCGGCGC GACACTGGAC

59051 CCCGACGGCA CCGTCCTCAT CGCGGGCGGC ACCGGCATGA TGGGTGGTCT

59101 CGTCGCCGAA CACCTGGTCC GCGCCTGGTC GGTGCGGCAC CTCCTGCTCG

59151 TCAGCCGGCA AGGGCCCGAC GCGCCGGACG CCCGCGACCT CGCCGACCGG

59201 CTGGTCGGCC TGGGCGCGAC GGTACGGATC GTCGCGGCCG ACCTGACGGA

59251 CGGGCGGGCC ACCGCGGACC TCGTCGCGTC GGTCGACCCG GCGCACCCGC

59301 TCACCGGTGT GATCCACGCG GCCGGCGTCC TGGACGACGC CGTGGTCACC

59351 GCGCAGACCT CCGACCAGCT GGCCAGGGTG TGGGCGGCCA AGGCGTCCGT

59401 CGCCGCCAAC CTGGACGCGG CCACGTCGGA GCTGCCGCTC GGCTTGTTCC

59451 TGATGTTCTC GTCCGCCGCC GGTGTCCTCG GCAACGCGGG CCAGGCCGGT

59501 TACGCGGCCG CCAACGCCTT CGTCGACGCC CTGGTCGGCC GCCGTCGCGC

59551 CACCGGCCTG CCCGGCCTGT CGATCGCCTG GGGCCTGTGG GCGCGCGGCA

59601 GCGCCATGAC CCGGCACCTG GACGACGCCG ACCTCGCGCG GCTGCGTGCC

59651 GGCGGGGTCA AGCCCCTGCT GGACGAGCAG GGCCTCGCCC TCCTCGACGC

59701 GGCGCGCGCC ACCGCCGCGC ACACCTCGCT GGTGGTCGCG GCCGGTATCG

59751 ACGTACGCGG ACTGAACAGG GACGACGTCC CCGCGATCCT CCGCGACCTG

59801 GCGGGCCGGA CCCGCCGCAG GGCGGCCGCC GACTCCACCG TCGACCAGGC

59851 CGCGCTGGAG CGGCGCCTCA CGGGCCTGGA CGAGGCCGAG CGCCGGGCTG

59901 TCGTCACCGA CGTCGTACGC GAATGCGTGG CGGCCGTGCT CGGCCACCGG

59951 TCGGCGGCCG ACGTACGCAC CGAGGCCAAC TTCAAGGACC TCGGCTTCGA

60001 CTCGCTCACT GCGGTGCAGC TGCGCAACCG CCTCTCGGCG GCGAGCGGCC

60051 TCCGCCTGCC CGCCACCCTG GCCTTCGACC ACCCCACCCC CCAGGCGCTG

60101 GCGGCGTACC TCGGCACGCG CCTGAGCGGC CGGACCGCCA CCCCCGTCGC

60151 ACCCGTGGCG CCTTCCGCGG CCGCGACGGA CGAGCCGGTG GCGATCGTCG

60201 CGATGGCCTG CAAGTACCCG GGTGGAGCGA CCTCGCCGGA AGGCCTCTGG

60251 GACCTGGTCG CGGAGGGCGT GGACGCGGTC GGCGCCTTCC CGACGGGCCG

60301 CGGCTGGGAC CTCGAACGGC TCTTCCACCC CGACCCGGAC CACCCCGGCA

60351 CGAGTTACGC CGACGAAGGG GCCTTCCTTC CTGACGCGGG CGATTTCGAT

60401 GCGGCGTTCT TCGGGATCAA TCCGCGGGAG GCGCTGGCGA TGGATCCGCA

60451 GCAGCGGCTG TTGCTGGAGG CGTCGTGGGA GGTGTTGGAG CGTGCGGGTA

60501 TCGACCCGAC GACGCTCAAG GGCACCCCGA CCGGCACGTA CGTCGGCGTG

60551 ATGTACCACG ACTACGCGGC AGGCCTCGCC CAGGACGCCC AACTGGAGGG

60601 CTACTCCATG CTCGCCGGCT CCGGCAGCGT GGTGTCCGGC CGCGTCGCCT

60651 ACACCCTGGG GCTTGAGGGT CCTGCGGTGA CGGTCGACAC CGCGTGCTCC

60701 TCGTCCCTGG TCTCCATCCA CCTGGCCGCG CAAGCACTGC GACAGGGCGA

60751 GTGCACTCTC GCCCTCGCGG GCGGCGTGAC CGTCATGGCC ACGCCCGAGG

60801 TGTTCACCGG ATTCTCGCGC CAGCGCGGCC TGGCCCCCGA CGGCCGCTGC

60851 AAGCCGTTCG CCGCCGCCGC CGACGGCACC GGCTGGGGCG AGGGTGTCGG

60901 TGTGTTGTTG CTCGAGCGGT TGTCGGATGC GCGGCGTCAT GGGCGTCGGG

60951 TGTTGGGTGT GGTGCGGGGT TCGGCGGTGA ATCAGGACGG TGCGAGTAAT

61001 GGGTTGACGG CGCCGAATGG TCCGTCGCAG GAGCGGGTGA TTCGTCAGGC

61051 GTTGGCCAGT GGTGGGTTGT CGTCGGTGGA TGTTGATGTG GTGGAGGGGC

61101 ATGGGACGGG GACCACGTTG GGTGATCCGA TCGAGGCGCA GGCTCTGCTG

61151 GCCACGTATG GGCAGGGGCG TCCGGTGGAT CGTCCGTTGT GGTTGGGGTC

61201 GGTGAAGTCG AATATTGGTC ATACGCAGGC GGCTGCGGGT GTTGCGGGTG

61251 TCATCAAGAT GGTGATGGCG ATGCGGCATG GTGTGGTGCC GGCGAGTTTG

61301 CATGTGGATG TGCCGTCGCC GCATGTGGAG TGGGATTCGG GTGCGGTGCG

61351 GTTGGCGGTT GAGTCGGTGC CATGGCCGGA GGTGGAGGGT CGTCCGCGTC

61401 GGGCGGGTGT GTCGTCGTTC GGGGCTTCGG GAACGAATGC GCACGTGATC

61451 GTGGAGTCTG TGCCCGATGG GCTGGGGGAG GACTCGGTAT CGGTCAGTGG

61501 TGAGGCTCCC GAGACTGAGA CTGACGGGCG CTTGGTGCCG TGGGTGGTAT

61551 CGGCCCGCAG CCCGCAGGCC CTGCGCGACC AGGCACTACG CCTGCGTGAT

61601 GCGGTGGCGG CCGACTCAAC GGTGTCGGTG CAGGATGTGG GCTGGTCGCT

61651 GCTGAAGACG CGTGCGCTGT TCGAGCAGCG GGCGGTGGTG GTGGGGCGTG

61701 AGAGGGCTGA ACTCCTGTCG GGGCTTGCTG TGTTGGCCGC TGGCGAGGAG

61751 CACCCGGCTG TGACGCGGTC CCGTGAGGAC GGGGTTGCTG CGAGCGGTGC

61801 TGTGGTGTGG CTGTTCAGTG GTCAGGGCAG TCAGTTGGTC GGTATGGGTG

61851 CTGGTTTGTA TGAGCGGTTC CCGGTGTTTG CGGCTGCGTT TGATGAGGTG

61901 TGCGGCCTGT TGGAGGGGCC GTTGGGCGTG GAGGCGGGTG GGTTGCGGGA

61951 GGTGGTGTTC CGTGGCCCGA GGGAGCGGTT GGATCACACG ATGTGGGCGC

62001 AGGCGGGGTT GTTTGCGCTG CAGGTGGGGT TGGCCCGGTT GTGGGAGTCG

62051 GTCGGGGTGC GGCCGGATGT GGTGCTCGGG CATTCGATCG GTGAGATCGC

62101 GGCCGCGCAT GTGGCGGGGG TCTTTGATCT GGCGGATGCC TGTCGGGTGG

62151 TGGGGGCGCG GGCCCGTTTG ATGGGTGGGC TGCCTGAGGG CGGGGCGATG

62201 TGCGCGGTGC AGGCCACGCC CGCCGAGCTG GCCGCCGACG TGGACGACTC

62251 TGGTGTGAGT GTGGCGGCGG TCAACACACC TGATTCGACG GTGATTTCAG

62301 GGCCGTCTGG TGAGGTGGAT CGGATTGCTG GGGTGTGGCG GGAGCGTGGG

62351 CGTAAGACGA AGGCGCTGAG CGTCAGTCAT GCCTTCCACT CGGCGTTGAT

62401 GGAGCCGATG CTCGCGGAGT TCACCGAAGC GATACGAGAG GTCAAGTTCA

62451 CGCGGCCGAA GGTGTCGTTG ATCAGCAACG TCTCTGGTCT GGAGGCGGGT

62501 GAGGAGATCG CGTCCCCGGA GTACTGGGCA CGCCATGTAC GCCAGACAGT

62551 GCTCTTCCAG CCCGGCATCG CCCAAGTGGC TTCCACGGCA GGCGTGTTTG

62601 TCGAGCTCGG CCCCGGCCCC GTACTGACTA CTGCCGCCCA GCACACCCTG

62651 GACGACGTAA CCGATAGGCA TGGCCCCGAA CCGGTACTGG TGTCCTCGCT

62701 GGCCGGTGAG CGTCCTGAGG AGTCGGCGTT CGTGGAGGCG ATGGCTCGTC

62751 TGCATACCGC TGGTGTTGCT GTGGACTGGT CGGTGTTGTT CGCGGGTGAT

62801 CGTGTGCCTG GGCTGGTGGA GTTGCCGACG TATGCGTTCC AGCGGGAGCG

62851 GTTCTGGTTG AGCGGCCGTT CTGGGGGTGG GGATGCGGCG ACTTTGGGTC

62901 TGGTGGCGGC GGGGCATCCG TTGTTGGGTG CGGCGGTGGA GTTCGCGGAC

62951 CGGGGTGGGT GTCTGCTGAC CGGTCGGCTG TCGCGGTCTG GGGTGTCGTG

63001 GCTTGCTGAT CATGTGGTGG CGGGTGCGGT TTTGGTGCCG GGTGCTGCGT

63051 TGGTGGAGTG GGCGTTGCGG GCCGGTGATG AGGTCGGTTG TGTGACGGTG

63101 GAGGAGTTGA TGTTGCAGGC GCCTTTGGTG GTGCCTGAGG CGTCGGGTCT

63151 GCGGGTTCAG GTGGTGGTCG AGGAGGCGGG TGAGGACGGG CGGCGCGGTG

63201 TCCAGATCTA TAGCCGGCCT GACGCGGACG CCGTGAGCGG CGACGACTCG

63251 TGGATCTGCC ACGCGACCGG CACCCTCACC CCCCAGCACA CCGACGCTCC

63301 GAACGACGGA CTGGCCGGCG CGTGGCCCGC GGCGGGCGCC GTGCCGGTGG

63351 ACCTGGCGGG CTTCTACGAG CGCGTGGCGG ACGCGGGCTA TGCGTACGGC

63401 CCGGGGTTCC AGGGGCTGCG TGCCGTGTGG CGGCACGGTC AGGACCTGCT

63451 GGCCGAGGTC GTCCTGCCCG AAGCCGCGGG TGCCCATGAC GGCTACGGCA

63501 TCCACCCCGC CCTCCTCGAC GCCACCCTCC ACCCGGCCCT GCTCCTCGAC

63551 TGGCCCGGGG AGGTGCAGGA CGACGACGGG AAGGTCTGGC TGCCTTTCAC

63601 CTGGAACCAG GTCTCCTTGC GGGCTGCGGG AGCCGCCACC GTACGCGTAC

63651 GTCTCTCGCC CGGCGAGCAC GACGAGGCGG AACGGGAAGT ACAGGTACTG

63701 GTGGCCGACG CCACCGGGAC CGACGTCCTG AGCGTGGGGT CGGTGACGTT

63751 GCGTCCCGCC GACATCCGGC AACTGCAGGC CGTGCCGGGT CACGACGACG

63801 GTCTGTTCTC GGTGGACTGG ACGCCGCTGC CGCTGTCGCG GACGGATGTG

63851 TCGCAGACGG ATGCCGACGG GGATGCCGAC TGGGTTGTGC TCTCGGACGG

63901 TGTCGGCAGC CTGGCTGATG TGGTGTCGGC GGCGGGTGGT GAAGCGCCGT

63951 GGGCAGTGGT CGCTCCCGTC GGTGCATCCG CGGGCGGCGG CCTTGCCGGC

64001 TTTGACCGCC GTGAGGGTCT TGACGGTCGG CTGGTCGTGG AGCGGGTGTT

64051 GTCACTCGTA CAGGAGTTCC TGGCCGCGCC GGAGCTGGCC GAGTCCCGGC

64101 TCCTCGTGCT GACCCGCGGC GCCGTGGCGA CCGGCGGCGA CGGCGACGGT

64151 GATGTGGACG CGTCCGCCGC AGCCGTATGG GGCCTGGTCC GCAGTGCTCA

64201 GTCCGAGAAC CCGGGCCGCT TCATCCTGCT CGACGTGGAC ATGGACGTGG

64251 ACGTCGACGT GGACATGGAC GTGGACGTCG ACGTGGACGT CGACGTGGAC

64301 GTGGACGGAG ACGGCAATGG CAGCGACCTG GACCCGGACC TGAACGGCCG

64351 ACGACTTCCC CACGCCACCC TGCGTCACGC CGCCGAGGAA CTCGACGAGC

64401 CCCAACTCGC CCTGCGCGAC GGACAACTGC TCGTTCCGCG GCTGGTCCGC

64451 GCCACCGGCG GCGGACTCGT CGTGGCGCCC ACCGACCGTG CCTGGCGCCT

64501 GGACAAGGGA AGCGCCGAGA CGCTGGAGAG CGTCGCGCCG GTCGCGTACC

64551 CCGGAGTCAT GGAACCCCTG GGCCCCGGCC AGGTCCGCCT CGGCATCCAC

64601 GCCGCGGGCA TCAACTTCCG CGACGTCCTG GTCAGCCTCG GCATGGTGCC

64651 CGGCCAGGTC GGCCTGGGCG GCGAAGGCGC CGGTGTCGTG ACGGAGACAG

64701 GCCCCGATGT CACCCACCTG TCGGTCGGCG ACCGCGTGAT GGGCGTCCTC

64751 CACGGCTCCT TCGGCCCGAC GGCCGTGGCG GACACCCGCA TGGTCGCGCC

64801 GGTTCCGCAG GGCTGGGACA TGCGGCAGGC GGCCGCGATG CCCGTCGCGT

64851 ATCTGACGGC TTGGTACGGG TTGGTGGAGC TGGCCGGTCT GAAGGCGGGC

64901 GAGCGCGTGC TGATCCACGC AGCCACGGGT GGTGTGGGAA TGGCGGCGGT

64951 GCAGATCGCC CGTCACCTGG GTGCCGAGGT GTTCGCCACC GCCAGTGCAG

65001 CCAAGCACGT CGTACTGGAA GAGATGGGCA TCGACGCCGC CCACCGCGCC

65051 TCCTCCCGGG ACCTCGCCTT CGAGGACACC TTCCGGCAGG CCACCGACGG

65101 GCGCGGCATG GACGTCGTCC TCAACAGCCT GACCGGCGAG TTCATCGACG

65151 CATCTCTGCG GTTGCTCGGC GACGGCGGCC GGTTCCTGGA GATGGGCAAG

65201 ACCGATGTGC GCACGCCGGA GGAGGTGGCC GCGGAGTACC CGGGTGTCAC

65251 CTACACCGTG TACGACCTCG TCACCGACGC GGGGCCGGAT CGCATCGCGG

65301 TCATGATGAG TGAGCTGGGC GAGAGGTTCG CTTCCGGTGC CCTTGACCCT

65351 CTGCCGGTGC GTTCCTGGCC GCTGGACAAG GCGCGTGAGG CGTTCCGGTT

65401 CATGAGTCAG GCCAAGCACA CCGGCAAACT CGTACTCGAC GTGCCCGCAC

65451 CGCTCGACCC CGACGGGACC GTCCTGATCA CCGGAGGCAC GGGGGCGCTG

65501 GGGCAGGTCG TGGCCGAGCA TCTGGTGCGG GAGTGGGGCG TACGGCACCT

65551 GCTGCTGGCC AGCCGCCGTG GACTGGACGC CCCCGGCAGC GGTGAACTCG

65601 CCGACAGGCT GTCGGACTTG GGCGCCGAGG TGACCGTCGC GGCGGCCGAT

65651 GTGAGCGACC CGGCCTCGGT GGTGGAGCTG GTCGGCAAGA CGGATCCCTC

65701 GCATCCGTTG ACGGGTGTCG TGCACGCGGC GGGCGTGCTT GAGGACGGGA

65751 TCGTGACGGC TCAGACGCCT GAGGGGCTGG CGCGGGTGTG GGCGGCCAAG

65801 GCCGCTGCGG CGGCGAATCT CCATGAGGCG ACCCGGGAGA TGCGTCTCGG

65851 TCTGTTCGTG GTGTTCTCCT CGGCGGCCGC CACGCTCGGC AGTCCGGGCC

65901 AGGCCAACTA CGCGGCTGCC AATGCCTATT GTGACGCGCT GATGCAGCGC

65951 CGACGGGCGG CGGGCCAGGT CGGCCTGTCG GTCGGCTGGG GTCTCTGGGA

66001 GGCACCGGAC GCCAAGCCGG GTGTTGCCGC CGACGCCAAA CCGGATGTTG

66051 CCGCCGACGC CAAGACGGGA GTTGCCGCCG ACGGCACTCC CCAGGGCATG

66101 ACCGGCACCC TGAGCGGCAC CGACGTGGCC CGCATGGCAC GCATCGGCGT

66151 CAAGGCGATG ACCAGCGCAC ACGGTCTCGC CCTGCTCGAC GCCGCACACC

66201 GCCACGGCCG CCCCCACCTC GTCGCCGTCG ACCTCGACAC CCGCGTCCTG

66251 GCGCACAAAC CCGCCCCGGC CCTCCCCGCC CTCCTGCGCG CCTTCGCCGG

66301 AGACCAGGGA GGCCAGGGAG GCGGCCGAGG CGGCGGTCGG GGCGGCGGCC

66351 CGGCACGACC GGCGGCCGCC ACCACCCGGC AGAACGTCGA CTGGGCCGCG

66401 AAGCTCTCCG TCCTGACAGC CGAGGAACAG CACCGCACCC TCCTCGACCT

66451 GGTACGGACG CACGCGGCAG CCGTCCTCGG GCACGCGGGC ACCGACGCCG

66501 TACGCGCCGA CGCCGCCTTC CAGGATCTCG GCTTCGACTC CCTCACCGCG

66551 GTCGAACTGC GCAACCGCCT CTCCGCCTCC ACCGGCCTGC GCCTGCCCGC

66601 CACGTTCATC TTCCGGCACC CGACCCCGTC GGCCATCGCC GACGAACTGC

66651 GCGCACAGCT GGCCCCCGCG GGGGCCGACC CGGCCGCGCC GCTCTTCGGT

66701 GAACTGGACA AGCTGGAGAC GGTGATCACG GGGCACGCGC ACGACGAGAG

66751 CACCCGGACC CGCCTGGCGG CACGCCTGCA GAACCTGCTG TGGCGCCTGG

66801 ACGACACTTC GGCCCGCTCG GACCACGCGG CCGGCGCGAG CGACGCCGAC

66851 GGCGACGCCG TCGAGAACCG AGACCTCGAG TCCGCGTCGG ACGACGAGCT

66901 CTTCGAGCTG ATCGACCGAG AACTGCCTTC TTGATCAGGA GTGGAGAAGA

66951 CATGCCGGGT ACGAACGACA TGCCGGGTAC CGAGGACAAG CTCCGCCACT

67001 ACCTGAAGCG AGTGACCGCG GATCTCGGAC AGACCCGTCA GCGCCTGCGC

67051 GACGTGGAGG AGCGCCAGCG GGAACCGATC GCCATCGTCG CGATGGCCTG

67101 CCGCTACCCG GGCGGGGTGG CCTCCCCCGA GCAGCTGTGG GACCTGGTCG

67151 CCTCACGCGG CGACGCCATC GAGGAGTTCC CCGCCGACCG CGGCTGGGAC

67201 GTGGCGGGCC TCTACCACCC CGACCCGGAC CACCCCGGCA CGACCTATGT

67251 ACGAGAGGCC GGATTCCTGC GGGACGCCGC CCGCTTCGAC GCCGACTTCT

67301 TCGGCATCAA CCCGCGCGAG GCGCTCGCCG CCGACCCGCA GCAACGGGTG

67351 CTCCTCGAAG TGTCGTGGGA ACTGTTCGAG CGGGCGGGCA TCGACCCCGC

67401 CACGCTCAAG GACACCCTCA CCGGCGTGTA CGCGGGGGTG TCCAGCCAGG

67451 ACCACATGTC CGGGAGCCGG GTCCCGCCGG AGGTCGAGGG CTACGCCACC

67501 ACGGGAACCC TCTCCAGCGT CATCTCCGGC CGCATCGCCT ACACCTTCGG

67551 CCTGGAGGGC CCGGCGGTGA CGCTCGACAC GGCGTGCTCG GCATCGCTGG

67601 TCGCGATCCA CCTCGCCTGC CAGGCCCTGC GCCAGGGCGA CTGCGGCCTG

67651 GCGGTGGCGG GAGGCGTGAC CGTACTGTCC ACGCCGACGG CGTTCGTGGA

67701 GTTCTCACGC CAGCGCGGAC TCGCACCGGA CGGCCGCTGC AAGCCGTTCG

67751 CCGAGGCCGC CGACGGCACC GGATTCTCCG AGGGCGTCGG CCTGATCCTC

67801 CTGGAACGCC TCTCCGACGC CCGCCGCAAC GGACATCAAG TACTCGGCGT

67851 CGTACGCGGA TCGGCCGTCA ACCAGGACGG CGCGAGCAAC GGCCTGACCG

67901 CCCCGAACGA CGTCGCCCAG GAACGCGTGA TCCGCCAGGC CCTGACCAAC

67951 GCCCGCGTCA CCCCGGACGC CGTCGACGCC GTGGAGGCAC ACGGCACCGG

68001 CACCACGCTC GGCGACCCGA TCGAGGGGAA CGCACTCCTC GCGACGTACG

68051 GAAAGGACCG CCCCGCCGAC CGGCCGCTGT GGCTCGGCTC TGTGAAGTCG

68101 AACATCGGCC ACACGCAGGC GGCTGCGGGC GTCGCAGGCG TCATCAAGAT

68151 GGTGATGGCG ATGCGCCACG GCGAGCTGCC CGCCTCCCTG CACATCGACC

68201 GGCCCACGCC CCACGTGGAC TGGGAGGGCG GGGGAGTGCG GTTGCTCACC

68251 GATCCCGTGC CGTGGCCACG GGCCGACCGC CCCCGCCGCG CGGGGGTCTC

68301 CTCCTTCGGC ATCAGCGGCA CCAACGCCCA CCTGATCGTG GAACAGGCCC

68351 CCGCCCCGCC CGACACGGCC GACGACGCCC CGGAAGGCGC CGCAACCCCC

68401 GGCGCTTCCG ACGGCCTCGT GGTGCCGTGG GTGGTGTCGG CCCGTAGTCC

68451 GCAGGCCCTG CGTGATCAGG CCCTGCGTCT GCGCGACTTT GCCGGTGACG

68501 CGTCCCGAGC GCCGCTCACC GACGTGGGCT GGTCTTTGCT GCGGTCGCGT

68551 GCGCTGTTCG AGCAGCGGGC GGTGGTGGCG GGGCGTGAGA GGGCTGAACT

68601 GCTGGCGGGG CTGGCTGCGT TGGCCGCTGG TGAGGAGCAC CCGGCTGTGA

68651 CGCGGTCCCG TGAGGAAGCG GCGGTTGCTG CGAGCGGTGA TGTGGTGTGG

68701 CTGTTCAGTG GTCAGGGCAG TCAGTTGGTC GGTATGGGTG CTGGTTTGTA

68751 TGAGCGGTTC CCGGTGTTTG CGGCTGCGTT TGATGAGGTG TGCGGCTTGC

68801 TGGAGGGGGA GCTGGGGGTT GGTTCGGGTG GGTTGCGGGA GGTGGTGTTC

68851 TGGGGCCCGC GGGAGCGGTT GGATCACACG GTGTGGGCGC AGGCGGGGTT

68901 GTTTGCGTTG CAGGTGGGGT TGGCCCGGTT GTGGGAGTCG GTCGGGGTGC

68951 GGCCGGATGT GGTGCTCGGG CATTCGATCG GTGAGATCGC GGCCGCGCAT

69001 GTGGCGGGGG TCTTTGATCT GGCGGATGCG TGTCGGGTGG TGGGGGCGCG

69051 GGCGCGTTTG ATGGGTGGGT TGCCTGAGGG TGGGGCGATG TGTGCGGTGC

69101 AGGCCACGCC CGCCGAGCTG GCCGCGGATG TGGATGGCTC GTCCGTGAGT

69151 GTGGCGGCGG TCAACACACC TGACTCGACG GTGATTTCAG GTCCGTCGGG

69201 TGAGGTGGAT CGGATTGCTG GGGTGTGGCG GGAGCGTGGG CGTAAGACGA

69251 AGGCGCTGAG CGTGAGTCAT GCTTTCCATT CGGCGTTGAT GGAGCCGATG

69301 CTCGGGGAGT TCACGGAAGC GATACGAGGG GTCAAGTTCA GGCAGCCGTC

69351 GATCCCGCTC ATGAGCAATG TCTCCGGAGA GCGGGCCGGC GAGGAGATCA

69401 CATCCCCGGA GTACTGGGCG AGGCATGTAC GCCAGACAGT GCTCTTCCAG

69451 CCCGGCGTCG CCCAAGTGGC CGCTGAGGCA CGCGCGTTCG TCGAACTCGG

69501 CCCCGGCCCC GTACTGACCG CCGCCGCCCA GCACACCCTC GACCACATCA

69551 CCGAGCCGGA AGGCCCCGAG CCGGTCGTCA CCGCGTCCCT CCACCCCGAC

69601 CGGCCGGACG ACGTGGCCTT CGCGCACGCC ATGGCCGACC TCCACGTCGC

69651 CGGTATCAGC GTGGACTGGT CGGCGTACTT CCCTGACGAC CCCGCCCCCC

69701 GCACCGTCGA CCTGCCCACC TACGCCTTCC AGGGGCGGCG CTTCTGGCTG

69751 GCGGACATCG CGGCGCCCGA GGCCGTGTCC TCGACGGACG GTGAGGAGGC

69801 CGGGTTCTGG GCCGCCGTCG AAGGTGCGGA CTTCCAGGCG CTCTGCGACA

69851 CCCTGCACCT CAAGGACGAC GAGCACCGCG CGGCTCTGGA GACGGTGTTC

69901 CCCGCGCTGT CCGCGTGGCG GCGCGAACGA CGTGAGCGGT CGATCGTCGA

69951 TGCCTGGCGG TACCGGGTCG ACTGGCGGCG CGTCGAGCTG CCGACACCCG

70001 TTCCGGGCGC CGGTACCGGT CCCGACGCCG ACACGGGCCT CGGGGCGTGG

70051 CTGATCGTGG CTCCCACGCA CGGGTCGGGT ACTTGGCCGC AAGCCTGTGC

70101 CCGGGCGTTG GAGGAGGCGG GCGCGCCGGT ACGTATCGTC GAGGCCGGCC

70151 CGCACGCCGA CCGGGCGGAC ATGGCGGACC TGGTCCAGGC ATGGCGGGCA

70201 AGCTGTGCGG ACGACACCAC CCAGCTCGGA GGAGTGCTCT CCCTGCTGGC

70251 TCTCGCCGAG GCACCGGCCA CCAGTTCCGA CACCACTTCC CACACCAGTA

70301 CCAGTTGCGG TACCGGCTCT CTCGCGTCCC ACGGCCTCAC CGGCACCTTG

70351 ACGCTGCTGC ACGGTCTGCT GGATGCGGGC GTCGAAGCGC CTCTCTGGTG

70401 TGCCACGCGC GGCGCCGTGT CGTGCGGCGA CGCCGATCCG CTCGTCTCCC

70451 CGTCGCAGGC CCCGGTCTGG GGACTCGGAC GCGTGGCCGC CCTGGAGCAT

70501 CCGGAGTTGT GGGGCGGCCT GGTCGACCTG CCCGCCGACC CGGAGTCGCT

70551 CGACGCGAGC GCGTTGTATG CGGTTCTGCG CGGAGACGGC GGCGAGGATC

70601 AGGTCGCGCT GCGCCGGGGC GCGGTCCTCG GCCGTCGCCT GGTGCCCGAC

70651 GCAACCCCGG ACGTGGCCCC CGGCTCGTCC CCGGACGTGT CCGGAGGCGC

70701 AGCCCATGCC GACGCGACCT CCGGGGAGTG GCAGCCGCAT GGTGCCGTCC

70751 TCGTCACCGG AGGCGTCGGC CACCTGGCCG ATCAGGTCGT ACGGTGGCTC

70801 GCCGCGTCCG GCGCCGAACA CGTCGTACTC CTGGACACGG GCCCCGCCAA

70851 CAGCCGTGGT CCCGGCCGGA ACGACGACCT CGCCGCGGAA GCCGCCGAAC

70901 ACGGCACCGA GCTGACGGTC CTGCGGTCCC TGAGCGAGCT GACAGACGTA

70951 TCCGTACGTC CCATACGGAC CGTCATCCAC ACATCGCTGC CCGGCGAGCT

71001 CGCGCCGCTG GCCGAGGTCA CCCCCGACGC GCTCGGCGCG GCCGTGTCCG

71051 CCGCCGCGCG GCTGAGCGAA CTCCCCGGCA TCGGGTCAGT GGAGACCGTG

71101 CTGTTCTTCT CCTCCGTGAC GGCTTCGCTC GGCAGTAGGG AGCACGGCGC

71151 GTACGCCGCC GCCAACGCCT ACCTCGACGC CCTGGCGCAA CGGGCCGGTG

71201 CCGATGCTGC GAGCCCCCGG ACGGTCTCGG TCGGGTGGGG CATCTGGGAT

71251 CTGCCGGACG ACGGTGACGT GGCACGCGGC GCCGCCGGGC TGTCCCGGAG

71301 GCAGGGACTC CCGCCGCTGG AACCGCAGTT GGCGCTCGGC GCCCTGCGCG

71351 CGGCGCTCGA CGGGGGCAAG GGGCACACGC TGGTCGCCGA CATCGAGTGG

71401 GAGCGGTTCG CGCCGCTGTT CACGCTGGCC AGGCCCACCC GGCTGCTCGA

71451 CGGGATCCCC GCGGCCCAGC GGGTCCTCGA CGCCTCCTCG GAGAGCGCCG

71501 AGGCCTCGGA GAACGCCTCG GCCCTCCGTC GCGAACTGAC GGCCCTGCCC

71551 GTGCGGGAGC GGACCGGGGC ACTTCTCGAC CTGGTCCGCA AACAGGTGGC

71601 CGCCGTCCTG CGCTACGAGC CGGGCCAAGA CGTGGCGCCC GAGAAGGCCT

71651 TCAAGGACCT GGGCTTCGAC TCGCTCGTGG TCGTGGAGCT GCGCAACCGG

71701 CTGCGCGCCG CCACCGGGCT CCGGCTGCCC GCCACCCTGG TCTACGACTA

71751 CCCCACACCC CGCACCCTCG CCGCACACCT GCTGGACAGG GTGCTGCCCG

71801 ACGGCGGCGC GGCAGAGCTC CCCGTGGCCG CCCACCTGGA CGACCTGGAG

71851 GCGGCCCTCA CCGACCTGCC GGCCGACGAC CCCCGGCGCA AGGGCCTGGT

71901 CCGGCGTCTA CAGACGCTGC TGTGGAAGCA GCCCGACGCC ATGGGGGCGG

71951 CGGGCCCCGC CGACGAGGAG GAGCAAGCCG CGCCCGAGGA CCTGTCGACC

72001 GCGAGCGCCG ACGACATGTT CGCCCTGATC GACCGGGAGT GGGGCACGCG

72051 GTGAGCGGGG TGGAGCGGGG TGTGGGGTCG GCGGGCCCTG TGGAACAGGG

72101 TGACGGACTC GCGGGCCTGG TCGAGCGGGC CGAGGCGCTG GCCGCTCTGC

72151 GGGGCGCCTT CGACGGCTCC CCGGGCACCG GCGGCAGCCT CGTCGTGCTC

72201 AGCGGCGCGG TGGGCACCGG CAAGACCGCG CTGCTACGGG CGTGGGCCGA

72251 CCGCATCGGC GCCGATGCCG ACGCCCTGGT CCTGACCGCC ACCGCCTGCC

72301 GCGCCGAGCG CGACCTGCCG CTTGGCGTCC TGGAACAGCT GGTACGCAGC

72351 CCCGGCCTGC CCCCGGCCAG CGCCGAGCGC GCGCTGGCGT GGTGGGACGA

72401 GGAGGCCTCG GCCACCCCCG GAAAGACGGA CGCGAACGGG ACGAGTGCCA

72451 ACGGGACGGA CGCCAACGGG ACGGGCGCGG GACAGACGGG CGCGGGGCAG

72501 GCGGGCGTGG GACAGACGGG CGTGGGCGGA GAGCCCGTCC TGGCCGCCTC

72551 CGCCCTGCGA GGCCTGTGCG AGGTGCTGCG GGACCTGCTC GCCGAGCGGC

72601 CCGTCGTGGT CGCCGTCGAC GACGCGCACC ATGCCGACGC GGCGTCGCTC

72651 CAGTGCCTGC TCTCCGTGGT GCGCCGGCTG CGGTCGGCAC GACTCCATGT

72701 GCTGTTCACC GAGTACGCCC ATCAGAAGGC GCAGAACGCC CTGCTGAGCA

72751 GCGAGTTCCT GCACGAGCCC GCCCTGCGGC GGATCCGCCT GGAACCGCTG

72801 TCGAAGGCGG GCGTGGAGGC CTTGCTCGCC CGGCACCTCG ACGAGCGGAC

72851 GGCACAAGAC CTCACCCCCG TCGTCCACGG CATGAGCGCG GGCCACCCGC

72901 TCCTCGTACG GGCGCTGGCC GAGGACCACC GTGCGGCGGG CGGCGCCGGG

72951 GAGGCGTACG GTCGTGCCGT CCTCAGCTTT CTGTACCGGC ACGAGACTCC

73001 GGTCACCCAA GTCGCCCGCG CCATCGCTGC GTTGGGCGCG CACGCCGGAC

73051 CCGGTCAGGT CGGGCGGCTG CTCGATGTCG ACGCGGCGTC CGTCGAGCGG

73101 GCCGTGCGGC AGCTGACCGT CGCGGAGGTG CTGCACGAGG GCCGCCTGTG

73151 CCACCCGGCG TTCGCGGCGG CGGTCCTGGA CGGCATGCCG CCCGAGGAAC

73201 GCCGCGCCCT GCACGGACGG GTCGCCGACC TCCTGCACGA GGAGGGGGCG

73251 CCGGCCACCG AAGTGGCCGC CCACCTCGTC GCCGCCGACC GGTCCGACGC

73301 CCCGTGGGCG GTACCCGTCT TCCAGGAAGC GGCCCAACTC GCCCTGGACG

73351 AGGACCAGGT GGAGACCGGC GTCGACTATC TGCGCGCGGC CCACCAGCGG

73401 TGCCGGGGCG CCGCGCAGCG TGCCGCGGTC GTCGGTGCGC TCGCCGACGC

73451 CGAGTGGCGG CTCGACCCAG CAAAGGTCCT GCGCCACCTG CCCGACCCTG

73501 CAGCCATGGC CCCACAAACG GACCCTGCCG CCCTGGCCCC ACACACGGAC

73551 CCCGCACCCA CAGCCGCACC CACAGCCGCC CCCACCCCCA CCCCCATCCC

73601 GACCACCCCA CCCCTCCCCA CCCACCTGCT CTGGCACGGG CGGGTCGAGG

73651 AAGGCCTGGA CGCCATCGGC ACGCTCACCG GGCCCGGACC CAACCCGGCG

73701 GGTGCGCCGC CGATGAACCC CGCGGACCTG GACACCCCAT GGCTGTGGGG

73751 CGCCTACCTC TATCCCGGGC ACGTCAAGGA GCGCCTGGGA TCCGGCGCCC

73801 TGTCCCCGCA GCGCTCGACC CCGCCGGCGG TCACGCCGGA GCTCCAAGGC

73851 GCGGGCACGC TGATGAACGA CCTGCTGCAC GGCGGCGAAC GCGACGCCAC

73901 CGAGGCCGCC GAGCGCGCCC TCAACCGCTA CCGGCTCGGC CCCCGCACCA

73951 TCGCGGTCCA GACGGCCGCG CTGGCCGCCC TCACCTACCG CGACCGGCCG

74001 CACCGCGCGG CCGCCTGGTG CGACGGCCTC GTCGCCCAGG CCGACGAGCG

74051 CAACAGCCCC ACCTGGCGGG CCCTGTTCAC CGCGTGGCGT GCCCTGCTCC

74101 ACCTGCGGCA GGGCGACCCG GCCGCAGCGG AACAGCGCGC CGAAACCGCC

74151 CTCGCCCTGC TCGGATCGAA GGGCTGGGGC GCCGCGATCG GCCTGCCGCT

74201 GGCAGCCGCC GTACAGGCCA AGGCGGCCCT CGGCGATGTC GACGGGGCGG

74251 CGGCCCTCCT GGAACGGCCC GTGCCCCAGG CGGTCTTCCA GACCCGCACC

74301 GGACTGCACT ACCTGGCGGC CCGGGGCCGC TATCACCTCG CCACCGGCTG

74351 CCACTACGCC GCACTGTGCG ACTTCTACGC CTGCGGGACC CGCATGAGCA

74401 GCTGGGGAGT GGACCTGCCC GCGCTGGAGC CGTGGCGCCT CGGCGCGGCG

74451 GAAGCGTACC TGGCCCTCGG CGAAGGACTC CTGGCACGCC AACTCGTCGA

74501 CGGCCAGCTG CCGTTGCCCA CGCCTGACGA CGGCCGCACC TGGGGCATGA

74551 CGTTGCGCCT GCGGGCGGCC ACGTCCCCCG CGCCGGCCCG GGCCGAACTC

74601 CTCGACGAGG CCGTGGCGGT GCTCCGGGAG AGCGGCGACA CCTTCGAGCT

74651 GGCGCGGGCC GTCGCCGACC AGGCTGTTGC CGTACGCGAA GGGGGCGAGG

74701 CGGAACGCGC CCGGCTGCTG GCCCGCAAGG CGGAGCTGCT GGCCCGGCGC

74751 TGGGGCAGCG CCCCCGCGCC CGCCACCGTC CCCGAACCGC CGGAGCGGCC

74801 AGGACCGGCC ACTCCGGACG CCGAACTGAC CAGTGCGGAG CGGAGGGTGG

74851 CCGAGCTGGC CGCCGAAGGG TTCACCAACC GGGAGATCTC CCGGAAGCTG

74901 TGCGTCACGG TCAGCACCGT GGAACAGCAC CTGACCCGGA TCTACCGGAA

74951 GCTCGACGTC AGGCGACTGG ACCTCCAGGC AGCCCTCGGC TGACCTTCAG

75001 GCGGCCCTCG GCTGACCGCA GGCCACGCGC CTACGGTCAG CCTTCCTGAG

75051 TCAGGACCGT ACAGCCGCCG TAGGTGTAGG TGTAGGCGTG GGCGAGATCG

75101 TCGCCGCGTC CAGACCCACC ACGGCCAGCT CCTCCGGAAG GAACGGGGGA

75151 GCGGTCAGCT CCGGGAGGCG TTCGTCGGCG CGCATCGCCA TCAGGAAACG

75201 GTTGGAGCCC AGTTCGGCCT GCGGCGCGTT GAGGCTCATC ACGTCCGTGA

75251 CGATCTCGGA CGCCTTCGGG GAACGGATCG ACGCCGCGGT GATGGCCTCG

75301 GCGAACCGCA GACGCTGCTC GGTGTCCACA CCGATGAGCC GCGGATCCGT

75351 CGCCGAGACA CGGCAGTTGA CGTAGTCGAT GTCCTTGGTC GCGGCGAGGA

75401 TCCACGGGTC GTCCACGGCC GCGCCGATCG CCTTCTGCAG GGCGCGGGTG

75451 CCGGCGCGGG CGGACCCCGT ACCCTCCTGC ACGCTCCGCT CGAACTCGCG

75501 GTCGATCGTG GTGGCGCAGC GCGCGGCCGA GCTCATGCCG TGGCCGTAGA

75551 TCGGGTTGAA AGCGGTCAGC GAGTCGCCGA TGACGAGCAG ACCGTCGGGC

75601 CACTGTTCGA GGCGCTCCGG ATAGAGGCGG CGGTTGGCGC CGGAGCGGGA

75651 ACCGAAGACG GGGGTGAGTG GTTCGGCGTC CCGGAGCAGG TCGGCGAGGA

75701 TCGGGTGGTT CAGGTTCTCG GCGAAGGGGA TGAACTCGTC CTCGTGTGTG

75751 GGCAGTTGCG CGCCCCGCGT GCAGGAGAGC GTCGCGAGCC AGCGGCCGCC

75801 CTCGATGGGG TAGACCACGC CGAAGCGGCC GGGTTCGCGC ACCCGGTCGT

75851 CGGCGGCGAT GTTCACGGCG GGGAAGTGCG TCGTAGCGCC CGGCGGGGCC

75901 TTGAAGAGCC GGGTGGCGTA GGCGACGCCC GCGTCCACGA CGTCTTCCTC

75951 CAGTGCCGGC ACGCCGAGGG CGGCGAGCCA CTGCTTGAGG CGGGAGCCGC

76001 GCCCGGTGGC GTCGATCACC AGGTCGGCCT CCAGCTGCTC CTGCCGACCG

76051 CTGTCGAGGT CGCGGACGAC GACACCGGTG ACCCGGCCGC CACTGCCACC

76101 ACCACTTCCC GTCAGCTCGA CGGCCTCGGT GCGCTGCCGG ACGGTGATGT

76151 TGTCGGCTCC CAAGGCCTGC TGACGTACCG TCAAGTCCAG CAGCGGGCGG

76201 CTGGCGACCA GCGCGAACTG GGTGGCGGGG AAGCGGTGCT GCCACCCCTG

76251 ACCGGTCAGC GTCACCAGGT CCTCGGGGAA GCCGAGGCGG CGGGCGCCGG

76301 CCGCGAGGAG GCGGTCGGTG GTGCCGGGCA GCATCTCCTC GATGAGGCGG

76351 GCGCCGTTGG ACCACAGGAG GTGCGCGTGG CGGGCCTGCG GGACCCCCTT

76401 GCGGTGCTGG GGCTCCTCGG GCAGCGCGTC ACGTTCCACG ACGGTGACGG

76451 CGTCGACGTG CCGGGCCAGG ACGTGGGCCG CCAGGGTGCC TGCCATGCTG

76501 GCACCCAGGA CGACGGCATG TGCGGGTCGG GTGGTGGTCA CGCGCGTATC

76551 CCTTCGGGGT GGGTGGTGTC GGCGGGCCCG GCCGGATCGT CCATGGTCAC

76601 GTCCGTGACG CCCCAGAACG CCTGGACCCG GCGGCCGAGC CCGTGCTCGT

76651 CGAGTTCGAC GATGCCGACG ATGCGGAAGG TCATCGGCCG CGGCCGCTGC

76701 ACGGTGACCG TGGTCGGCGT CACCACGAAA CGGTCGTCCA TCGACGTCAT

76751 CGGCGGGTCC GGCACCTCGT GCGTACCGCA GGAGACGGCC AGTTCGAGAT

76801 GGCGGCGGAG ATCGTCCTTG CCCACCATCG GGGGCCGCCC CACGGGGTCC

76851 TCGAAGACGA TGTCGTCCGT GAACAGGTCG AGGACGCCTT CGATGTCACC

76901 GGCGTTGATG CGCTCGGCGT AGTCGACGGC CATCTGCTTG CGCGCGGCCT

76951 CGTCGGGCAT GGCACCTCCA GGAAGGGTGG GCAGACCTTG TGAAAGTCAT

77001 CGAGGGCCGT TCGGTTCAGC CGAGGACCGT GAGATCGGAT GTGCCCCAGT

77051 ACGACTTCAG ATGCCGGATG AGGCCGGACG CGTCCATGCG GATCACGAGC

77101 ATCGCCGTGC GGTGTATGCG GGCCGTCCCC GGGGCGTCGG GGGCCTTGAG

77151 CCAGCCCCGC TCCGCGTAGA GCGGGCCCAC GGGCAGGTAG TCCATGACGG

77201 AGGAAATCTG GATCAGCGCG TGCGTGGCGT CCTGCCCGGC GACGGGCTCG

77251 GCCGCCTCCT CGCGCAGGTG CGCGGCGAGC AGCGGTTCGT AGTGGGCGCG

77301 CAGCGCGTCG TGCCCGGTGA CGGGCGGGAG GCCGACCGGG TCCTCGAGGA

77351 CCGCGTCGGG CGCGTACAGA TCGATGATCG CGTCCAGGTC CCCGGCGTTG

77401 ATCCGCCGGC TGTGCTCCAG GGCCCGCTTC TTGCGGGCGA ACTCGTTCAT

77451 CGCTGCCCCT CCACTGCCTG ACCGTGTCCG TTGCCGTTGC CGTTGCCGTT

77501 GCCGTTGCCG TGTCCGTTGC CCTGCCCGGT GGGCTGTCCG TTGCCCTGTC

77551 CGCTCGCGCC GTCCCTGCCG AGGTCCCGGT CGATGAACGC GAAGATCTCG

77601 TCCGCCGACG CGTCCTGGAT ACGTGTACGA GTGGCCACCG CGACCTCGCC

77651 GGCCGTGTCC TGCGGCGCGT CGAGCCTGGC CAGCGTCGCG CGCAGCCGCC

77701 CCGCCAGTTC GGCCCGCGCC GAGCCGTCCT TCGAGGAGAC CGAGAGCAGC

77751 GAGTCCTCGA TGCGCTCGAA CTCCGCCAGG ACGTCGGCGA GCGGATCCGC

77801 CGCGCGCGGG GCCAGCTCCT GCCGCAGCTG CGCGGCGAGC TCCGCCGGGT

77851 TGGGATGGTC GAAGACGAAC GTGGCGGGCA GCTTCAGCCC CGTCGCGGCC

77901 GAGAGCCGGT TGCGCAGCTC CACCGCGGTC AGGGAGTCGA AGCCGAGTTC

77951 CCGCAGCCCC TGCGTCGCGT TGACGGGCGT GGCCGCGTCG TAGCCGAGGA

78001 CGGCCGCGAT ATGGGTGCAC ACCAGGTCGA GCAGCGCCTC CTCCCGCTCG

78051 GGGTCGGACA TCGCGCCGAG CGACTTGAGC AGCGCGGCCG CCCCCGCCGA

78101 CACGGCACCG CCGCCGCTCT TGCTCCCCCC GCGCACCAGG TCGCGCAGCA

78151 GCGCCGGTGC GGGGTGGCTC TGGGCCTGCC GGCGCATCCG GGCCAGGTCC

78201 AGACGGACCG GCGCGTACAG GGGCAGTCCG CCGGCCCACG CCGCGTCGAG

78251 GAGGGCGAGT CCCTCGTCGG CGCCGAGCCC GACCACGCCG GCGCGGGCAT

78301 GGCGCGCCCG GTCGGCGTCG GTGAGCCGTC CCGACATGCC GCTCGCCAGC

78351 TCCCAGTAGC CCCACGCCAG GGAGGTCGCC GCCGCACCGC CGTCGTGCCG

78401 GTGCCGGGCC AGCGCGTCCA AGAAGGCGTT GGCGGCCGTG TAGCTGCCCT

78451 GGCCGGGGCC GCCGAGCAGC CCGGCGACCG AGGAGTACAG GACGAACGCG

78501 GACAGGTCCG CGTCCCGCGT CAGCTCGTGC AGGTGCCACG CGGCGTCCGC

78551 CTTCACGCGC ATCACCTCCT CGACCTGCTC GGCCGTGAGG TTCTGCACCA

78601 CGGCGTCGTT CACGGTGCCC GCGCAGTGGA AGACGGCGGT CAGCGGGTGG

78651 TCCGAGGGCA CCGCCGCGAG GAGGGCGGCG GCTTCGTCCC GGTCGCCCGG

78701 GTCGCACGCG GCGAAGGTGA CTCGCGCGCC GAGCGCGGAG AGGTCGGCGG

78751 CCAGTTCGAG TGCGCCCGGC GCGTCGGCTC CCCGCCTGCT GGACAGCAAC

78801 AGGTGCCTGG CTCCGTACCG TTCCACCAGG TGACGGGCCG TCAGCGAGCC

78851 GAGTGCTCCG GTGCCGCCGG TGACCAGCAC GGTGCCCTCG GGGTCGAAGG

78901 CGGGAGGCAG CGAGAACACG GTCGTGCCCG CCGAGGGCGG GGCCGCCATC

78951 GCGGCGGGCG CCTGCCGGAT GTCCCACACG GTGATGTCGA GCGGCGTCAG

79001 AGCACGGCTG TCACCCCGTT CCGCGGGCAG CCCGGGCTCC GCCGACTCCG

79051 TGATCTCGGC AAGCTCGGTC AGCTCGGTCA GCTCCGCGAG GATTTCCCGT

79101 ACGCGCCCGG GCTCGGGCGG CACGACAGCC TGTCCCTCGT CCGGACGACC

79151 GCCCGCACGG TGGACCACCA GGGCCCCCTC GTGGCGGAGG GTGACGTCGG

79201 CCGCGCGCTC GGCGCCCGAA TCATCCGCCG TCGACGCACC GTCCACGGCC

79251 TCGACCCGCC ACCGCCCGGC AAGAGCAAGA CGCAGCACGG CACGGCCGAC

79301 GGAACCGGTT TCCTCCCCGA CGAGCAGAGT CTCGCCGCCG CGCGGCGCCA

79351 CGACATCCGC CAGCACGTGA TACGCGGACA CATAGGCCCC CAAGGACCCG

79401 GCCGCCTGCG CCCAACTCCA GCCCGCCGGA ACCGGCATAA GCAGCGCGGC

79451 ATCGGTGACG GCCACCGGGC CCACCGCGTC GAACAACCCC ATCACCCGGT

79501 CGCCCACGGC CACCGAACCG ACCTCGCCGC CGACTTCCGT CACCACACCG

79551 GCACCCTCGA CCTGGCCCGC CGTGAGCGGC CCCGGCGCCG CGGCCCGCAC

79601 CGCCACCCGC ACCTCGTGCG GCTCCAGCGC CCGTCCGGCC TCGGGAGCGT

79651 CGACAAGGGA CAACTGCTGT CCGCCGCCCG CCTCTTGGCA CCGAGCCAGC

79701 CGCCACGTGA GCGATCCGAC CGGCGGCACC AGCCGCACCG ACGCGTCGTC

79751 GCGCACGAGC CGTGGCACGT AGGCGCGCCC GTCACGCAGC GCCAATTCCG

79801 GTTCGCCGGA GGCCAGTACG CCGGTCAGCG TGGCCGGAGA AGACTCCAGT

79851 CCGTCCACGT CGAGCAGCGT GAGGCGACCG GGATTCTCGG CCTGCGCGCT

79901 GCGCACCAGA CCCCACAGCG ACGCGCCCGC CAGATCACCG GCGGTCTCAC

79951 CCGGCCGCGC GGCGACCGCG CCTCGGGTGA CGACGACGAG ACGGGTCGCC

80001 GCGAACGCCG GGTCGTCCAC CCACTCCTTG AGCAGCGACA GAAGGGACAC

80051 GGTGGCCAGC CGCGCGTACC CGGCCGGGTC GCCGCCCCTG CCATCGGCAT

80101 CCGCAACGGC CCCGGCACCT GCGCCGGGCG CGGCGCACAC GGCGAGCACG

80151 ACATCGGGCG CTTCGCCCCC AGCCGCCACT CCGTCCCGGA GCGCACCGAA

80201 CGTGTCCCAC ACGGGGCCGG CGGCCAGCGC ATCGGACAAG GCGTCGGCCA

80251 GCGCACCGGC CGACGTACCG CCCATCGGGC CACTCTCGAC CGGCGCGAGG

80301 ACCGCGGCAC GCGGGGCGCC GCCGCCCGTC TCCTCGGCCC GCGCGGCGAC

80351 CTCCATCCAC ACGAGCCGGA ACAGCGCGTC ACGGTCCGCC GCACGGGCGC

80401 CCGCGATCTG GTGGGCGGCC ACCGGCCGTA CCGTGAGCGA CTCCAGCGTG

80451 AGAACCGGCT CCCCGCCTCC GCCCCCGTCC ACGGCCGTGA GGGCCAGCTG

80501 GTCGGGCGCG GTGCGTGCGA TACGTACCCG CAACTTCTCA GCGCCCGGCG

80551 CGTGCACCCG CAACCCGCTC CAGGAGAACG GCAGCAGCAC TTGGTCGGTG

80601 TCGGCGGACG ACGTGACCGC GTCCAGGATC AGCGCGTGCA GCGTGGCGTC

80651 GAGCAACACC GGGTGCACCT GGTAGCGGTC GGCCCTGCCG CTCTCCGCCT

80701 CGGGCAGCGC CACCTCGGCG AAAAGGTCGT CCCCGAGCCG CCACGCGCTC

80751 ACCAGTCCCT GTGAGCCGGG CCCGAAGTCA TAGCCGTACG AAGCGAGTTC

80801 CCCGTACGGA TCCTGCTCGC CGACCGGTGT GGCGCCCGGG GGCGGCCACG

80851 TCCCGCCGAA CGAGGCGTCC CCGGCGTCGG GCCCCGGGGG AGCGACCACG

80901 CCCGCGGCAT GCCGGGTCCA CACGGCCTCC TCGCCCTCAC CCGTGGGCCG

80951 CGAATGGACG GTCACGGGAC GCCGCCCGTC CTCGGCCACG GAACCGACCA

81001 CCACCTGCAC GTCGACCGCG CCCGCACCCT CGTCCCCGAA GGCGAGCGGA

81051 GTGTGCAGCG TCAGCTCCGC CAACTCCGCG CAGCCGGCCC GCACCGCGGC

81101 CTGCAGCGCG AGCTCCACGA ACGCCGAACC GGGCAGCAGC ACCGTGTCCA

81151 TGACCCGGTG CTCGGCCAGC CACGCCTGGT CCCGCGGAGA GATCCGGCCG

81201 GTCAGCAGGT GACTGCCGCC GTCCGCGAGT TCCACGGCGG CTCCGAGCAG

81251 CGGATGCCCC GCGGACGCGA GCCCGAGCCC CGCCGGGTCC CCGGCGAGCC

81301 CCCTGCGCCC CTCCAGCCAG AACCGCTCCC GCTGGAAGGC GTACGTCGGC

81351 AGATCCACCA CCCGAGGCAG CGGCACGGCC GGGAACCAGC CCGTCCAGTC

81401 GACCTCCGCC CCCGCGCCGA AGGCCTGGGC GGCCGCGCGG GTGAGCTGCG

81451 CGGCGTCGCC GTGGTCGCGG CGCAGGGTGG GCACGACGGT GGCGGGCATG

81501 TCGGCCCGCT CGATGGTCTC CTCCATGCCG AGGTTGAGGA CGGGGTGGGG

81551 GCTGGCCTCG ATGAACAGGC GGTAGCCGTC GGCCAGCAGC GCTTCGATGG

81601 TGTCGGCGAA GCGGACGGGC TGGCGGAGGT TGGTGACCCA GTAATCCGTG

81651 TCGAGGGTGG TGGTGTCGTC GAGGCGTTCG GCGGTGACCG TGGAGTAGAA

81701 GGCGACGTCC GTGGTCGTGG GCCGGATGTC GGCCAGGCGC TCGGTGAGGA

81751 GGTCGTGGAG CTGGTCGATC TGGGGGCCGT GGGAGGCGTA TCCGACGTCG

81801 ATGACGCGGG CGCGCAGGCC TCGCGCCTCC GCATCCGCGA CCACGGCTGC

81851 CACATGCTCC GGCGGCCCTG AAATGACCGT AGAGGAGGGC CCGTTGACGG

81901 CAGCGACACA CACGCCGGGC CGGTCGCCGA TGAGCTCAGC AACCTGCTCC

81951 GAGCCGGCCC CCAACGACGC CATGTCGCCC TGCCCCATGA GCTGACGGAG

82001 CGCGTCACTG CGTACGGCCA CGATCCGCGC CGCATCCTCC AGTGACAGTG

82051 CCCCCGCCAC ACACGCGGCG GCCATCTCGC CCTGCGAGTG CCCGATGACG

82101 GCAGCCGGGG TGATGCCGTA ATCGGCCCAC ACCGAAGCCA GCGAGACCAT

82151 CACCGCCCAC AACACGGGCT GCACGACCTC GACCCGGGAC AGCTCACTCC

82201 CGTCCCCGCG CAACACCGCA CTCAGCGACC AGTCCACATG CGCCGACAGG

82251 GCCCGCTCAC ACTCCGCGAT CCGCGCCGCG AAGACGGGGG ACTCGTCAAG

82301 GAGCTGGGCA CCCATGCCCA CCCACTGCGA CCCCTGCCCC GGAAACACCA

82351 ACACCGGACC CGCGCCGGAG GCGCCCTGTA CGGCGCCCTC GACGACGTCC

82401 GGTGACGGCT CGCCCGCCGC CAGGGACCGT AGCCCGGCGA GGAGAGTCTG

82451 GCGGTCCTTG CCCACGACGA CGGCTCGGTT CTCGAACACC GACCGGGTCT

82501 TGACCAGGGA CCAGCCCACG TCCAGCGGCG ACGCGAGCCG CGGGTCGGCG

82551 GTGGCGCGGT CGGCCAGCAG GCGGGCCTGG GCCCGCAGCG CCTCCTCGCC

82601 GCGCGCCGAC ACCACCCAGG GCACCACTCC GGCCGGCGCC GCGGCGTCCT

82651 CCGCCGGAGC GGTCACGGGC TCCGGCGCGT CCGGGGCCTG TTCCAGGATG

82701 AGGTGCGCGT TGGTGCCGGA GATGCCGAAG GCGGACACCC CGGCGCGGCG

82751 CGGGCGTTCG CCGCGCGGCC AGGAGACCGG TTCGGACAGC AGGCGGACGC

82801 CACTGCCGTC CCAGTCCACG TGCGGCGTGG GCGCGTCGAT GTGCAGGGAG

82851 GCGGGCAGCT GTTCGTTGCG CAGCGCCATG ACCATCTTGA TCACACCGGC

82901 GACACCGGCC GACGCCTGCG CGTGCCCGAT GTTCGACTTG ATCGAGCCGA

82951 GCCACAGCGG CCGGTCCGCG GGCCGCTCCT TGCCGTAGGT GGCGACGAGC

83001 GCGCTGGCTT CGATGGGGTC GCCCAGCATG GTGCCGGTGC CGTGCGCCTC

83051 CACCGCGTCG ACGTCCTCGG CGGAGAGCCG CGCGTTGGCG AGTGCCTGCC

83101 GGATCACCCG CTGCTGCGCC TGCCCGTTGG GTGCCGTGAG CCCGTTGCTC

```
83151  GTGCCGTCCT GGTTGATGGC CGAACCCCGG ATCACCGCCA GGACGTTGTG
83201  GCCGTTGCGC CGGGCCTCCG AGAGCCGTTC GAGTACGACC AGGCCGACTC
83251  CCTCGGCCCA GCCGGTGCCG TCGGCGGCGG CCGCGAACGG CTTGCACCGG
83301  CCGTCCTTGG CGAGCCCGCG CTGCAGCGAG AACTCGACGA ACGAGCCCGG
83351  CGTGGCCATC ACCGTCGCGC CGCCCGCGAG AGCGAGCGAG CACTCGCCCT
83401  GGCGCAGCGC GTGCGCCGCC TGGTGGATCG CCACCAGGGA CGAAGAGCAG
83451  CCGGTGTCGA TCGTCATGGC GGGGCCTTCT AGGCCGAGTA CGTACGACAC
83501  CCTGCCGGAG GCGACACAGC CGAGGTTGCC GGTGCCGATG TAGCCCTCGA
83551  CCTCGGTGGG CTGTTCACCG ACGAGCGCGA GGTAGTCGAA GATGGTCAGG
83601  CCCGTGAACA CCCCGGCGTC GCTGCCCTTG AGGGTCTCCC GGTCGAGGCC
83651  CGCGCGTTCG ATCGCCTCCC ACGCGGTCTC CAGGAGCAGC CGCTGCTGCG
83701  GGTCCATCGC GACGGCCTCG CGGGGGCTGA TGCCGAAGAA TCCGGCGTCG
83751  AAGTCGCCCG CGTCGTAGAG GAACCCGCCT TCGCGCACAT AGCTGGTGCC
83801  GCGGCTCTCC GGGTCCGGGT CGTACAGCGT CTCCAGGTCC CAGCCCCGGT
83851  CGTCGGGGAA GGCCCCCATG GCGTCCTTGC CGGCCGCGAC CAGATCCCAC
83901  AGCTCCTCGG CGGAGCGGAC GTCGCCCGGA TAGCGGCAGG CCATGCCGAC
83951  GATCGCGATC GGCTCGTCGT CGGCGGCGCC CCTGGAGGCC CCGGCCGCCC
84001  GCACCGGGTC GGCGGAGGCC GCCGCGTCAC CGGACAGCTC GGCCCGCAGG
84051  ACGTCGGTGA GCGCGTCGGG GGTGGGGTGG TCGAAGACGA CCGTGGTCGG
84101  CAGTGTCAGG CCGGTGCTCT TGTTCAGCCT GTTGCGCAGC TCCACCGCGG
84151  TCAGCGAGTC GAAGCCCAGC TCCTGGAACG GCTTGGTGGC GGGCACCGCG
84201  TCGACGTCCG AGTGCCCCAG CGTGGCCGCC GCCTGGGAGC GCACGTGCTG
84251  CAGCAGCAAC TGCCGCTGCT GCGCCGGCTT CGCCTCCGTC AGCTCCTGCT
84301  GGAGCGACGA TGCCTCCGTG GCGTCTTCCT GCTGTGCCGC GGGTGCGCTG
84351  GCCCGCCGGT TCTCGGGCAG ATCGGCGAGG AGCGGGCTGG GCCGCTGCGC
84401  GGTGAACGTC GACGTGAACT GCGCCCAGTC GAAGTTCGCC ACGGTCAGCG
```

84451 TCGTCTCACC CGCGTCCAGG GCCTGCTGCA GCGCCTTGAC GCACAGCTCC

84501 GGGCTGAGCG GGTGCAGGCC GAAGCGGCTG AAGAACGTCA ACGCGGCCTG

84551 GTCCGCCGCC ATGCCCGCCT CGGCCCAGGG CCCCCAGGCG ATGGAGGTGG

84601 CGGGCAGGCC CTCGGCGCGG CGGTGCTCGG CGAGGGCGTC GAGGAAGTGG

84651 TTGGCCGCAC CATAGGCGCC CTGCTGGCCA CTGCCCCACA CGCCTGCGCC

84701 CGACGAGAAC ATCACGAACG CCGAGAGCGG CAACTCCCGG GTCAGTTCAT

84751 GCAGATGGTG AGCGGCGAGC GCCTTCGGAC GCAGCACCTC GTCCAGCTCG

84801 GCACCCGACA CGTCGCCGAG ACCGATGTAG TTCGGCACGC CGGCCGCGTG

84851 GATGACGGCG GTCAGCGGGT GCTCGGCGGG GACATCGTCG ATGAGGCGTC

84901 GCACCTGCTC GCGGTCGCCG ACGTCGCAGG CGGTGACGGT GACGGCGGCC

84951 CCCAACTCCG TCAGTTCCGC GGCGAGTTCC TGTGCTCCCG GGGCGTCGGG

85001 GCCGCGGCGG CTGGTCAGGA GGAGGTGCGG GGCGCCCGCA CGGGCGAGCC

85051 ACCGCGCGAG GACGGCGCCG ATGCCGCCGG TCCCGCCGGT GATGAGAGTG

85101 GTGCCGTCGG GCCGCCAACC AAGCCCGCTG CCGACCGTGT TGGCGGGCGC

85151 GTGTGCAAGG CGACGGGCAT GGACGCCGGA CGGCCGGATG GAGATCTGGT

85201 CCTCGTCCTG CGGAACCAGC GCGGCGGCCA GCCGGGCCAG CGTCTGATGG

85251 TCGATACGAG CGGGCAGATC GACCAGCCCG CCCCACAGCC GCGGATACTC

85301 CAGCGCAGCG ACGCGCCCCA GCCCCCACAC CTGAGCCTGC ACCGGGTGGG

85351 TGAGGGCGTC GCCGGCGCTC GTGGAAACAG CCCCCTGCGT GAGAGTGCGT

85401 ACGGCGATGT CGGCGCCGTT GTCCGCGAGG GCCTGGACGA GAGCGGTCGT

85451 CGCGGCGAGT CCGGCGGGCA CGGCCGAGTG CTCGGGATGC GGCTCCTCGT

85501 CCAGGGCCAG CAGATTGACG ACTCCGGCAA ACGCGGCCCC GTCCATCAGG

85551 ACACGCAGCT CCTGCGCCAA CTCCGTACGC TCCATGGCAC GTGCGTCGAC

85601 CACGTGGCGT CGCACCTCGC CACCATGGGC GGTCAGCGTC TGCGCGGTCG

85651 CGAGGACGGC CGGGTGGTCG GCGTGCGCGG CGGGCACGAG CAGCAGCCAG

85701 GCCCCGCTGA GCTCCGGCGC CGGCACGTCG GGCAGATGCT TCCAAGTGAC

85751 CTGATAACGC CAGGAGTCGA CGGTGGACTG CTCGCGGTGC CGACGCCGCC

85801 AGGCCGAGAG GACGGGCAGC GCGGACTCCA GCGCTCCGAC GCTCTCCGCC

85851 TGCCCCTCGA TCTCCAGACT GCCGGCGAGG GCGTCGATGT CCAGGTCCTC

85901 GATCGCCTGC CACACCCGGG CCTCGACCGG ATCGTGCCCA CCACCCACGG

85951 CTGCGACCGC CGCGGGCGGC TCCACCCAGT AGTGCTTGTG CTGGAAGGCG

86001 TAGGTGGGGA GGTCGACGGT ACGGGGGGTG GGGTCGGCCG GGAACCAGCG

86051 CCGCCAGTCG ACGGGGGCGC CGGCGGTGAA GGCGTGGGCG GCCGCGCGGG

86101 TGAGCTGGGT GGTGTCACCG TGGTCGCGAC GCAGGGTGGG GATGGTGACG

86151 GCCGTCCCCG CAGCACCGGC CTGCTGCTCG ATGGTCTCCT GGATGCCGAG

86201 GTTGAGGACG GGGTGGGGGC TGGCCTCGAT GAACAGGCGG TAGCCGTCGG

86251 CCAGCAGCGC TTCGATGGTG TCGGCGAAGC GGACGGGCTG GCGGAGGTTG

86301 GTGACCCAGT AGGCGGTGTC TAGGGCGGTG GTGTCGTCGA GGCGCTCTGC

86351 GGTGACCGTC GAGTAGAACG CCACGTCGGT GGTGGTCGGC TGGATGTCGG

86401 CGAGCCGGTC GGTGAGGAGG TCGTGGAGCT GGTCGATCTG GGGACCGTGG

86451 GAGGCGTACC TGACGTCGAT GACGCGGGCC CTGAGTCCCT GCGCCTCCGC

86501 ATCGGCGACG ACGGCTGCCA CATGCTCCGG CGGGCCCGAA ATCACGGTCG

86551 ACGACGGTCC GTTGACGGCC GCGACGACTA CGCCCGGCCG GTCGCCGATC

86601 AGCTCTGCGG CCTGCTCGGC ACCGGTGCTG AGCGAGGCCA TGTCGCCGTG

86651 CCCTTGCAGC TGACGAAGCG CGTCGCTGCG TACGGCTACG ATCCGTGCCG

86701 CATCCTCCAG TGACAGTGCC CCCGCCACAC ACGCGGCAGC CATCTCGCCC

86751 TGCGAGTGCC CGATGACGGC AGCCGGGGTG ATGCCGTAAT CGGCCCACAC

86801 CGCAGCCAGC GAGACCATCA CCGCCCACAG CACGGGCTGC ACGACCTCGA

86851 CCCGGGACAG CTCGCTCCCG TCCCCGCGCA AGACATCACT CAGCGACCAG

86901 TCCACATGCG CCGACAGCGC CTGCTCACAC TCCGCGATCC GCGCCGCGAA

86951 GACGGGCGAC TCGTCAAGGA GCTGGGCGCC CATGCCCACC CACTGCGACC

87001 CCTGCCCCGG AAACACCAAC ACCGGCCCAG GACCCACATC ACCGGCCACC

87051 CCGGCCACCA CATCCGCCGA CGCCTCACCC GCGGCCAATG CCTCCAGGCT

87101 GGCACCAGCC TGAGCCAAGT CCCGCCCCAC GACCACGGCC CGCTGATCGA

87151 ACAACGCGCG TGTCGTGGCC AGCGACCAGC CCACCTCGGA GACCGACGCA

87201 TCCGCCAGCC CGGCCGCGAA CTCGCCCAGC CGCCGCGCCT GTTCACGCAA

87251 CGCGTCCGGC GTCCGCCCGG ACACCACCCA CGGCACGACC CCACCCGGCT

87301 CAGCCGCCAC GGGGCCCGGC GCGTCCTCTT CCGGCGGCGC CTCCTCCAGA

87351 ATCAGGTGCG CGTTCGTCCC GGAGATCCCG AACGCCGAGA TGCCTGCCCG

87401 CCGCGTGCGC TCCGCCGGCC AGTCCACGGG CTCGGAGAGC AGTCGTACGC

87451 TGCCCTGTTC CCACTGGACG TGCGGTGACG GGGCGTCGAT GTGCAGGGAG

87501 GTCGGGAGGA GACCGTTGCG CATCGCCATG ACCATCTTGA TGACGCCCGC

87551 GACACCGGCG GCGGCCTGCG TGTGGCCGAT GTTGGATTTC ACCGAGCCGA

87601 GCCAGAGCGG ACGGTCCTCC GGGCGCCCCT GGCCGTACGT GGCGATCAGG

87651 GCCTGCGCCT CGATGGGGTC GCCGAGCGTG GTGCCGGTGC CGTGCGCCTC

87701 TACGGCGTCG ATGTCCTCGG CGGAGAGGCG GGCGTTGGCG AGGGCGGCGC

87751 GGATGACGCG TTCCTGGGAG GGGCCGTTGG GGGCGGCGAG CCCGTTGCTC

87801 GTACCGTCCT GGTTGGTGGC CGAACCCCGT ATCACCGCAA GGACCTTGTG

87851 GCCGCGGCGC CGCGCTTCGG AGAGCAGCTC CAGCGCCACC ACCCCGGCGC

87901 CCTCGCCCCA GCCGGTGCCG TCGGCGGCGG CCGCGAACGG CTTGCACCGC

87951 CCGTCGGGCG CGAGCCCCCG CTGCCGGGAG AACTCGGTGA ACGAACCCGG

88001 CGTCGCCATC ACCGTCGAAC CGCCCGCCAG CGCGAGCGAG CACTCGCCCT

88051 GCCGCAGCGC CTGACTTGCC AGATGGATCG CCACCAGGGA CGACGAGCAC

88101 GCCGTGTCGA CGGTGACCGC GGGACCTTCG AGCCCCACCG TGTAGGAGAT

88151 CCGGCCCGAC ACCACACTGC CGAGGTTGCC GGTGCCGATG TACCCCTCGA

88201 CGTCGCTGGC CGTCTGGCTG ATCAGCGTCA GGTAGTCGTG GGCGCTCACT

88251 CCGGTGAAGA CGCCGGTGTC GCTGCCCTTC AGCGCGTGCG GGTTCATGCC

88301 CGCGTGCTCG ATCGCCTCCC ACGCGGTCTC CAGGAGCAGC CGCTGCTGCG

88351 GATCCATCGC CGTGGCCTCG CGCGGGCTGA TGCCGAAGAA CTCGGCGTCG

88401 AAATGGCCGG CGTCGTACAG GAAGGCGCCG TCCCGCACAT AGCTGGTGGC

88451 CGGATGCTCC GGATCCGGGT GATACAGCGA CTCCAGGTCC CAGCCCCGGT

88501 CGTCGGGGAA CCCCGCGACC GCGTCACCCC CGTCGCGCAC GAGTTCCCAG

88551 AGGTCCTCCG CCGACCGGGC GCCGCCCGGG TAGCGGCAGG CCATGCCGAC

88601 GATGGCGACC GGCTCGGTCG ATTCCTTGTC GTGGAGCCGT TGCCGGGCCT

88651 GGCGCAGCTC CGCGGTGACC CACTTGAGGT GATCGAGAAG CTTCTCCTCG

88701 TTCGACATCT GACCCAGGCT CCTTGGCGCT ACGTGGTGAT CGGGGCGTAT

88751 GAGGTTGGGG GAGGGCAAGG GGGCCGGTGT GGCCGGGGCT CATCGCGCTC

88801 AGGACTGATC GCTGCTCAGG ACTTCCCGAA CTCACTGGAG ATGAGGTCGA

88851 AGATGTCGTC CGCGCTCGCC GCCTCCAGAT CGGCATGGGC CGAATCAGTG

88901 CCTTCCGGCC CGTCCTGCGC CGGACTCCAC TTCGACACAA GGACCTGCAG

88951 CCGGCCCACG ATGCGGCGCC GGGCCGCCTC GTCCACCTCG GCCGCTCCGA

89001 ACGCCGTGTC CCACTTGTCG AGCGCCGCGA GCACGTCGCC CTCACCTGCG

89051 ACCTCGGCGC CGTCGCCGAG CTGTCCGCGC AAGTGCGTGG CGAGGGCCTC

89101 GGGCGTGGGA TGGTCGAAGA TCACGGTGGC GGGGAGCGAG AGTCCGGTCG

89151 TGGTGTTGAG CTGGTTGCGC AGCTGGACCG CGGTGAGCGA GTCGAAGCCC

89201 AGCTCCTGGA ACGGCTTCGC GGCGGGAATG TCCTCCACCG TGCGGCCGAG

89251 CGTCGCGGCC GCGTATGTCC GGACCTGCTG GACCAGGAAG CCGAGCCGCT

89301 GTGATGCGGG CGTCTTCGCC AGCTCCTCGC GGAACGCGCT CGTCTCGGCG

89351 GCGGTCCCCG TCTGCTCGGC CTCCCGCTGG TTCTCCGGAA GGTCGTCGAG

89401 GAACGGACTG GGCCGCTGCG CGGTGAACGT CGGCGTGAAC TTCGCCCAGT

89451 CGAAGTTCGC CACGGTCAGC GTGGCGTCGC CCGCGTCGAC CGCCTGGTGC

89501 AGCGCCTTGA CGCACAGATC CGGAGCGATC GGGAGCAGAC CGAAGCGCTT

89551 GAAGTACGTC AGTGACTCCG GGTCGGCGGA CATGCCCGCC TCGGCCCAGG

89601 GCCCCCAGGC GATGGAGGTG GCGGGCAGGC CCTGGGCGCG GCGGTGCTCG

89651 GCGAGGGCGT CGAGGAAGTG GTTGGCCGCA CCATAGGCGC CCTGCTGGCC

89701 ACTGCCCCAC ACGCCGGCGC CCGACGAGAA CATCACGAAC GCCGAGAGGT

89751 CCAGGTCGCG CGTCAACTCG TGCAGGTTCC AGGCCGCGTC GGACTTCGAC

89801 CCCAGCACCT CGCCGAGGCG CGCGGTCGTC AGATCACCGA TCGCGGTCAG

89851 ATCGGTCATG CCCGCCGCGT GGATGACGGC TGTGAGGGGA TGCTCGGCCG

89901 GCATGTCGTC GATGAGGCCG CTCAGTTGGC GGGGATCGCT GACGTCGCAG

89951 GCGGTGATGG TGACGGCGGT GCCGAGCCCG TCGAGCTCGG CGGCGAGTTC

90001 CCGGGCGCCG GGCGCGTCGG GCCCGCGACG GCTGGTGAGG TGAAGACGGG

90051 GGGCGCCCTG CCGGGCCAGC CAACGGGCGA GGACGGCACC GATGCCGCCG

90101 GTCCCGCCGG TGATCAGGGT GGTGCCCCGA GGCCGCCAGG TGGCCTCGCT

90151 GTGCACGGGA TTCTGAATGC TTCCGACGGC GTGCGTGAGG CGCCGGTGGT

90201 GGATTCCGGT GGGGCGGACG GCGGTCTGGT CCTCGTCGTC CTGGGGGAGG

90251 AGAGCGGCGG CGAGGCGGGG GAGGGTGTGG CGGTCGATAC GAGCGGGGAG

90301 GTCGACGAGT CCGGCCCAGA GGCGCGGGTG TTCGAGGGCT GCGACGCGGC

90351 CGAGCCCCCA GACGTGAGCC TGGAGGGGGT GGGTGAGTGG GTCGGTGGCG

90401 GCCGTGGACA CGGCACCCTG CGTGACGGTG TGCAGGGGTG CGGTCGTGCC

90451 GTTGTCGCCG AGGGCCTGGA GGAGAGCGGT CGTCGCGGCG AGCCCCGCGG

90501 GCACGGCGGG GTGCTCGGGG TGCGGCTCCT CGTCCAGCGC CAGCAGATTG

90551 ACGATTCCGG CAAGACCGGC CGTGTCCACC GCGGCCAGCT CCTGACGTCC

90601 CGCCCGGCCG GTCTCGACCG GATGCAGCCG GACGGCGGCC GCCCCGTGCT

90651 CGCTCAACGC CTCGGCGGTG GCTCGTACGG CGGGGTGCTC CGCCTTGTCG

90701 GCAGGGACGA ACAGCAGCCA GTCGCCGCCG AGTTCCGGTG CGGGCCCGTC

90751 GGACCGCTGT TTCCACGTGA CGCGGTACCG CCAGGAGTCG ATGGTCGCCT

90801 GGTCCTGGTG CCGACGCCGC CAGCCCTTGA GCACCGGCAA CGCGGGCTCC

90851 AGCGCCCGGA CCGCCTCCTC GCTGCCCTCC TCCGACCCCA GCGTCTCGGC

90901 CAGCAGACCG AGATCGAGCT CCTCGACGGC GTGCCACAGC TGGGCCTCGG

90951 CCGCACTCTG CTCACCGCTG ACGGCGCCCG AGGCGGACGC GGAACGTTCG

91001 AGCCAGTAGT GCTGGTGTTG GAAGGCGTAG GTGGGGAGGT CGACGGTGCG

91051 GGGGGTGGGG TCGGCCGGGA ACCAGCGCCG CCAGTCGACG GGGGCGCCGG

91101 CGGTGAAGGC GTGGGCGGCG GCACGGGTGA GCTGGGTGGT GTCGCCGTGG

91151 TCGCGGCGGA GGGTGGGGAC GACGGTGGCG GGGATGTCCG CCTGCTCGAT

91201 GGTCTCCTCC ATGCCCAGGC CCAGCACGGG GTGGGCGCTG GCCTCGATGA

91251 ACAGGCGGTA GCCGTCCGCG AGAAGGGCTT CGATGGTGTC GGCGAACCGG

91301 ACCGGCTGGC GGAGGTTGGT CACCCAGTAA TCCGTATCCA GGGCTGTGGT

91351 GTCCGTCAGA CGCTCGGCGG TGACCGTCGA ATAGAAGGCC ACGTCCGTGT

91401 TCGCGGGCCG GATGTCAGCC AGGCGTTCGG TCAGCAGATC GTGGAGCTGG

91451 TCGATCTGGG GGCCATGCGA GGCGTACCCG ACGTCGATGA CACGGGCGCG

91501 CAGACCACGT GCCTCCGCAT CGGCGACCAC GGCAGCCACA TGCTCCGGCG

91551 GCCCTGAAAT CACCGTAGAC GACGGCCCAT TGACCGCCGC GACGACCACG

91601 CCCGGCCGGT CACCGATCAG CTCAGCGGCC TGCTCGGCAC CGGTGCTCAG

91651 CGAGGCCATG TCACCGTGCC CTTGCAGCCG ACGAAGCGCG TCACTGCGTA

91701 CGGCTACGAT GCGCGCCGCA TCCTCCAGCG ACAGCGCCCC CGCGACGCAC

91751 GCGGCAGCCA TCTCACCCTG CGAGTGCCCG ATCACAGCAG CCGGAGTGAC

91801 CCCGTAATCA GCCCACACCG CAGCCAGCGA GACCATCACC GCCCACAACA

91851 CCGGCTGCAC GACCTCGACC CGGGACAGCT CACTCCCATC CCCGCGCAAC

91901 ACCGCACTCA GCGACCAGTC CACATACGCC GACAGCGCCC GCTCACACTC

91951 CGCAATCCGC GCCGCGAAGA CGGGGGACTC GTCCAGCAGC TGGGCACCCA

92001 TGCCCACCCA CTGCGACCCC TGCCCCGGAA ACACCAACAC CGGCCCAGGA

92051 CCCACATCAC CAGCAACCCC GGCCACCACA CCCGCCGAAG CCTCACCCGC

92101 AGCCAACGCC CCCAGGCCAG CCGTCAACGC ATCGCGGTCA CGCCCCACCA

92151 CCACAGCCCG GTGCTCGAAC ACCGACCGGG TCGTGGTCAA CGACCAGCCC

92201 ACATCAGCCG CCGACGCATC CGCCGGCCCG GCCGCGAACT CGCCCAGCCG

92251 CCGCGCCTGT GCACGCAGCG CGTCCGGCGT CCGCCCGGAC ACCACCCACG

92301 GAACGACCCC ACCCGGCTCC TCGGCCACGG AGCCCGGCAC GTCCTCCTCC

92351 TCCGGTGGTG CCTCCTCCAG GATCAGATGC GCGTTCGTCC CCGAGAAGCC

92401 GAACGAGGAC ACCCCCGCCC GGCGCGGGCG CTCGCCCCGG GGCCACTTCA

92451 CCGGGTCGGT GAGCAGGCGC AGCCCGCTGC CGTCCCACTC CACGTGGGGC

92501 GAGGGGGCGT CGACGTGCAG GATGGCGGGC AGCAGGTCGT GCCGCAGGGC

92551 CAGGACCATC TTGATGACAC CGGCCACACC GGCGGCGATC TGCGTGTGGC

92601 CGATGTTGGA CTTCACCGCT CCCACCCACA GCGGCCGGTC CTCCGGCCGT

92651 TCCCGGCCGT AGGCGGAGAT GAGAGCCCCG GCCTCGATGG GGTCGCCGAG

92701 CGTGGTGCCG GTGCCGTGCG CCTCCACGGC GTCGATGTCC TCGGGGGCGA

92751 GGCGGGCGTT GGCGAGGGCG GCGCGGATGA CGCGTTCCTG GGCGGGGCCG

92801 TTGGGGGCGG TCAGGCCATT GCTCGCGCCG TCCTGGTTGA TCGCCGAACC

92851 CCGGATCACC GCGAGGACCT TGTGGCCCTT CCTGCGGGCG TCGGAGAGAC

92901 GCTCAAGGAG AACCACCCCC GTACCCTCCG CCATGCCCAT GCCGTCGCTG

92951 CTCGCCGAGA ACGGCTTGCA CCGTCCGTCG GGGGCCAGGC CGCGCAGTTC

93001 GCTGAAGCCG ATCAGCGGGG CGGGCGACGA CATCACGTAC GTGCCGCCCG

93051 CCAGCGCCAG CGAGCACTCC TGTGTGCGCA GGGCCTGGGT GGCGAGGTGA

93101 AGGGAGACCA GCGACGAGGA GCACGCCGTG TCGACCGTCA CCGCGGGGCC

93151 TTCGAGGCCC AGGGTGTAGG CGACGCGGCC GGAGGTGACG CTGCCGGAGT

93201 TGCCGATGGT GAAGTATCCG GCGGTGCCCT CGGGGACCTC GGACGCGCCG

93251 AGGGCGTAGT CGAGTCCGTC ACAGCCGATG AAGGTGCTGG TGTCGCTGGA

93301 GCGGAGGCTG AGGGGGTCGA TGCCGGCCCG TTCGATCGCC TCCCACGCCG

93351 TCTCCAGGGC GAGCCGCTGC TGCGGCGCCA TGGCCGCGGC CTCGGTGGGT

93401 CCGATGCCGA AGAAGGTGGG GTCGAAGTCA CCGGCGTCGT AGACGAAGCC

93451 GCCTTCCCGG ACGTAACTGG TGCCGGTGCT CTCGGGGTCC GGGTCGTAGA

93501 GGGAATCGAG GTCCCAGTTG CGGTTGCCGG GCAGGGGCGC GACGGCGTCG

93551 CCGCCGGTGG AGACCAGCTC CCAGAACTCT TCGGGAGACC GGACTCCGCC

93601 GGGCAGCCGG CAGGCCATGC CGATGACCGC GACCGGTTCG TGGCCCGCCG

93651 ACTCGACGTC CTGCAGCCGG CGTTCCGTCT GACGCAGGTC CGCGGTGACA

93701 CGCTTGAGGT ATTCCAGAAG TTTCTCTTCG GTGTGCGCCA TCCCGGTGAC

93751 AACCGCCCCT CTCCGCGAGA ACAGACCGCA GACTCGTCGA CGGCGCTAAA

93801 GCCCTCCTAA TACTCGGCTG TGTACCGCTC GCTGCCACGG GTGTCCGCAC

93851 TGGTCGGAGG CTCCGGCCCA GGGAACAGGG GCTTTCTTAG GGGCGCTTAA

93901 GCGGTGCCTG CCAGGGTGTG CCGGTGTCAG GCCGTCACGC CCTGATCAGC

93951 GGCGTCGCCC GTGCCGTGCC CGTGCGGTCG GTGGGCCTGA CCGTCGGTCC

94001 GGACAACGCG AAGCGAGGCA TCGTGCCCAT CACGGATAGC AAGCCGGCCG

94051 CCACATTCCC CGACCTGGTC GACCCGTCGT TCTGGGCGCG GCCGCACGCG

94101 GAACGCGTGG CGCTGTTCGA GGAGATGCGC GGGCTGCCGC GGCCGGCGTT

94151 CATCCGGCAG AACATGCCCG GCGTGCCCTG GACGTTCGGC TACCACGCGC

94201 TGGTCAAGTA CGCGGACATC GTGGAGGTGA GCCGCCGCCC GCAGGACTTC

94251 TCCTCGAACG GCGCGACCAC CATCATCGGT CTGCCGCCCG AGCTGGACGA

94301 GTACTACGGC TCGATGATCA ACATGGACAA CCCGGAACAC TCGCGGCTGC

94351 GGCGCATCGT CTCGCGTTCC TTCGGCCGCA ACATGATCCC CGAGTTCGAG

94401 GCCGTGGCGA CCCGCACCGC CCGCCGCATC ATCGACGAGC TCATCGCGCG

94451 GGGACCCGGC GACTTCATCA GGCCCGTCGC CGCGGAGATG CCCATCGCCG

94501 TGCTCAGCGA CATGATGGGC ATCCCGGCGG AGGACCACGA CTTCCTCTTC

94551 GACCGGTCCA ACACGATCGT CGGCCCCCTC GACCCGGACT ACGTGCCGGA

94601 CCGGGCGGAC TCCGAACGCG CGGTGATCGA GGCGTCACGC GAACTCGGCG

94651 ACTACATCGC TGGCCTTCGT GCGGAACGGC TCGCCGCCCC CGGCAACGAC

94701 CTCATCACCA AGCTCGTGCA AGTCCAGGCG GACGGCGAGC AGTTGACGCG

94751 GCAGGAACTC GTCTCCTTCT TCATCCTGCT CGTCATCGCC GGGATGGAGA

94801 CCACCCGCAA CGCCATCTCG CACGCGCTGG TACTGCTGAC CGAGCATCCC

94851 GAGCAGAAGC AGCTGCTGCT CTCGGACTTC GACACGCACG CGCCGAACGC

94901 GGTCGAGGAG ATCCTCAGGG TCTCCACGCC CATCAACTGG ATGCGGCGCG

94951 TCGCCACCCG CGACTGCGAC ATGAACGGCC ACAGGTTCCG CAGGGGCGAC

95001 CGGATCTTCC TGTTCTACTG GTCGGGCAAC CGGGACGAAT CCGTCTTCCC

95051 TGACCCGTAC CGGTTCGACA TCACGCGCGG GACGAACGCG CACGTCACGT

95101 TCGGCGCGGT GGGCCCGCAC GTCTGCCTCG GGGCCCACCT CGCCCGTATG

95151 GAGATCACCG TCCTGTACCG GGAGCTGCTC GCGGCGCTGC CCCAGATCCA

95201 TGCCGTGGGG CAGCCCCGCA GGCTGGACTC CAGCTTCATC GAAGGGATCA

95251 AGCACCTGCA CTGCGCCTTC TGAGCACATA CGCTTCCCTC TGCGCATGTG

95301 CGCTCACGAC GCTCCGATCA GCGACTGCCA ACGACTGTCA GCGACCGGAC

95351 AGGGCCAAGG GCGGTGGGGA CATCAGGTGC ATGTCACCCG CGAGTATGGC

95401 CCGCTGCAGC TCCTGGAGCG GGCGCCCGGG TTCGAGCCCC AGCTCGTCGT

95451 TGAGCGTCTT GCGCACCGAC TGGTACACCT TCAGCGCGTC CGCCTGCCGC

95501 TCGGAGCGGT AGAGCGCCAG CATCAGCTGG CGGTAGAACG CCTCGCACAT

95551 CGGGTTCTCC GCGGTGAGGG CGTACAGCAT GCCCACGGCC TCGCGGTGCC

95601 GGCCGAGCTG GAGCTGGCAC TCGACGAGCA TCTCCTGACA CTCCAGGCGG

95651 ATCTCGGTCA GCCAGGTCGA GAAGCCGTCG ATGATCGGGC CGTTGGTGCC

95701 GGGACCGTTC CCGCCCTGCC CGAGGATCGG GCCGCGCCAC AGCGCGAGCG

95751 CCTGCCCGAA ACAGGAGGCC GCCTCGTCGA ACCGCTTCTC CCTGAGCAAC

95801 GACCGCCCCA CGTCCACCAG TTCGGGGAAG ATCTGGGCAT CGATCTGGTC

95851 GTCGTCCCGC TTGTGCAGGA CGTACCCCGG CGCACGGGTC TCGACGGGGT

95901 TGCCCGCCGA ACCGGGCACC TTGAGGAACT TGCGGAGCTG GGAGATGTAC

95951 ACATGCAGTC CCGCCGTGGC GCGCCGCGGC AGGTCCTCGC CCCAGATCTC

96001 CCGCATCAGC TGCTCCAGGG AGACCACCCG GTCGGCGCGG ATGAGGAGCA

96051 CGGTGAGGAC GATCTCCACC TTCTGGGCGT TGATGGTGGC GTAGTCGTTT

96101 CCGTCCTTGA TGCGGAGCGG GCCCAGCATT TCGTATCTCA CCGAGCGTTC

96151 CCCCTTGCTG TCGCACGCTG CTGCGCACTG TCGGCCAGGG CCTTGGAGAT

96201 GACTTCCGTG ACGCCCTGCT GGTGCGTGTT CAGATAGAAG TGGCCCCCGG

96251 CGAAGACCTT GAGGTCGAAG GGGCCTTCCG TGTGCTGCTG CCAGGCCTCG

96301 ACCTCGTCCA GCGGCGCCTG CGGGTCCCGG TCGCCCACCA GGGCGGTGAT

96351 GGGGCAGGAC AGCGGCGGCG ACGGGTTCCA CCGGTACAGC TCGACCGCCC

96401 GGTAGTCGTT GCGGACGACC GGGATGATCT CCGCGAGCAG TTCCTCGTCG

96451 TCCAGGAACC GCGGGTCAGT GCCACCGGCC CGGCGCAGCT CGGCGGCCAA

96501 CTCGGTGTCG TCGAGGAGGT GTACGGTGCC GCGCCGGAAG CGGGACGGCG

96551 CGCGGCGTCC CGAGACGAAC AGCCGGCAGG GCTGCTTCCC CGTGCGCTCG

96601 CGGAGCCGCT GGGCGACTTC GTAGGCGAGG ACGGCGCCCA TGCTGTGGCC

96651 GAAGAACGCC AACGGGCGGT CGTCGAACGG GCCGAGCGCA TCGGTGATGA

96701 GGTCGGCGAG TTCCCCGATG TCGTCCAGGA GCCGCTCTCT GCGGCGGTCC

96751 TGTCGCCCGG GGTACTGCAC CGCGAGGACC TCGCTGTCGG TCGGGAGAGT

96801 GGGGGATTGC GCAAGGGGGT GGTAGTAGGA GGCCGAGCCG CCCGCGTGGG

96851 GGAAGCAGAC CAGGCGAACG ACGGCTTCCG GTCGGGGCCG GAAGCGACGT

96901 ATCCAAGGGT CCGACATATC GGGTGGGGGG AAGGCAGACA AGATCTTTCC

96951 CTTCGCCAGG AACGCTGACA ACGGTGTGTC GCCACATCAC ATAGCCGCTC

97001 CTGATCATGC GCAGCTCAAA GTTTAAACGG CAACGTCGCT AACGGGGGAG

97051 CAGGGCGGAA TCAGACATTC CCCATCCTTT ATTCCGCGAT TCTTACGTGA

97101 TCGAATCCCG GCGGCCAAGA TGGAGTAAAT TTCAATATGA ATGCTTAACG

97151 CCGCACAGCT TGTACGGCGG GCCGCCCGGG CGGTGACTGG CGTCCCTGCC

97201 AGCCGTGATG GCCTGACGAG GCCTCCGGGA TCCATCCCCC GCCCGCTGTC

97251 GCCGAGTTCT TTGCGGGATT ATTACGTTGC ATTGGTTTGC TTCGTGGCCC

97301 GGGCCGTTGG CCTGCGCTAT TTGGCAGCCT TCCGTCATGG GTGGTAAAAG

97351 ATCGCCTTTC CCCTCTGGGG TGCCGGTCGA GCTGGCCTCG ACCGCGATTG

97401 TGGCTTGTTG TTTTCTTGTG GCGCCGCGTG TGAAACAGCG GCAGTTGGCC

97451 ACTCGCTCTG ACAGGCTCCG GGGACGGGGT TGTCACCTTT TGGGGTGACT

97501 GGCCTCGTTC AAGGCGTCCT GGCCCGTGGT GCATCCGCGA TCGTCGTGCC

97551 ATGGGTGAAG TGGGAAGGAG CACAGAACGA TGAGCGAGAG CATGGCGTGG

97601 CTGACGCGGG ACGTCCGCAA GGCCCGCAAG GAGGGCAGTG CGGGGACCGC

97651 GCGGCGCCGA GCCGACCGGC TGGCGGACCT GGTCGCCCAC GCCCGCTCGG

97701 CGTCGCCGTA CTACCGGGAG CTCTACCACG GCCTGCCCGA GCGGATCGAG

97751 GACCCGACGC TGCTGCCGGT GACGGACAAG AAGCAGCTGA TGGACCACTT

97801 CGACGACTGG CCGACGGACC GCGACATCAC CTTCGAGAAG GTCCGCGCGT

97851 TCACCGACGA CCCCGAGCTG ATCGGGCGGC GCTTCCTCGG CCGCTATCTG

97901 GTGGCCACCA CGTCGGGCAC CAGCGGCAGG CGCGGCCTGT TCGTGCTCGA

97951 CGACCGGTAC ATGAACGTGT CCTCCGCCGT CTCCTCCCGG GTGCTCGCCT

98001 CCTGGCTCGG CCCCCTCGGC ATCGCCCGGG CCGTCGTCCA CGGCGGCCGC

98051 TTCGCCCAAC TCGTCGCCAC CGAGGGACAT TACGTCGGCT TCGCCGGATA

98101 CTCCCGCCTG CGCCAGGACG GCGGAGCGCG CAGCAAGCTC GTCCGCGCCT

98151 TCTCTGTGCA CGAGCCGATG TCACGTCTGG TCGCCGAACT CAACGAGTAC

98201 CGGCCCGCGT TCGTCATCGG CTACGCCAGT ACGATCATGC TGCTCACCGC

98251 CGAACAGGAA GCGGGCCGGC TGCACATCGA CCCGGTGCTG GTCGAGCCCG

98301 CGGGCGAGAC GATGACCGAG AGCGACACCG ACCGCATCGC TGCGGCGTTC

98351 GGCGCCAAGG TGCGCACGAT GTACAGCGCG ACCGAGTGCA CCTACCTCAG

98401 CCACGGCTGC GCCGAGGGCT GGTACCACGT CAACGACGAC TGGGCCGTGC

98451 TCGAACCGGT CGACGCCGAC CACCGGCCCA CCCCGCCGGG GGAGTTCTCG

98501 CACACCACCC TGATCAGCAA CCTCGCCAAC CGCGTCCAGC CGTTCCTCCG

98551 CTACGACCTG GGCGACAGCG TCATGCTCCG CCCCGACCCC TGCCCCTGCG

98601 GCACCCCCTC GCCCGCGATC CGGGTCCAGG GCAGGTCGGG CGACATCCTC

98651 ACCTTCCCCT CGGGCCGGGG CGACGACGTC AGCCTCGCCC CGCTCGCCTT

98701 CAGCAGCCTC TTCGACCGCA TGCCCGGAGT CGAGCTCTTC CAGATCGAGC

98751 AGACCGCGCC GTCGACCCTG CGCGTCCGCG TGGTCCAGGC GCCCGGCGCC

98801 GACGCGGACC ACGTGTGGCA GCGGGCCCAC GACGGGCTGA CCCACCTCCT

98851 CGCCGACAAC AAGCTCGACA ACGTAACCGT CGAACGGGGC GAGGAGCCGC

98901 CGCGGCAGGC ATCCGGCGGC AAGTACCGGA CGATCATCCC GCTCGCCGCC

98951 TGAACGCTCG CCGACTAGCC GCGCGCCGCC TGAGCTGCTC TCACCGCGCG

99001 TACGGGCGCA GCGGAGGCTC CTCGTCGACC CACGGCTGGC TGTGGATCAG

99051 CAGCTCGATC GGGAAGTTCA GCAGGCCGGG CAGGGCGTCG ACGGCCTCCT

99101 GGCTGTTGAG CGGCATGACC GGCTTGGCGC AGTGCGCGCG GTCGATGCGG

99151 CTCGTGTCGG CGGGACCGGG GTGCTCGATC GCATCGGCGA CCAGGTCGTA

99201 GCTGACCTGG TCGACGACCA TGGCGATGTG GGTCGGCCAC GGCCGACCCG

99251 GACAGATGTC CTGGACGCCG ATGCGGTGGG CGCCCGGCAG CGACGGCGCC

99301 TCCCCGTCGG CCACCACGGA CTCGTCGGCG TATGAATAGA TCGTGGTGTA

99351 CGACGGTCCT GCGGGCATGG GCGTGCCGTC GGCGCCCAGA GCCTTCGACC

99401 AGTTCGAGTC GCGGGCGAAC TGCAGGACCG ACGCCGGGCA GCCCGCCACC

99451 TCGGCGATCG GGCGGCAGGG CGAGGCCAGC CGGGTCCCCT GGAACGGGGA

99501 GCCCAGGGTC ACCATGTCGT CGACCTTCCC CGGCAGGTCC GGCCAGAAGC

99551 GCAGGGCCCA CGCCGTGAGG AGGCCGCCCT GGCTGTGCCC GACGAGATCG

99601 ACCTTCCGGC CGGTGGCCTC CTGGATCGCG CGGGTCGCGT ACACCACGTA

99651 CTCGACGGAC TCCTGCATGT CACGGAGCCC GCGACCGGGA GAATCCACCC

99701 AACAGGACTG GTAGCCCTTC TTCTTCAACT CGGCCATGTA GTTCCAGGCG

99751 TAGTTCTCCT CGCCCTTGAG GCCGGTCCCG GGCACGAAGA GGACGGTCGG

99801 CTTGTCACCG GCGTCACGCA GGTCCCCCAG CTCCGTCCCG CAGTGCAGCG

99851 CCTTGGCGAG CTCGGCCGCC GGTATCTCCA ACGGGGGAGA GGAAACATCC

99901 GCCGCCGAAG CGGCGGAGGC CGGAAGCACG GTGGCGGCCA GCACGGCCGC

99951 CACGAGTCCG CCGAGCCATG AGGACAAGCG CACGGTGACC TCCACAGGAA

100001 CCTTCACGAG TGAGCGGAAA CTCCCTCCGG AGGGAGCACC TCATCGTGCG

100051 GCGGCGCCAC AGTAGCCGTC AACTGCCCCA CGGGGCTGAG TAGTTGACAG

100101 TTGGCCGGGC TCGGCCGGCG AAGCGCCCGG GCCCCGCCGC CCCGCGCCGT

100151 GCGCGAGGGG TCCGTGACCT GGGTGGACGG TCCGGTTGGA CATCCCGGGG

100201 GAGCCTCTGG CATGGTCGCC CGTCCGTCCC CCTCAAGAAC CGAAGGGAGC

100251 GTCACGATCA CGATGATCGA AGTCAGCACG CGCAGCATGA AGGAAGCGGC

100301 TGCCGCCGAG CAGCTCCGCG CGGAGACCAC GACACTGGAC ATTCCAAAGG

100351 GTTTCGACCT GTGGACGGCC GACGAGATCG CGGAGTGGCT CGACGGCGTC

100401 GAGGACGACC CGGCAGTCTC CGACGCCGAC TTCTACGCGG CCCAGCAGCG

100451 GTGCGACGGG TCCTCGGCAC CGAGGGCACC TGACCCGCCG GCGGCCCTGC

100501 GCGGCCCTAC GTGTGCAGCG CCCCGTCCTC CTCCACATGC CCCTCCGGCT

100551 CCAGCTGGAT CGTCGAGTGG GCCACGTCGA AGTGGCCCCC GACACACCGC

100601 TGAAGGCGCC CCAGGAGCTC CCCGTACCCG CTCGCGAGAG CCTCCTCCGT

100651 GACCACCACG TGCGCGGTGA GCACCGGCAT CCCCGAGGTG ACCGTCCAGC

100701 CGTGCAGATC GTGCACGGCG ACCACGCCCC GCTCCTCCAG CAGGTGCCGG

100751 CGCACCTCGC CGAGGTCGAC GTCCTGCGGG GTCGCCTCCA GCAGGACGTG

100801 CAAGGAGTCC CGCAGCAGGC CGTACGCGCG CGGCACGATC AGCAGGCCGA

100851 TGACGATCGA CGCGATCGGG TCGGCGGCCT GCCACCCCGT GAGCAGGATG

100901 ACCAGGCCGC CCACGATCAC CGCGACCGAG CCGAGCGCGT CGCCCAGCAC

100951 CTCCAGGTAC GCGCCCCGCA GATTGAGGCT CTTCTCCTTG GCGTCCCGCA

101001 GCAGCCACAG GCCCACCAGG TTGGCGGCGA GCCCGCCCAG CGCGACCACG

101051 AACATCAGGC CGCCCTTCAC CTCCACCGGC TCGCTGAACC GGCCGATCGC

101101 CGACCACAGG ACCCAGGCGA AGATGACGAC CAGGAGCAGC GCGTTCAGGA

101151 CCGCGGAGAA GATCTCCACG CGGTAGAACC CAAAGGTGCG CCGCGGCGTC

101201 GGCGCCCGCT GGGCGAGGGT GATGGCACCG AGGGCCAGCG AGACGCCGAC

101251 CGCGTCGGTC AGGCTGTGGG CGGCGTCGGC GAGCAGCGCG AGGCTGCCGG

101301 ACAGGAGCGC GCCGACCACC TGGATGACGG TGATCGAGCC GCTGATGCCG

101351 ATGGTCCACA GCAGGCGCTT GCGGTACGTG CCGCTGAGAG TGCCGCCCGC

101401 CGCCCCGGCG GACGGACCGT GGTCGTGCCC CATGCCCGCG AGTGGACCAC

101451 GGCGGCGCGG CACCCGCCAC CGAGCGGCCG CCGGTCGGCT CAGTGCAGCC

101501 GGGCCTGGGT GGAGGTGTCG CGCTGGTGCG GGATGCCGAG CGGCGGCGGC

101551 AGCTCGCCCT GCTGCACCCT GACCGTGCGC ACGGGGGCGG GGACCCGGAT

101601 GCCCTCGGCG CGGTAACGCT GGTGCAGGCG CTTGATGAAC TCGTGCTTGA

101651 TGCGGTACTG GTCGCTGAAC TCGCCGACGC CGAGGATCAC CGTGAAGCTG

101701 ATCCGCGAGT CGCCGAAGGT GTGGAAGCGG ATCGCCGCCT CGTGGTCGGG

101751 GACCGCGCCG GTGATCTCGG CCATCACCTC GTCCACCACC TCGGTCGTGA

101801 CCTTCTCGAC CTGCTCCAGG TCGCTGTCGT AGCTGACCCC GACCTGCACC

101851 ATGATCGACA GCTCCTGCTC GGGGCGGCTG TAGTTGGTCA TGTTGGTGCC

101901 GGCGAGCTTC GCGTTGGGGA TGATGACGAG GTTGTTGGAG AGCTGGCGGA

101951 CCGTGGTGTT GCGCCAGTTG ATGTCGACGA CGTAGCCCTC CTCCCCGCTG

102001 CTGAGCTGGA TGTAGTCGCC GGGCTGCACG GTCTTCGCGG CGAGGATGTG

102051 CACGCCCGCG AAGAGATTGG CGAGCGTGTC CTGCAGTGCG AGGGCGACCG

102101 CGAGACCTCC CACGCCGAGG GCGGTGAGCA GCGGTGCGAT GGAGATGCCG

102151 AGGGTCTGAA GGACGATGAG GAAGCCCATC GCGAGCACCA CGACGCGGGT

102201 GATGTTCACG AAGATGGTGG CCGATCCGGC CACTCCGGAG CGGGACTGTG

102251 CCACGGCCTT CACCAGGCCG GTGACGATCC GGGCCGCCGT GAGCGTGGCG

102301 GCCAGGATGA GCAGCGCGGT CAGCGTCATG GTGACGTTGC GTCCGGTGCG

102351 CGGCGTGAGC GGCAGCGCGC CCGCCGCGGC GGCGAGCCCG GCGGTGATGG

102401 CCGCGCAGGG CACGAGGGTG CGCAGGGCGT CGACGATGAC GTCGTCACCG

102451 CTCCACCGGG TTTTGCTCGC CCGTTCGCCG AGCCACCTCA GAAGTGCGCG

102501 GAGCAGCAGC CCGGCGACGA CGCCGGCGAC GACCGCGATA CCGGCCACGA

102551 TCCAGTCGTG CAGTGTGAGG GCACGGGTCA TCAGTTCGCT CCCGTCGTAC

102601 GGGGGGAGTG CGCCTGTGTG GGGCGTATGT GATGTGACGT CACCTTGTGA

102651 TACCTGCTCG ATTCCGGGGA GTGCGGTCAC GCCGGGACGA GAGCTCGGTT

102701 CCGGCGCGGA CGTCATCCTG CCCCATCCGC CCACGGCAGG CGTGCATACC

102751 CCCACCTGGA TCTTCACAGA CCGGCCACGT CTGTCCATGC GCCGATGAGC

102801 GCGCTGCCCG TGGTAAAGCA TTGAGTCAGG CGATTTGGCC ACTCGGCACT

102851 CGGCGGACCG GTCGAGCCGG TCGATCTACG TGAGCGGAGG CGGTTGAGCA

102901 TGGCGTCCAT GTGCAGACCC GGAATGTCAC CCGTCAATTC GCACAACGAG

102951 TGGGATCCGC TGGAGGAGAT CATCGTCGGG CGGCTGGAGG GCGCGACCAT

103001 TCCCTCCAGC CATCCGGTCG TGGCGTGCAA CATCCCGACC TGGGCGGCAC

103051 GGCTGCAGGG TCTCGCCGCC GGGTTCGAGT ATCCGCAGCG GCTGATCGAG

103101 CCGGCGCAGC AGGAGCTCGA CCAGTTCATC GCTCTCCTGC AATCCCTCGA

103151 CGTCACAGTG AGACGGCCGG CGGCCGTCGA CCACAAGCAC CGCTTCGGGA

103201 CCCCCGACTG GCAGTCGCGC GGCTTCTGCA ATTCCTGTCC GCGGGACAGC

103251 ATGCTCGTCG TCGGCGACGA GATCATCGAG ACCCCGATGG CGTGGCCGTG

103301 CCGCTGTTTC GAGACGCACT CGTACCGCGA ACTCCTCAAG GACTACTTCC

103351 GGCGCGGCGC GCGCTGGACG GCGGCGCCGC GCCCCCAGCT CACCGAGGCC

103401 CTGTACGAGA AGGACTTCCG CCCTCCCGAG GAGGGCGAAC GATGCGCTAC

103451 ATCCTCACCG AGTTCGAGCC GGTGTTCGAC GCGGCGGATT TCGTGCGGGC

103501 GGGCCGCGAC CTGTTCGTGA CGCGGAGCAA CGTCGCCAAC CTGCTGGGCA

103551 TCGAGTGGCT GCGCCGCCAC CTTCGGGCCG GAGTACCGCG TGCCACGAGA

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Professor P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

INTERNATIONAL FORM

RECEIPT IN THE CASE OF AN ORIGINAL DEPOSIT
***issued pursuant to* Rule 7.1 by the**
INTERNATIONAL DEPOSITARY AUTHORITY
identified at the bottom of this page

NAME AND ADDRESS OF DEPOSITOR

I. IDENTIFICATION OF THE MICROORGANISM

Identification reference given by the DEPOSITOR:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY:
Escherichia coli XL1-Blue MR (MO-CN11)	NCIMB 40956

II. SCIENTIFIC DESCRIPTION AND/OR PROPOSED TAXONOMIC DESIGNATION

The microorganism identified under I above was accompanied by:

☐ a scientific description

☒ a proposed taxonomic designation

(Mark with a cross where applicable)

III. RECEIPT AND ACCEPTANCE

This International Depositary Authority accepts the microorganism identified under I above, which was received by it on 1 July 1998 (date of the original deposit)[1]

IV. RECEIPT OF REQUEST FOR CONVERSION

The microorganism identified under I above was received by this International Depositary Authority on (date of the original deposit) and a request to convert the original deposit to a deposit under the Budapest Treaty was received by it on (date of receipt of request for conversion)

V. INTERNATIONAL DEPOSITARY AUTHORITY

Name: NCIMB Ltd.,

Address: 23 St Machar Drive,
Aberdeen,
AB24 3RY,
Scotland.

Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s):

Date: 9 July 1998

1 Where Rule 6/4(d) applies, such date is the date on which the status of International Depositary Authority was acquired.

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Professor P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

INTERNATIONAL FORM

RECEIPT IN THE CASE OF AN ORIGINAL DEPOSIT
***issued pursuant to* Rule 7.1 by the**
INTERNATIONAL DEPOSITARY AUTHORITY
identified at the bottom of this page

NAME AND ADDRESS OF DEPOSITOR

I. IDENTIFICATION OF THE MICROORGANISM

Identification reference given by the DEPOSITOR:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY:
Escherichia coli XL1-Blue MR (MO-CN33)	NCIMB 40957

II. *SCIENTIFIC DESCRIPTION AND/OR PROPOSED TAXONOMIC DESIGNATION*

The microorganism identified under I above was accompanied by:

☐ a scientific description

☒ a proposed taxonomic designation

(Mark with a cross where applicable)

III. RECEIPT AND ACCEPTANCE

This International Depositary Authority accepts the microorganism identified under I above, which was received by it on
1 July 1998 (date of the original deposit)[1]

IV. RECEIPT OF REQUEST FOR CONVERSION

The microorganism identified under I above was received by this International Depositary Authority on
(date of the original deposit) and a request to convert the original deposit to a deposit under the Budapest Treaty was received by it on
(date of receipt of request for conversion)

V. INTERNATIONAL DEPOSITARY AUTHORITY

Name: NCIMB Ltd.,

Address: 23 St Machar Drive,
Aberdeen,
AB24 3RY,
Scotland.

Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s):

Date: 9 July 1998

1 Where Rule 6/4(d) applies, such date is the date on which the status of International Depositary Authority was acquired.

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Professor P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

INTERNATIONAL FORM

RECEIPT IN THE CASE OF AN ORIGINAL DEPOSIT
issued pursuant to Rule 7.1 by the
INTERNATIONAL DEPOSITARY AUTHORITY
identified at the bottom of this page

NAME AND ADDRESS OF DEPOSITOR

I. IDENTIFICATION OF THE MICROORGANISM

Identification reference given by the DEPOSITOR:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY:
Escherichia coli XL1-Blue MR (MO-CN02)	NCIMB 40958

II. SCIENTIFIC DESCRIPTION AND/OR PROPOSED TAXONOMIC DESIGNATION

The microorganism identified under I above was accompanied by:

☐ a scientific description

☒ a proposed taxonomic designation

(Mark with a cross where applicable)

III. RECEIPT AND ACCEPTANCE

This International Depositary Authority accepts the microorganism identified under I above, which was received by it on 1 July 1998 (date of the original deposit)[1]

IV. RECEIPT OF REQUEST FOR CONVERSION

The microorganism identified under I above was received by this International Depositary Authority on (date of the original deposit) and a request to convert the original deposit to a deposit under the Budapest Treaty was received by it on (date of receipt of request for conversion)

V. INTERNATIONAL DEPOSITARY AUTHORITY

Name: NCIMB Ltd.,

Address: 23 St Machar Drive,
Aberdeen,
AB24 3RY,
Scotland.

Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s):

Date: 9 July 1998

1 Where Rule 6/4(d) applies, such date is the date on which the status of International Depositary Authority was acquired.

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Dr. P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

NAME AND ADDRESS OF THE PARTY TO WHOM THE VIABILITY STATEMENT IS ISSUED

INTERNATIONAL FORM

VIABILITY STATEMENT
issued pursuant to Rule 10.2 by the
INTERNATIONAL DEPOSITARY AUTHORITY
identified on the following page

I. DEPOSITOR	II. IDENTIFICATION OF THE MICROORGANISM
Name: AS ABOVE Address:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY: NCIMB 40956 Date of the deposit or of the transfer[1]: 1 July 1998

III. VIABILITY STATEMENT

The viability of the microorganism identified under II above was tested on 1 July 1998 2. On that date, the said microorganism was:

[3] [X] viable

[3] [] no longer viable

1 Indicate the date of the original deposit or, where a new deposit or a transfer has been made, the most recent relevant date (date of the new deposit or date of the transfer).

2 In the cases referred to in Rule 10.2(a)(ii) and (iii), refer to the most recent viability test.

3 Mark with a cross the applicable box.

IV. NDITIONS UNDER WHICH THE VIABILITY TEST HAS BEEN PERFORMED[4]
V. INTERNATIONAL DEPOSITARY AUTHORITY
Name: NCIMB Ltd., Address: 23 St Machar Drive, Aberdeen, A24 3RY, Scotland. Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s): Date: 9 July 1998

4 Fill in if the information has been requested and if the results of the test were negative.

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Dr. P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

NAME AND ADDRESS OF THE PARTY TO WHOM THE VIABILITY STATEMENT IS ISSUED

INTERNATIONAL FORM

VIABILITY STATEMENT
issued pursuant to Rule 10.2 by the INTERNATIONAL DEPOSITARY AUTHORITY identified on the following page

I. DEPOSITOR	II. IDENTIFICATION OF THE MICROORGANISM
Name: AS ABOVE Address:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY: NCIMB 40957 Date of the deposit or of the transfer[1]: 1 July 1998

III. VIABILITY STATEMENT

The viability of the microorganism identified under II above was tested on 1 July 1998 [2]. On that date, the said microorganism was:

[3] [X] viable

[3] [] no longer viable

1 Indicate the date of the original deposit or, where a new deposit or a transfer has been made, the most recent relevant date (date of the new deposit or date of the transfer).

2 In the cases referred to in Rule 10.2(a)(ii) and (iii), refer to the most recent viability test.

3 Mark with a cross the applicable box.

IV. NDITIONS UNDER WHICH THE VIABILITY TEST HAS BEEN PERFORMED[4]
V. INTERNATIONAL DEPOSITARY AUTHORITY
Name: NCIMB Ltd., Address: 23 St Machar Drive, Aberdeen, A24 3RY, Scotland. Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s): Date: 9 July 1998

4 Fill in if the information has been requested and if the results of the test were negative.

BUDAPEST TREATY ON THE INTERNATIONAL RECOGNITION OF THE DEPOSIT OF MICROORGANISMS FOR THE PURPOSES OF PATENT PROCEDURE

Dr. P.F. Leadlay,
Department of Biochemistry,
University of Cambridge,
80 Tennis Court Road,
Cambridge.
CB2 1GA

NAME AND ADDRESS OF THE PARTY TO WHOM THE VIABILITY STATEMENT IS ISSUED

INTERNATIONAL FORM

VIABILITY STATEMENT
issued pursuant to Rule 10.2 by the INTERNATIONAL DEPOSITARY AUTHORITY identified on the following page

I. DEPOSITOR	II. IDENTIFICATION OF THE MICROORGANISM
Name: AS ABOVE Address:	Accession number given by the INTERNATIONAL DEPOSITARY AUTHORITY: NCIMB 40958 Date of the deposit or of the transfer[1]: 1 July 1998

III. VIABILITY STATEMENT

The viability of the microorganism identified under II above was tested on 1 July 1998 2. On that date, the said microorganism was:

3
[X] viable
3
[] no longer viable

1 Indicate the date of the original deposit or, where a new deposit or a transfer has been made, the most recent relevant date (date of the new deposit or date of the transfer).

2 In the cases referred to in Rule 10.2(a)(ii) and (iii), refer to the most recent viability test.

3 Mark with a cross the applicable box.

IV. NDITIONS UNDER WHICH THE VIABILITY TEST HAS BEEN PERFORMED[4]
V. INTERNATIONAL DEPOSITARY AUTHORITY
Name: NCIMB Ltd., Address: 23 St Machar Drive, Aberdeen, A24 3RY, Scotland. Signature(s) of person(s) having the power to represent the International Depositary Authority or of authorised official(s): Date: 9 July 1998

4 Fill in if the information has been requested and if the results of the test were negative.

INTERNATIONAL SEARCH REPORT

Interi ıal Application No
PCT/GB 00/02072

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 C12N15/52 C12N15/76 C12P17/18 C12P19/44 C12P19/62
C12Q1/68 C07H17/08 C07H19/01

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 C12N C12P C12Q C07H

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)
EPO-Internal, MEDLINE, STRAND, EMBL, BIOSIS, EMBASE, WPI Data, PAJ, CHEM ABS Data

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	DONOVAN M J ET AL.: "Isolation of DNA involved in monensin biosynthesis by Streptomyces cinnamonensis;" ABSTR. ANNU. MEET. AM. SOC. MICROBIOL. 88 MEET., 1988, page 261 XP000949887	1-3,6-14
Y	abstract	30-38

X	ARROWSMITH T J ET AL.: "Characterisation of actI-homologous DNA encoding polyketide synthase genes from the monensin producer Streptomyces cinnamonensis." MOLECULAR AND GENERAL GENETICS, vol. 234, no. 2, August 1992 (1992-08), pages 254-264, XP002149754	1-3,6-14
Y	page 263, right-hand column, line 1-5	30-38

	-/--	

[X] Further documents are listed in the continuation of box C.

[X] Patent family members are listed in annex.

° Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
16 October 2000	08. 01. 2001

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	van de Kamp, M

Form PCT/ISA/210 (second sheet) (July 1992)

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	MALPARTIDA F ET AL: "Homology between Streptomyces genes coding for synthesis of different polyketides used to clone antibiotic biosynthetic genes" NATURE, vol. 325, no. 6107, 26 February 1987 (1987-02-26), pages 818-821, XP002075972	1-3,6-14
Y	abstract page 819, left-hand column, line 16 -right-hand column, line 1; figure 1 ---	30-38
X	ASHWORTH D M ET AL.: "Selection of a specifically blocked mutant of Streptomyces cinnamonensis: isolation and synthesis of 26-deoxymonensin A." THE JOURNAL OF ANTIBIOTICS, vol. 42, no. 7, July 1989 (1989-07), pages 1088-1099, XP002149776 cited in the application	1-3, 6-14,36
Y	abstract page 1088, line 10-15 scheme 1,2 ---	30-38
X	WO 98 49315 A (KOSAN BIOSCIENCES INC ;UNIV LELAND STANFORD JUNIOR (US)) 5 November 1998 (1998-11-05)	36,45
Y	figure 6G compound #102 example 6 claims 1-10 ---	30-38
X	HOPWOOD D A: "Genetic contributions to understanding polyketide synthases" CHEMICAL REVIEWS, vol. 97, no. 7, November 1997 (1997-11), pages 2465-2497, XP002130647 figures 3,13 table 1 page 2486, paragraph C ---	36
Y	WO 98 01546 A (CORTES JESUS ;LEADLAY PETER F (GB); STAUNTON JAMES (GB); BIOTICA T) 15 January 1998 (1998-01-15) cited in the application page 5, line 12 -page 10, line 11 claims 1-6 --- -/--	30-38

INTERNATIONAL SEARCH REPORT

Intern al Application No
PCT/GB 00/02072

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	ZERBE-BURKHARDT K ET AL.: "Cloning, sequencing, expression, and insertional inactivation of the gene for the large subunit of the coenzyme B12-dependent isobutyryl-CoA mutase from Streptomyces cinnamonensis." JOURNAL OF BIOLOGICAL CHEMISTRY, vol. 273, no. 11, 13 March 1998 (1998-03-13), pages 6508-6517, XP002149755 abstract	
A	ROWE C J ET AL: "Construction of new vectors for high-level expression in actinomycetes" GENE, vol. 216, no. 1, August 1998 (1998-08), pages 215-223, XP004149299 cited in the application abstract	
T	WO 00 00500 A (LEADLAY PETER FRANCIS ;CORTES JESUS (GB); STAUNTON JAMES (GB); BIO) 6 January 2000 (2000-01-06) Note: 100.0 % aa seq identity of SEQ ID NO:23 with SEQ ID NO:19 in 920 aa overlap. page 14, line 15-17 page 17, line 15-20 page 24, line 16-20 examples 1,3,26 claim 18	1-3, 6-14, 30-38

INTERNATIONAL SEARCH REPORT

.....ational application No.
PCT/GB 00/02072

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:

2. ☐ Claims Nos.:
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:

3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

see additional sheet

1. ☐ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.

2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.

3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:

4. ☒ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

see further information sheet invention 1

Remark on Protest

☐ The additional search fees were accompanied by the applicant's protest.

☐ No protest accompanied the payment of additional search fees.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

This International Searching Authority found multiple (groups of) inventions in this international application, as follows:

1. Claims: 1,8-12,14,43,44 (all partially); 2-7,13,15-42, 45 (all completely)

A DNA sequence comprising the complete monensin (mon) gene cluster, or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with one of the peptides according to SEQ ID NOs 12-33 (AcpX to MonAX as set out in table II), provided that said polypeptide is not all or part of amino acid 1-920 encoded by monAI. Vectors, transformed cells, hybridization probes and their uses.

Use of mon genes to control expression (monRI), to effect chain release (monAIX and monAX), to provide a desired stereochemical outcome (monBI and monBII), or to provide epoxidase or cyclase activity (monCI and monCII). Mon polypeptides having isomerase activity (MonBI and MonBII), or having chain terminating activity (MonAIX or MonAX), or having epoxidase activity (MonCI), or having cyclase activity (MonCII).

Processes for producing polyketides involving monensin loading or extension modules or domains. DNA sequences encoding hybrid polyketide synthases containing one or more monensin modules or domains (provided that it is not encoding an ery loading module, the first and second ery extension modules and the ery chain-terminating thioesterase in which the AT domain of the first ery extension module has been substituted by the ethyl malonyl-CoA AT from the monensin synthase), polyketide synthases encoded by said DNA sequences, and polyketide compounds produced by said polyketide synthases. Vectors and transformed cells.

Methods of producing S. cinnamonensis capable of producing enhanced levels of monensin by overexpressing or amplifying the monRI gene, S. cinnamonensis strains produced thereby, and use of said strains in monensin production.

Process for expressing a heterologous gene, e.g., a PKS gene, in S. cinnamonensis under the control of monRI.

2. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:5 (GdhA as set out in table II), vectors, transformed cells, hybridization probes and their uses.

3. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:6 (DapA as set out in table II), vectors, transformed cells, hybridization probes and their uses.

4. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:7 (Orf3 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

5. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:8 (Orf4 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

6. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:9 (Orf5 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

7. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:10 (Orf6 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

8. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:11 (Orf7 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

9. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:34 (Orf29 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

10. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:35 (LipB as set out in table II), vectors, transformed cells, hybridization probes and their uses.

11. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:36 (Orf31 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

12. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:37 (Orf32 as set out in table II), vectors, transformed cells, hybridization probes and their uses.

13. Claims: 1,8-12,14 (all partially)

A DNA sequence or a part or a variant of it which encodes a polypeptide (or part of it) which is at least 80%, preferably at least 90% identical with a peptide according to SEQ ID NO:38 (AmtA as set out in table II), vectors, transformed cells, hybridization probes and their uses.

14. Claims: 43,44 (both partially)

Process for expressing a heterologous gene, e.g., a PKS gene, in S. cinnamonensis under the control of actII/orf4.

INTERNATIONAL SEARCH REPORT

Information on patent family members

Inter al Application No
PCT/GB 00/02072

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 9849315 A	05-11-1998	AU 7172298 A	24-11-1998
		EP 0979286 A	16-02-2000
		US 6117659 A	12-09-2000
WO 9801546 A	15-01-1998	AU 3450997 A	02-02-1998
		AU 3451497 A	02-02-1998
		BG 103133 A	28-04-2000
		BR 9710209 A	11-01-2000
		CA 2259420 A	15-01-1998
		CA 2259463 A	15-01-1998
		CN 1229438 A	22-09-1999
		EP 0909327 A	21-04-1999
		EP 0910633 A	28-04-1999
		WO 9801571 A	15-01-1998
		GB 2331518 A	26-05-1999
		NO 990012 A	23-02-1999
		PL 331285 A	05-07-1999
		SK 182498 A	16-05-2000
		AU 7666198 A	30-12-1998
		EP 0983348 A	08-03-2000
		WO 9854308 A	03-12-1998
WO 0000500 A	06-01-2000	AU 4524599 A	17-01-2000
		AU 4524799 A	17-01-2000
		WO 0000618 A	06-01-2000

PATENT COOPERATION TREATY

PCT

REC'D 12 JAN 2001
WIPO PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference	**FOR FURTHER ACTION**	see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.
IS/BP5858469		
International application No.	International filing date *(day/month/year)*	(Earliest) Priority Date *(day/month/year)*
PCT/GB 00/ 02072	30/05/2000	28/05/1999
Applicant		
BIOTICA TECHNOLOGY LIMITED et al.		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 9 sheets.

☐ It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**

a. With regard to the **language,** the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

☐ the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing :

☒ contained in the international application in written form.

☐ filed together with the international application in computer readable form.

☐ furnished subsequently to this Authority in written form.

☒ furnished subsequently to this Authority in computer readble form.

☒ the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☒ the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. ☐ **Certain claims were found unsearchable** (See Box I).

3. ☒ **Unity of invention is lacking** (see Box II).

4. With regard to the **title,**

☒ the text is approved as submitted by the applicant.

☐ the text has been established by this Authority to read as follows:

5. With regard to the **abstract,**

☐ the text is approved as submitted by the applicant.

☒ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the **drawings** to be published with the abstract is Figure No. 1

☒ as suggested by the applicant.

☐ because the applicant failed to suggest a figure.

☐ because this figure better characterizes the invention.

☐ None of the figures.

INTERNATIONAL SEARCH REPORT

International application No.
PCT/GB 00/02072

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:

2. ☐ Claims Nos.:
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:

3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

see additional sheet

1. ☐ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.

2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.

3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:

4. ☒ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

see further information sheet invention 1

R mark on Prot st

☐ The additional search fees were accompanied by the applicant's protest.

☐ No protest accompanied the payment of additional search fees.

INTERNATIONAL SEARCH REPORT

[redacted]ional application No.
PCT/GB 00/02072

Box III TEXT OF THE ABSTRACT (Continuati n of item 5 of the first sheet)

abstract:
line 8 is modified as follows:
removal of the word 'novel'.

PATENT COOPERATION TREAT

RECEIVED
28 SEP 2001

PCT

From the INTERNATIONAL BUREAU

To:
STUART, Ian
Mewburn Ellis
York House
23 Kingsway
London WC2B 6HP
ROYAUME-UNI

RECORDS ENT'D
RECORDS SEEN
DIARY ENT'D
RENEWAL ENT'D X
ALREADY ENT'D

NOTICE INFORMING THE APPLICANT OF THE COMMUNICATION OF THE INTERNATIONAL APPLICATION TO THE DESIGNATED OFFICES

(PCT Rule 47.1(c), first sentence)

Date of mailing (day/month/year) 20 September 2001 (20.09.01)	
Applicant's or agent's file reference IS/BP5858469	**IMPORTANT NOTICE**

International application No.	**International filing date** (day/month/year)	**Priority date** (day/month/year)
PCT/GB00/02072	30 May 2000 (30.05.00)	28 May 1999 (28.05.99)

Applicant
BIOTICA TECHNOLOGY LIMITED et al

1. Notice is hereby given that the International Bureau has communicated, as provided in Article 20, the international application to the following designated Offices on the date indicated above as the date of mailing of this Notice:
 KP,KR,US

 In accordance with Rule 47.1(c), third sentence, those Offices will accept the present Notice as conclusive evidence that the communication of the international application has duly taken place on the date of mailing indicated above and no copy of the international application is required to be furnished by the applicant to the designated Office(s).

2. The following designated Offices have waived the requirement for such a communication at this time:
 AE,AG,AL,AM,AP,AT,AU,AZ,BA,BB,BG,BR,BY,CA,CH,CN,CR,CU,CZ,DE,DK,DM,DZ,EA,EE,EP,ES,
 FI,GB,GD,GE,GH,GM,HR,HU,ID,IL,IN,IS,JP,KE,KG,KZ,LC,LK,LR,LS,LT,LU,LV,MA,MD,MG,MK,
 MN,MW,MX,MZ,NO,NZ,OA,PL,PT,RO,RU,SD,SE,SG,SI,SK,SL,TJ,TM,TR,TT,TZ,UA,UG,UZ,VN,YU,

 The communication will be made to those Offices only upon their request. Furthermore, those Offices do not require the applicant to furnish a copy of the international application (Rule 49.1(a-bis)).

3. Enclosed with this Notice is a copy of the international application as published by the International Bureau on
 20 September 2001 (20.09.01) under No. WO 01/68867

REMINDER REGARDING CHAPTER II (Article 31(2)(a) and Rule 54.2)

If the applicant wishes to postpone entry into the national phase until 30 months (or later in some Offices) from the priority date, **a demand for international preliminary examination** must be filed with the competent International Preliminary Examining Authority before the expiration of 19 months from the priority date.

It is the applicant's sole responsibility to monitor the 19-month time limit.

Note that only an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II has the right to file a demand for international preliminary examination.

REMINDER REGARDING ENTRY INTO THE NATIONAL PHASE (Article 22 or 39(1))

If the applicant wishes to proceed with the international application in the **national phase**, he must, within 20 months or 30 months, or later in some Offices, perform the acts referred to therein before each designated or elected Office.

For further important information on the time limits and acts to be performed for entering the national phase, see the Annex to Form PCT/IB/301 (Notification of Receipt of Record Copy) and Volume II of the PCT Applicant's Guide.

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No. (41-22) 740.14.35

Authorized officer
J. Zahra

Telephone No. (41-22) 338.83.38

Record Copy

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty

For receiving Office use only

International Application No. PCT/GB 00 / 02072

International Filing Date 30 MAY 2000 30.05.2000

Name of receiving Office and "PCT International Application" United Kingdom Patent Office PCT International Application

Applicant's or agent's file reference *(if desired) (12 characters maximum)* IS/BP5858469

Box No. I TITLE OF INVENTION POLYKETIDES AND THEIR SYNTHESIS

Box No. II APPLICANT

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

BIOTICA TECHNOLOGY LIMITED
181A HUNTINGDON ROAD
CAMBRIDGE
CB3 0DJ
GB

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State *(that is, country) of nationality:* GB

State *(that is, country) of residence:* GB

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

LEADLAY PETER FRANCIS
17 CLARENDON ROAD
CAMBRIDGE
CB2 2BH
GB

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only *(if this check-box is marked, do not fill in below.)*

State *(that is, country) of nationality:* GB

State *(that is, country) of residence:* GB

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Deleted BO/GB

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

STUART, IAN ~~and others~~
MEWBURN ELLIS
YORK HOUSE
23 KINGSWAY
LONDON WC2B 6HP
GB

Telephone No. 0117 9266411

Facsimile No. +44 20 7240 9339

Teleprinter No.

☐ Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTORS

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

STAUNTON JAMES
29 PORSON ROAD
CAMBRIDGE
CB2 2ET
GB

This person is:

- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(if this check-box is marked, do not fill in below.)*

State *(that is, country) of nationality:* GB

State *(that is, country) of residence:* GB

This person is applicant for the purposes of: ☐ all designated states ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.))*

OLIYNYK MARKO
DEPARTMENT OF BIOCHEMISTRY
CAMBRIDGE UNIVERSITY
TENNIS COURT ROAD
CAMBRIDGE
CB2 1QW
GB

This person is:

- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(if this check-box is marked, do not fill in below.)*

State *(that is, country) of nationality:* UA

State *(that is, country) of residence:* GB

This person is applicant for the purposes of: ☐ all designated states ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.))*

This person is:

- ☐ applicant only
- ☐ applicant and inventor
- ☐ inventor only *(if this check-box is marked, do not fill in below.)*

State *(that is, country) of nationality:*

State *(that is, country) of residence:*

This person is applicant for the purposes of: ☐ all designated states ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.))*

This person is:

- ☐ applicant only
- ☐ applicant and inventor
- ☐ inventor only *(if this check-box is marked, do not fill in below.)*

State *(that is, country) of nationality:*

State *(that is, country) of residence:*

This person is applicant for the purposes of: ☐ all designated states ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

PCT/GB 00/02072

Box No. V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) *(mark the applicable check-boxes; at least one must be marked)*:

Regional Patent

- [X] **AP** — **ARIPO Patent: GH** Ghana, **GM** Gambia, **KE** Kenya, **LS** Lesotho, **MW** Malawi, **SD** Sudan, **SL** Sierra Leone, **SZ** Swaziland, **UG** Uganda, **ZW** Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- [X] **EA** — **Eurasian Patent: AM** Armenia, **AZ** Azerbaijan, **BY** Belarus, **KG** Kyrgyzstan, **KZ** Kazakstan, **MD** Republic of Moldova, **RU** Russian Federation, **TJ** Tajikistan, **TM** Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- [X] **EP** — **European Patent: AT** Austria, **BE** Belgium, **CH and LI** Switzerland and Liechtenstein, **CY** Cyprus, **DE** Germany, **DK** Denmark, **ES** Spain, **FI** Finland, **FR** France, **GB** United Kingdom, **GR** Greece, **IE** Ireland, **IT** Italy, **LU** Luxembourg, **MC** Monaco, **NL** Netherlands, **PT** Portugal, **SE** Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- [X] **OA** — **OAPI Patent: BF** Burkina Faso, **BJ** Benin, **CF** Central African Republic, **CG** Congo, **CI** Côte d'Ivoire, **CM** Cameroon, **GA** Gabon, **GN** Guinea, **GW** Guinea-Bissau, **ML** Mali, **MR** Mauritania, **NE** Niger, **SN** Senegal, **TD** Chad, **TG** Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT *(if other kind of protection or treatment desired, specify on dotted line)*

National Patent *(if other kind of protection desired, specify on dotted line)*:

- [X] **AE** United Arab Emirates
- [X] **AL** Albania.....
- [X] **AM** Armenia.....
- [X] **AT** Austria.....
- [X] **AU** Australia.....
- [X] **AZ** Azerbaijan
- [X] **BA** Bosnia & Herzegovina.....
- [X] **BB** Barbados
- [X] **BG** Bulgaria.....
- [X] **BR** Brazil.....
- [X] **BY** Belarus.....
- [X] **CA** Canada
- [X] **CH and LI** Switzerland and Liechtenstein.....
- [X] **CN** China.....
- [X] **CR** Costa Rica
- [X] **CU** Cuba.....
- [X] **CZ** Czech Republic.....
- [X] **DE** Germany.....
- [X] **DK** Denmark.....
- [X] **DM** Dominica
- [X] **EE** Estonia.....
- [X] **ES** Spain.....
- [X] **FI** Finland.....
- [X] **GB** United Kingdom.
- [X] **GD** Grenada
- [X] **GE** Georgia.....
- [X] **GH** Ghana.....
- [X] **GM** Gambia
- [X] **HR** Croatia.....
- [X] **HU** Hungary
- [X] **ID** Indonesia
- [X] **IL** Israel.....
- [X] **IN** India
- [X] **IS** Iceland
- [X] **JP** Japan.....
- [X] **KE** Kenya.....
- [X] **KG** Kyrgyzstan.....
- [X] **KP** Democratic People's Republic of Korea.....
- [X] **KR** Republic of Korea.....
- [X] **KZ** Kazakstan
- [X] **LC** St Lucia
- [X] **LK** Sri Lanka
- [X] **LR** Liberia.
- [X] **LS** Lesotho.....
- [X] **LT** Lithuania
- [X] **LU** Luxembourg
- [X] **LV** Latvia
- [X] **MA** Morocco
- [X] **MD** Republic of Moldova
- [X] **MG** Madagascar
- [X] **MK** The former Yugoslav Republic of Macedonia.....

- [X] **MN** Mongolia
- [X] **MW** Malawi.....
- [X] **MX** Mexico.....
- [X] **NO** Norway
- [X] **NZ** New Zealand
- [X] **PL** Poland
- [X] **PT** Portugal
- [X] **RO** Romania
- [X] **RU** Russian Federation
- [X] **SD** Sudan
- [X] **SE** Sweden
- [X] **SG** Singapore
- [X] **SI** Slovenia
- [X] **SK** Slovakia
- [X] **SL** Sierra Leone
- [X] **TJ** Tajikistan
- [X] **TM** Turkmenistan
- [X] **TR** Turkey
- [X] **TT** Trinidad and Tobago
- [X] **TZ** Tanzania
- [X] **UA** Ukraine
- [X] **UG** Uganda
- [X] **US** United States of America.....

- [X] **UZ** Uzbekistan
- [X] **VN** Viet Nam
- [X] **YU** Yugoslavia
- [X] **ZA** South Africa
- [X] **ZW** Zimbabwe

Check-boxes reserved for designating States which have become party to the PCT after issuance of this sheet:

- [X] **DZ** Algeria
- [X] **AG** Antigua and Barbuda
- [X] **MZ** Mozambique
- [X] Any other state which is party to the PCT

Delete RO/GB

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. *(Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)*

Supplemental Box ***If the Supplemental Box is not used, this sheet need not be included in the request.***

Use this box in the following cases:

I. If, in any of the Boxes, the space is insufficient to furnish all the information:	***In such case, write "Continuation of Box No. ..." (indicate the number of the Box) and furnish the information in the same manner as required according to the captions of the Box in which the space was insufficient;***
in particular:	
(i) if more than two persons are involved as applicants and/or inventors and no "continuation sheet" is available:	*in such case, write "Continuation of Box III" and indicate for each additional person the same type of information as required in Box No. III. The country of the address indicated in this box is the applicant's state (that is, country) of residence if no state of residence is indicated below;*
(ii) if, in Box No. II or in any of the sub-boxes of Box No. III, the indication "the States indicated in the Supplemental Box" is checked:	*in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the applicant(s) involved and next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is applicant;*
(iii) if, in Box No. II or in any of the sub-boxes of Box No. III, the inventor or the inventor/applicant is not inventor for the purposes of all designated States or for the purposes of the United States of America:	*in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the inventor(s) and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is inventor;*
(iv) if, in addition to the agent(s) indicated in Box No. IV, there are further agents:	*in such case, write "Continuation of Box No. IV" and indicate for each further agent the same type of information as required in Box No. IV;*
(v) if, in Box No. V, the name of any State (or OAPI) is accompanied by the indication "patent of addition," or "certificate of addition," or if, in Box No. V, the name of the United States of America is accompanied by an indication "Continuation" or "Continuation-in-part":	*in such case, write "Continuation of Box No. V" and the name of each State involved (or OAPI), and after the name of each such State (or OAPI), the number of the parent title or parent application and the date of grant of the parent title or filing of the parent application;*
(vi) if, in Box No. VI, there are more than three earlier applications whose priority is claimed:	*in such case, write "Continuation of Box No. VI" and indicate for each additional earlier application the same type of information as required in Box No. VI.*
(vii) if, in Box No. VI, the earlier application is an ARIPO application:	*in such case, write "Continuation of Box No. VI", specify the number of the item corresponding to that earlier application and indicate at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed.*
2. If, with regard to the precautionary designation statement contained in Box No. V, the applicant wishes to exclude any State(s) from the scope of that statement:	***in such case, write "Designation(s) excluded from precautionary designation statement" and indicate the name or two-letter code of each state so excluded.***
3. If the applicant claims, in respect of any designated Office, the benefits of provisions of the national law concerning non-prejudicial disclosures or exceptions to lack of novelty:	***in such case, write "Statement Concerning Non-Prejudicial Disclosures or Exceptions to Lack of Novelty" and furnish that statement below.***

Continuation of Box IV

ARMITAGE, IAN M.
BRASNETT, ADRIAN H.
CALDERBANK, T. ROGER
CARTER, STEPHEN
COLEIRO, RAYMOND
CRIPPS, JOANNA E
FORD, MICHAEL F.
HACKNEY, NIGEL J.
HARRISON, DAVID C.
KIDDLE, SIMON J.
KREMER, SIMON M.
LYONS, JUNE, M.
NICHOLLS, KATHRYN M.
PAGET, HUGH C.E.
SANDERSON, MICHAEL J.
STONER, G. PATRICK
STUART, IAN
.WALTON, SEÁN M
WATSON, ROBERT J.

Continuation of Box No. ?

Box No. VI PRIORITY CLAIM		☐ Further priority claims are indicated in the Supplemental Box		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is: national application: country	regional application:* regional Office	international application: receiving Office
item (1) 28/05/99 28 MAY 1999 ▲	9912563.5	GB		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) *(only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office)* identified above as item(s): (1)

** Where the earlier application is an ARIPO application, it is mandatory to indicate in the supplemental box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.*

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

▲ Added ▲▲ Deleted RO/GB

Choice of International Searching Authority (ISA) *(If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):*

ISA /

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date *(day/month/year)* Number Country *(or regional Office)*

Box No. VIII CHECK LIST; LANGUAGE OF FILING

This international application contains the following number of sheets		
request	:5	
description (excluding sequence listing part)	:99	
claims	:10	
abstract	:1	
drawings	:4	
sequence listing part of description	~~:74~~ ▲▲	73 ▲
Total number of sheets	~~:193~~ ▲▲	192 ▲

This international application is **accompanied by** the item(s) marked below:

1. ☐ fee calculation sheet
2. ☐ separate signed power of attorney
3. ☒ copy of general power of attorney; reference number, if any: (x 3)
4. ☐ statement explaining lack of signature
5. ☒ priority document(s) *identified in Box No. VI as item*(s):
6. ☐ translation of international application into (language):
7. ☒ separate indications concerning deposited microorganisms or other biological matter
8. ☐ nucleotide and/or amino acid sequence listing in computer readable form
9. ☒ other *(specify): 23/77*

Figure of the drawings which should accompany the abstract: 1

Language of filing of the international application: ENGLISH

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

STUART, IAN
APPOINTED AGENT

For receiving Office use only

1. Date of actual receipt of the purported international application: 30 MAY 2000 30.05.2000		2. Drawings: ☑ received: ☐ not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA/	6. ☑ Transmittal of search copy delayed until search fee is paid	

For International Bureau use only

Date of receipt of the record copy by the International Bureau: 21 JUNE 2000 (21.06.00)

PCT 30 AUG 2001
WIPO PCT

PATENT COOPERATION TREATY

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference	FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
IS/BP5858469		

International application No.	International filing date *(day/month/year)*	Priority date *(day/month/year)*
PCT/GB00/02072	30/05/2000	28/05/1999

International Patent Classification (IPC) or national classification and IPC
C12N15/52

Applicant
BIOTICA TECHNOLOGY LIMITED et al.

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 9 sheets, including this cover sheet.

 ☐ This report is also accompanied by ANNEXES, i.e. sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

 These annexes consist of a total of sheets.

3. This report contains indications relating to the following items:

 - I ☒ Basis of the report
 - II ☒ Priority
 - III ☒ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
 - IV ☒ Lack of unity of invention
 - V ☐ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations suporting such statement
 - VI ☒ Certain documents cited
 - VII ☐ Certain defects in the international application
 - VIII ☒ Certain observations on the international application

Date of submission of the demand	Date of completion of this report
27/12/2000	28.08.2001

Name and mailing address of the international preliminary examining authority:

European Patent Office
D-80298 Munich
Tel. +49 89 2399 - 0 Tx: 523656 epmu d
Fax: +49 89 2399 - 4465

Authorized officer

Roscoe, R

Telephone No. +49 89 2399 2554

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB00/02072

I. Basis of the report

1. With regard to the **elements** of the international application *(Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17))*:
Description, pages:

1-173 as originally filed

Claims, No.:

1-45 as originally filed

Drawings, sheets:

1/4-4/4 as originally filed

Sequence listing part of the description, pages:

1-80, filed with the letter of 29.09.00

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language: , which is:

- ☐ the language of a translation furnished for the purposes of the international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of a translation furnished for the purposes of international preliminary examination (under Rule 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☒ furnished subsequently to this Authority in written form.
- ☒ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. The amendments have resulted in the cancellation of:

☐ the description, pages:

☐ the claims, Nos.:

☐ the drawings, sheets:

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed (Rule 70.2(c)):

 (Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.)

6. Additional observations, if necessary:

II. Priority

1. ☐ This report has been established as if no priority had been claimed due to the failure to furnish within the prescribed time limit the requested:

 ☐ copy of the earlier application whose priority has been claimed.

 ☐ translation of the earlier application whose priority has been claimed.

2. ☐ This report has been established as if no priority had been claimed due to the fact that the priority claim has been found invalid.

 Thus for the purposes of this report, the international filing date indicated above is considered to be the relevant date.

3. Additional observations, if necessary:
 see separate sheet

III. Non-establishment of opinion with regard to novelty, inventive step and industrial applicability

1. The questions whether the claimed invention appears to be novel, to involve an inventive step (to be non-obvious), or to be industrially applicable have not been examined in respect of:

 ☒ the entire international application.

 ☐ claims Nos. .

because:

☐ the said international application, or the said claims Nos. relate to the following subject matter which does not require an international preliminary examination (*specify*):

☒ the description, claims or drawings (*indicate particular elements below*) or said claims Nos. 1-45 are so unclear that no meaningful opinion could be formed (*specify*):
see separate sheet

☐ the claims, or said claims Nos. are so inadequately supported by the description that no meaningful opinion could be formed.

☒ no international search report has been established for the said claims Nos. 1, 8-12, 14, 43, 44 (all partially).

2. A meaningful international preliminary examination cannot be carried out due to the failure of the nucleotide and/or amino acid sequence listing to comply with the standard provided for in Annex C of the Administrative Instructions:

☐ the written form has not been furnished or does not comply with the standard.

☐ the computer readable form has not been furnished or does not comply with the standard.

IV. Lack of unity of invention

1. In response to the invitation to restrict or pay additional fees the applicant has:

☐ restricted the claims.

☐ paid additional fees.

☐ paid additional fees under protest.

☐ neither restricted nor paid additional fees.

2. ☐ This Authority found that the requirement of unity of invention is not complied and chose, according to Rule 68.1, not to invite the applicant to restrict or pay additional fees.

3. This Authority considers that the requirement of unity of invention in accordance with Rules 13.1, 13.2 and 13.3 is

☐ complied with.

☐ not complied with for the following reasons:

4. Consequently, the following parts of the international application were the subject of international preliminary examination in establishing this report:

☐ all parts.

☒ the parts relating to claims Nos. 1, 8-12, 14, 43, 44 (all partially); 2-7, 13, 15-42, 45 (all completely).

VI. Certain documents cited

1. Certain published documents (Rule 70.10)

and / or

2. Non-written disclosures (Rule 70.9)

see separate she t

VIII. Certain observations on the international application

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:
see separate sheet

The documents mentioned in the present International Preliminary Examination Report are numbered as in the search report, i.e. D1 corresponds to the first document of the search report etc.

II. Priority

As the priority document was not available to the IPEA, this opinion / report has been established based upon the assumption that priority was valid. Should this later not turn out to be the case, then D10 may become relevant to the assessment of the present claims.

III. No Opinion

No opinion could be expressed for claims insofar as they relate to unsearched subject-matter (see section IV). Hence, no opinion has been formulated for claims 1, 8-12, 14, 43, 44 (all partially).

Further, the present set of claims as a whole is considered unclear, since the claimed subject-matter is not clearly defined. The reasons for this are set out in section VIII. Hence, no opinion is expressed for any of the present claims.

IV. Lack of Unity

The present application lacks unity and can be divided in to 14 different invention groups as set out in the Annex to the International Search Report. The reasoning for the lack of unity was set out in the invitation to pay additional fees. The International Preliminary Examination Authority agrees with this reasoning. Since applicant failed to pay additional Search Fees, only invention group I can be subject to Preliminary Examination.

Preliminary statement on Novelty, Inventive Step and Industrial Applicability

For the benefit of the applicant, the authorized authority has decided to provide a basic indication of the novelty, inventive step and industrial applicability of

applicants monensin gene cluster. Individual claims will however not be addressed due to the lack of clarity of the claims.

- **Novelty (Art.33(2) PCT)**

None of the cited prior art documents disclose the monensin gene cluster.

- **Inventive Step (Art.33(3) PCT)**

The motivation to isolate the monensin gene cluster is evidenced by prior art attempts using actI probes (e.g. D1 and D2). Data were however inconclusive although complementation data from D1 could be taken to demonstrate partial isolation of the cluster. Further, in view of the conflicting data, D2 (last paragraph) suggests that in the context of the search for monensin, one should test whether eryA-homologous DNA is found in S.cinnamonensis. D6 also suggests that probes based on ery genes should be used for the isolation of modular PKSs (p.2470, col.2). It is indeed the methodology suggested in D2 and D6 which applicant used to isolate the monensin gene cluster. Hence, applicant has merely put the teaching of D2 or D6 into practice. Given the monensin gene cluster, the uses thereof, e.g. for the construction of hybrid PKSs is routine (has been practiced on equivalent PKS enzymes). Hence, the isolation and uses of the monensin gene cluster which have been searched are not considered inventive.

- **Industrial Applicability (Art.33(4) PCT)**

The present claims appear to have industrial applicability.

VI. **Certain documents**

In accordance with Rule 70.10, PCT, applicants attention is drawn to the following document(s):

WO-A-00/00500 (Publication date, 06.01.00; Priority date, 29.06.98; Filing date, 29.06.99)

VIII. **Certain observations**

- **Clarity (Art.6 PCT)**

The requirement that the claims should be clear does not only apply to individual claims but applies to the claims as a whole. The problems listed below demonstrate how extensive the lack of clarity is in the present claims. Due to this lack of clarity, no examination of the present set of claims can be reasonably carried out.

Claim 1 - "at least part of" - size ?

Claim 2 - "monensin gene cluster" - define by technical features / "variant" - how much variation ?

Claim 3 - "part of" / "allele, mutation or other variant" - define each term

Claim 4 - "at least part" / "monBI,..." - arbitrary definitions, need to be defined by reference to sequences.

Claim 6 - "as set out in the appended sequence data" - show where

Claim 11 - "corresponding polypeptide" - DNA comes from defined in open-ended manner so need to define polypeptide more clearly.

Claim 16 - "binds specifically" - under which conditions ?

Claim 18 - "gene responsible for levels of activity" - definition by result to be achieved. Same applies to subsequent manipulation.

Claims 21-23 - preferences should be defined in dependent claims

Claim 36 - product by process definition. Not acceptable, since combination of known modules of PKSs could arrive at same compounds as can be produced by the broadly defined synthase of claim 35. Major novelty problem.

The above problems are found in numerous claims, yet only the first incidence of the problem has generally been referred to. Claims 1-8, 11, 16, 18-27, 30-32, 34, 36, 39-41 and 43 all contain clarity problems of the types listed above.

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

COMMUNICATION OF
INTERNATIONAL APPLICATIONS

(PCT Article 20)

To:

Commissioner
US Department of Commerce
United States Patent and Trademark
Office, PCT
2011 South Clark Place Room
CP2/5C24
Arlington, VA 22202
ETATS-UNIS D'AMERIQUE

in its capacity as designated Office

Date of mailing:
15 August 2001 (15.08.01)

The International Bureau transmits herewith copies of the international applications having the following international application numbers and international publication numbers:

International application no.:	International publication no.:
PCT/GB00/02072	

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer:

J. Zahra

Telephone No.: (41-22) 338.83.38

Copy for the elected Office (EO/US)

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

COMMUNICATION IN CASES FOR WHICH NO OTHER FORM IS APPLICABLE

To:

STUART, Ian
Mewburn Ellis
York House
23 Kingsway
London WC2B 6HP
ROYAUME-UNI

Date of mailing (*day/month/year*) 14 August 2001 (14.08.01)	
Applicant's or agent's file reference IS/BP5858469	**REPLY DUE** see paragraph 1 below
International application No. PCT/GB00/02072	International filing date (*day/month/year*) 30 May 2000 (30.05.00)
Applicant BIOTICA TECHNOLOGY LIMITED	

1. ☐ REPLY DUE within _____ months/days from the above date of mailing

☐ NO REPLY DUE, however, see below

☒ IMPORTANT COMMUNICATION

☐ INFORMATION ONLY

2. COMMUNICATION:

The International Bureau regrets to inform the applicant that, due to a clerical error, the above identified international application has not been published promptly after the expiration of 18 months from the priority date, as provided in PCT Article 21(2)(a).

International publication will now take place on 20 September 2001 (20.09.01).

Meanwhile, the International Bureau will communicate a copy of the international application to each designated Office, in accordance with PCT Article 20.

A copy of this notification has been sent to the receiving Office RO/GB and all designated Offices.

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No. (41-22) 740.14.35

Authorized officer
R. Chrem

Telephone No. (41-22) 338.83.38

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

To:

Commissioner
US Department of Commerce
United States Patent and Trademark
Office, PCT
2011 South Clark Place Room
CP2/5C24
Arlington, VA 22202
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing:	
20 September 2001 (20.09.01)	
International application No.: PCT/GB00/02072	Applicant's or agent's file reference: IS/BP5858469
International filing date: 30 May 2000 (30.05.00)	Priority date: 28 May 1999 (28.05.99)
Applicant: LEADLAY, Peter, Francis et al	

1. The designated Office is hereby notified of its election made:

[X] in the demand filed with the International preliminary Examining Authority on:

27 December 2000 (27.12.00)

[] in a notice effecting later election filed with the International Bureau on:

2. The election [X] was

[] was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer:

J. Zahra

Telephone No.: (41-22) 338.83.38